

# A3LA-RM / A3LA-RM-MIL User Guide

Version D

May 31, 2023



## LEGAL DISCLAIMER AND CONDITION OF USE

This document contains information for the A3LA-RM and A3LA-RM-MIL modems and accompanying accessories (“Product”), which is provided “as is.” Reasonable effort has been made to make the information in this document reliable and consistent with specifications, test measurements and other information. However, NAL Research Corporation and its affiliated companies, directors, officers, employees, agents, trustees or consultants (“NAL Research”) assume no responsibility for any typographical, technical, content or other inaccuracies in this document. NAL Research reserves the right in its sole discretion and without notice to you to change Product specifications and materials and/or revise this document or withdraw it at any time. User assumes the full risk of using the Product specifications and any other information provided.

NAL Research makes no representations, guarantees, conditions or warranties, either express or implied, including without limitation, any implied representations, guarantees, conditions or warranties of merchantability and fitness for a particular purpose, non-infringement, satisfactory quality, non-interference, accuracy of informational content, or arising from a course of dealing, law, usage, or trade practice, use, or related to the performance or nonperformance of any products, accessories, facilities or services or information except as expressly stated in this guide and/or the Product and/or satellite service documentation. Any other standards of performance, guarantees, conditions and warranties are hereby expressly excluded and disclaimed to the fullest extent permitted by the law. This disclaimer and exclusion shall apply even if the express limited warranty contained in this guide or such documentation fails of its essential purpose.

In no event shall NAL Research be liable, whether in contract or tort or any other legal theory, including without limitation strict liability, gross negligence or negligence, for any damages in excess of the purchase price of the Product, including any direct, indirect, incidental, special or consequential damages of any kind, or loss of revenue or profits, loss of business, loss of privacy, loss of use, loss of time or inconvenience, loss of information or data, software or applications or other financial loss caused by the Product (including hardware, software and/or firmware) and/or the Iridium satellite, or arising out of or in connection with the ability or inability to use the Product (including hardware, software and/or firmware) and/or the Iridium satellite to the fullest extent these damages may be disclaimed by law and whether advised of the possibilities of such damages. NAL Research is not liable for any claim made by a third party or made by you for a third party.

## REVISION HISTORY

Revision	Date	Description
1.3	8/2/16	Initial version
A	5/20/20	Added revision history Updated address Updated document number Added AT^VOLB command
A.1	06/09/2021	Updated to new template; proofread.
B	04/19/2022	Formal release
C	03/31/2023	Added A3LA-RM-MIL
D	05/31/2023	Changed "+5.0 V to +32 V" to "+6.0 V to +32 V". Added antenna and Power/Data Cable photos (section 2)

## REFERENCE DOCUMENTS

The latest revisions of the NAL documents are available from the NAL Research website at

<https://www.nalresearch.com/>.

Reference	Title	Revision/Date
[1]	A3LA-RM Product Information	05/03/2019
[2]	Getting Started With Model A3LA-RM (TN2012-21-V1.1)	04/08/2013
[3]	SatTerm Software Manual (TN451-94000-001A)	Version A, 06/01/2022
[4]	Additional Information on DirectIP SBD (TN2007-637-V1.0)	02/01/2007
[5]	Additional Information on SBD (AN2012-04-V4.0)	02/01/2012

# TABLE OF CONTENTS

<b>1</b>	<b>Introduction</b> .....	<b>17</b>
<b>2</b>	<b>Multi-interface Connector</b> .....	<b>19</b>
2.1	RS-232 Data Interface (Standard 9-Wire Configuration) .....	20
2.2	RS-232 Data Interface (3-Wire Configuration) .....	21
2.3	DC Power Input .....	22
2.4	Power On/Off Control .....	23
2.5	Audio Interface .....	23
2.6	Digital Peripheral Link (DPL).....	24
<b>3</b>	<b>Antenna</b> .....	<b>25</b>
<b>4</b>	<b>SIM Card Interface</b> .....	<b>27</b>
<b>5</b>	<b>LED Display</b> .....	<b>28</b>
<b>6</b>	<b>Configuration Settings</b> .....	<b>29</b>
<b>7</b>	<b>Modes of Operation</b> .....	<b>30</b>
<b>8</b>	<b>AES-256 Bit Encryption</b> .....	<b>31</b>
<b>9</b>	<b>Self-monitoring to Prevent Modem Lockup</b> .....	<b>32</b>
<b>10</b>	<b>Mounting Recommendations</b> .....	<b>33</b>
<b>11</b>	<b>Technical Support</b> .....	<b>34</b>
<b>12</b>	<b>Appendix A: AT Interface</b> .....	<b>35</b>
12.1	Command Types .....	35
12.2	Basic Commands .....	35
12.3	Extended Commands .....	35
12.4	Command and Response Characters .....	37
12.5	Command Entry .....	37
12.6	Command Responses.....	38
12.7	Hardware Failure Reporting.....	39
	<b>Appendix B: AT Command Set Description</b> .....	<b>40</b>
	(Iridium Radio Link Protocol) .....	40
B.1	AT – Attention Code.....	40
B.2	A/ – Repeat Last Command .....	40
B.3	+++ – Escape Sequence.....	40
B.4	En – Echo.....	40

B.5	On – Online .....	40
B.6	Qn – Quiet Mode .....	40
B.7	Vn – Verbose Mode .....	41
B.8	Wn – Error Correction Message Control .....	41
B.9	Zn – Soft Reset .....	41
B.10	&Cn – DCD Option .....	41
B.11	&Dn – DTR Option.....	41
B.12	&Fn – Restore Factory Settings.....	42
B.13	&Kn – Flow Control .....	42
B.14	&Mn – Asynchronous/Synchronous Mode.....	42
B.15	&Qn – Sync/Async Mode .....	42
B.16	&Sn – DSR Override .....	43
B.17	&V – View Active and Stored Configuration.....	43
B.18	&Wn – Store Active Configuration .....	43
B.19	&Yn – Designate Default Reset Profile .....	43
B.20	\Kn – Control Break.....	43
B.21	%R – Display Registers .....	44
B.22	*Pn – Power .....	44
B.23	+CBST – Select Bearer Service Type.....	44
B.24	+CGMI – Manufacturer Identification .....	45
B.25	+CGMM – Model Identification .....	45
B.26	+CGMR – Revision.....	45
B.27	+CGSN – Serial Number .....	45
B.28	+CMEE – Report Mobile Equipment Error .....	45
B.29	+CPAS – Modem Activity Status .....	47
B.30	+CR – Service Reporting Control.....	48
B.31	+DS – Set Data Compression Function .....	48
B.32	+DR – Data Compression Report Level.....	49
B.33	+CEER – Extended Error Report.....	50
B.34	+CHUP – Hangup call .....	50
B.35	+CMGD – Delete SMS Message .....	51
B.36	+CMGF – SMS Message Format.....	53

B.37 +CMGL – List SMS Messages.....	54
B.38 +CMGR – Read SMS Message .....	55
B.39 +CMGS – Send SMS Message.....	56
B.40 +CMGW – Write SMS Message To Memory.....	56
B.41 +CMOD – Call Mode.....	57
B.42 +CNMI – New SMS Message Indications to DTE.....	57
B.43 +COPS – Operator Select .....	59
B.44 +CPBF – Find Phonebook Entries .....	60
B.45 +CPBR – Read Phonebook Entries .....	61
B.46 +CPBS – Select Phonebook Storage .....	61
B.47 +CPBW – Write Phonebook Entry.....	62
B.48 +CPIN – Enter PIN.....	63
B.49 +CPMS – Select Preferred SMS Message Storage .....	64
B.50 +CREG – Network Registration .....	65
B.51 +CSCA – SMS Service Center Address.....	66
B.52 +CSCB – Select Cell Broadcast Message Types .....	66
B.53 +CSCS – Select TE Character Set .....	67
B.54 +CSMS – Select SMS Message Service .....	67
B.55 +CSTA – Select Type of Address.....	68
B.56 +GMI – Manufacturer Identification.....	68
B.57 +GMM – Model Identification .....	68
B.58 +GMR – Revision .....	69
B.59 +GSN – Serial Number.....	69
B.60 +GCAP – General Capabilities .....	69
B.60.1A – Answer.....	69
B.62 D – Dial .....	69
B.62.1 D> – Direct Dial From Phonebook .....	70
B.63 Hn – Hangup.....	70
B.64 S0=n – Auto-Answer .....	71
B.65 Xn – Extended Result Codes .....	71
B.66 +CLVL – Volume Level Control .....	71
B.67 +CMUT – Mute Control.....	72

B.68	+CRC – Cellular Result Codes .....	73
B.69	+CVHU – Voice Hangup Control.....	73
B.70	+CCLK – Real-Time Clock.....	74
B.71	–MSVTS – DTMF Generation in Voice Call.....	74
B.72	–MSVTR – DTMF Received in Voice Call .....	75
B.73	–MSVLS – Local DTMF Feedback Selection.....	76
B.74	–MSSTM – Request System Time .....	76
B.75	–MSGEO – Request Geolocation .....	77
B.76	+CCFC – Call Forward Service.....	78
B.77	+CLCC – Request Current Call Status .....	80
B.78	+CNUM – Read MSISDN Numbers .....	80
B.79	+CSSSC – Supplementary Services Shortcode .....	80
B.80	+WIRLP – Iridium Radio Link Protocol .....	81
B.81	+WFRNG – Force IRLP Renegotiation .....	83
B.82	+WTM – IRLP Test Mode.....	83
B.83	+WDLDM – IRLP Dynamic Link Delay Measurement.....	84
B.84	+WDAV – Register or Deregister an RS-232 DAV Data Peripheral .....	84
B.85	+SBDWB – Short Burst Data: Write Binary Data.....	85
B.86	+SBDRB – Short Burst Data: Read Binary Data .....	86
B.87	+SBDRT – Short Burst Data: Read Text Message .....	86
B.88	+SBDD – Short Burst Data: Clear SBD Message Buffer(s).....	87
B.89	+SBDC – Short Burst Data: Clear SBD MOMSN.....	88
B.90	+SBDS – Short Burst Data: Status.....	88
B.91	+SBDTC – Short Burst Data: Transfer MO Buffer to MT Buffer .....	89
B.92	+CAR – Audio Output Control .....	89
B.93	In – Identification .....	89
B.94	+CIER – Indicator Event Reporting.....	90
B.95	+CRIS – Ring Indication Status .....	92
B.96	+CSQ[F] – Signal Quality.....	92
B.97	+CULK – Unlock.....	93
B.98	+CVMI – Voicemail Indication.....	94
B.99	+CICCID – Read ICC ID from SIM .....	95

B.100	+CLIP – Calling Line Identification Presentation .....	95
B.101	+CLIR – Calling Line Identification Restriction.....	96
B.102	+IPR – Fixed DTE Rate.....	97
B.103	+SBDWT – Short Burst Data: Write a Text Message .....	98
B.104	+SBDEET – Short Burst Data: Detach.....	99
B.105	+SBDI – Short Burst Data: Initiate an SBD Session.....	100
B.106	+SBDIX[A] – Short Burst Data: Initiate an SBD Session Extended .....	101
B.107	+SBDDSC – Short Burst Data: Delivery Short Code .....	104
B.108	+SBDMTA – Short Burst Data: Mobile-Terminated Alert.....	105
B.109	+SBDREG – Short Burst Data: Network Registration .....	105
B.110	+SBDAREG – Short Burst Data: Automatic Registration .....	108
B.111	+SBDSX – Short Burst Data: Status Extended.....	110
B.112	+CCWA – Call Waiting service .....	111
B.113	+CLCK – Facility Lock .....	113
B.114	+CPWD – Change Password .....	116
B.115	+CSDT – Sidetone .....	117
B.116	+CDSI – Report SMS status .....	117
B.117	+GPSSTA – Configure GPS Status .....	119
B.118	+PA – GPS: List of NMEA Message Formats.....	119
B.119	+PLOC – GPS: Display Position to 5 <sup>th</sup> Decimal Place.....	120
B.120	^AA – Auto Answer Display.....	120
B.121	^AD – Auto Dial.....	120
B.122	^ADR – Auto Dial Retry .....	121
B.123	^CCOP – Change Crypto Officer Password (Encryption).....	121
B.124	^CMGEC – Clear SMS Encrypted Storage.....	121
B.125	^FFW – Flash Firmware.....	122
B.126	^KD – Key for Decryption (Encryption) .....	122
B.127	^KE – Key for Encryption (Encryption) .....	122
B.128	^KZ – Key Zeroization (Encryption) .....	123
B.129	^MODRSTn – Modem Reset Information Message Displayed .....	123
B.130	^MPTDC- Modem Power Toggle Data Connection .....	123
B.131	^MPTFP- Modem Power Toggle Forced Power-cycle.....	124

B.132	^MPTFR- Modem Power Toggle Forced Registration .....	125
B.133	^MPTNC- Modem Power Toggle Not in Data Connection .....	125
B.134	^MSB – Motion Sensor Begin .....	126
B.135	^PKTS – Use Packets .....	126
B.136	^PKTST – Packet Send Timer.....	127
B.137	^PKTRT – Packet Resend Timer .....	127
B.138	^PKTTH – Packet Send Threshold .....	128
B.139	^RESETMODEMTG – Reset Modem Toggle .....	128
B.140	^RESETMODEMVF – Reset Modem Verify .....	128
B.141	^RLE – Use Run Length Encoding.....	129
B.142	^SE – Configure Streaming Encryption .....	129
B.143	^SMSD – SMS Delete .....	130
B.144	^SMSE – SMS Erase.....	130
B.145	^SMSR – SMS Read .....	130
B.146	^SSI – Send Start-Up Information .....	131
B.147	^STR – Self Test Run (Encryption).....	131
B.148	^UE – Use Encryption .....	131
B.149	^VOLB – Volume Boost .....	132
<b>Appendix C: S-Register Definitions .....</b>		<b>133</b>
C.1	S-Register Commands.....	133
C.1.1	Sr – Direct S-Register Reference.....	133
C.1.2	Sr? – Direct S-Register Read .....	133
C.1.3	Sr=n – Direct S-Register Write.....	133
C.1.4	Referenced S-Register Read .....	133
C.1.5	=n – Referenced S-Register Write .....	133
C.2	Standard S-Registers.....	134
C.3	Iridium Specific S-Register Extensions .....	137
<b>Appendix D: Summary of Result Codes .....</b>		<b>141</b>
<b>Appendix E: Informative Examples.....</b>		<b>145</b>
E.1	Unit Identification .....	145
E.2	Setting the Default Configuration.....	146
E.3	Power-on to Sending an SBD Message.....	146

E.4	SBD Automatic Notification Registration.....	147
E.5	SBD Automatic Notification Message Reception.....	148
E.6	SBD Automatic Notification Automatic Registration.....	149
E.7	Originating a Data Call .....	149
E.8	Answering a Data Call .....	150
E.9	Disconnecting a Data Call .....	150
E.10	Coordination of +CLCC and +CPAS responses.....	151
<b>Appendix F: Power Consumption .....</b>		<b>153</b>
<b>Appendix G: The Iridium Network.....</b>		<b>160</b>
G.1	Iridium Network Data Capabilities.....	161
G.2	Dial-up Data Service.....	162
G.3	Direct Internet Connection .....	164
G.4	Short Burst Data.....	165
G.5	Short Messaging Service .....	165
G.6	RUDICS .....	166
G.7	Iridium Geolocation .....	166
<b>Appendix H: Standards Compliance .....</b>		<b>167</b>
<b>Appendix I: MIL-STD-810G Certification .....</b>		<b>168</b>
<b>Appendix J: Export Compliance.....</b>		<b>169</b>
<b>Appendix K: Design Specifications.....</b>		<b>170</b>
K.1	Mechanical Specifications.....	170
K.2	RF Specifications .....	170
K.3	Electrical Specifications.....	170
K.4	Environmental Specifications .....	171
K.5	Data I/O Specifications.....	171
K.6	Related Hardware .....	171
<b>Appendix L: Mechanical Drawing .....</b>		<b>172</b>

## TABLE OF FIGURES

Figure 1: Iridium Satellite Modem A3LA-RM .....	18
Figure 1 HRC-24-7R Power/Data Cable.....	19
Figure 2: Power Input Setting for the A3LA-RM .....	23
Figure 3: A3LA-RM Connected to a DPL Handset via the HRC-24-8R.....	24
Figure 4: SYN7391-C Antenna with Cable.....	25
Figure 5: Location of the SIM Reader .....	27
Figure 6: Iridium Satellite Modem A3LA-RM .....	28
Figure 7: Average Current Drawn During Standby .....	154
Figure 8: Average Power Consumption During Standby .....	154
Figure 9: Average Current Drawn During Standby with DPL Handset.....	155
Figure 10: Average Power Consumption During Standby with DPL Handset.....	155
Figure 11: Average Current Drawn During a Data Switch Call.....	156
Figure 12: Average Power Consumption During a Data Switch Call.....	156
Figure 13: Average Current Drawn During an SBD Transmission .....	157
Figure 14: Average Power Consumption During an SBD Transmission .....	157
Figure 15: Average Current Drawn During an SMS Transmission .....	158
Figure 16: Average Power Consumption During an SMS Transmission .....	158
Figure 17: Average Current Drawn During a Voice Call Using DPL Handset .....	159
Figure 18: Average Power Consumption During a Voice Call Using DPL Handset .....	159
Figure 19: Iridium Network Major Components .....	160
Figure 20: Iridium Network Data Capabilities.....	162
Figure 21: PSTN Dial-up Connectivity .....	163
Figure 22: Iridium Dial-up Data Service .....	164
Figure 23: Mil-STD-810G Certification .....	168
Figure 24: A3LA-RM Mechanical Drawing .....	172

## TABLE OF TABLES

Table 1: Pin Assignment for the Multi-Interface Connector .....	19
Table 2: General RF Parameters .....	25
Table 3: Custom Antenna Specifications .....	26
Table 4: Numeric and Verbose Mode Formats.....	39
Table 5: Standard S-Registers .....	134
Table 6: Iridium Specific S-Register Extensions .....	137
Table 7: V.25ter/Hayes Result Codes.....	141
Table 8: GSM 7.07 Result Codes .....	143
Table 9: GSM 7.05 Result Codes .....	143
Table 10: Iridium Specific Result Codes .....	144
Table 11: Unit Identification .....	145
Table 12: Default Configuration.....	146
Table 13: Sending an SBD Message .....	146
Table 14: SBD Automatic Notification Registration.....	147
Table 15: SBD Automatic Notification Message Reception.....	148
Table 16: SBD Automatic Notification Automatic Registration .....	149
Table 17: Originating a Data Call.....	149
Table 18: Answering a Data Call .....	150
Table 19: Disconnecting a Data Call.....	150
Table 20: Coordination of +CLCC and +CPAS Responses.....	151

## ACRONYM LIST

3GPP .....	3rd Generation Partnership Project
AES .....	Advanced Encryption Standard
ASCII .....	American Standard Code for Information Interchange
AT .....	Two-letter sequence starting a string of modem commands. The AT is intended to get the modem's <u>attention</u> prior to executing a command.
BIS .....	Bureau of Industry and Security
CTS.....	Clear to send
DAV .....	Data After Voice
DC.....	Direct current
DCD .....	Data carrier detect
DCE.....	Data circuit-terminating equipment
DoD .....	Department of Defense
DPL .....	Digital Peripheral Link
DSN.....	Defense Switch Network
D-sub .....	D-subminiature
DSR .....	Data set ready
DTE .....	Data terminal equipment
DTMF.....	Dual-tone multi-frequency
DTR.....	Data terminal ready
EAR .....	Export Administration Regulations
EMI .....	Electromagnetic interference
EMSS .....	Enhanced Mobile Satellite Services
ETSI.....	European Telecommunications Standards Institute
FCC .....	Federal Communications Commission
FDMA .....	Frequency-division multiple access
GMT.....	Greenwich Mean Time
GND.....	Ground
GPRS.....	General Packet Radio Service
GPS .....	Global Positioning System

---

GSM.....	Global System for Mobile Communications
IMEI .....	International Mobile Equipment Identification
I/O .....	Input/output
IP .....	Internet Protocol
IP67 .....	Ingress Protection Code 67
ISP.....	Internet Service Provider
ISU .....	Iridium subscriber unit (modems, phones, trackers)
LAN .....	Local area network
LBT.....	L-band transceiver
LCD .....	Liquid-crystal display
LED .....	Light-emitting diode
LEO .....	low-earth orbit
NIPRNet.....	Non-classified Internet Protocol Router Network
NMEA .....	National Marine Electronics Association
NOC .....	Network Operation Center
OFAC.....	Office of Foreign Asset Controls
PCM.....	Pulse-code modulation
PIN.....	Personal identification number
PPP .....	Point-to-point protocol
PSTN .....	Public switched telephone network
RF.....	Radio frequency
RH.....	Relative humidity
RHCP.....	Right-handed circular polarization
RI .....	Ring indicator
RTS.....	Request to send
RUDICS .....	Router-based unrestricted digital internetworking connectivity solution
SBD .....	Short-burst data
SIM .....	Subscriber identification module
SMS .....	Short message service
TBR .....	Time Between Reports

TCP .....Transmission Control Protocol  
TDD.....Time-division duplex  
TDMA .....Time-division multiple access  
TNC.....Threaded Neill–Concelman  
TON .....Type of number  
UART.....Universal asynchronous receiver-transmitter  
VDC.....Volts (Direct Current)  
VSWR.....Voltage standing wave ratio

# 1 INTRODUCTION


This user guide provides you with information on the operational features, and electrical and mechanical interfaces of the A3LA-RM. The A3LA-RM is a satellite modem comprising a 9523 L-Band Transceiver (LBT) with an extended input voltage range. The A3LA-RM-MIL is a variation of the original A3LA-RM. It functions the same as the A3LA-RM but is also certified to the environmental MIL-STD-810G standards and is IP67 rated.

**NOTE:** Unless otherwise noted, all references to the A3LA-RM also applies to the A3LA-RM-MIL.

The A3LA-RM has an internal microcontroller programmed to monitor the modem's connectivity status to prevent hardware lockup. It is designed to transmit either AES 256-bit encrypted or unencrypted data via the Iridium satellite network. Similar to a standard landline modem, the A3LA-RM can be controlled by any data terminal equipment (DTE) capable of sending standard AT commands via an RS-232 serial port. A DTE can be a desktop computer, a laptop computer, a smartphone, or even a microcontroller. The A3LA-RM is functionally compatible with models 9522B, A3LA-R, and A3LA-RS. It is approximately 60% smaller in volume and 50% lighter than the 9522B. Model A3LA-RM-MIL is an A3LA-RM that has been certified to MIL-STD-810G standards and IP67 rating.

Services supported include:

- Dial-up data switch
- Direct Internet connection (or NIPRNet connection)
- Direct Internet connection using Apollo Emulator (only for DoD EMSS gateway)
- Short Message Service (SMS)
- Short Burst Data (SBD)
- Router-based Unrestricted Digital Internetworking Connectivity Solution (RUDICS)
- Voice when combined with the Digital Peripheral Link (DPL) audio handset



**Figure 1: Iridium Satellite Modem A3LA-RM**

**Important:** Do not disassemble the A3LA-RM for repair or services. The warranty is voided if the A3LA-RM is disassembled. Return it to NAL Research for any services.

## 2 MULTI-INTERFACE CONNECTOR

The multi-interface connector on the A3LA-RM-MIL device is a male 25-pin miniature D-sub type that includes five (5) interfaces—RS-232, DC input power, ON/OFF control line, analog audio, and DPL. The multi-interface connector pin assignments are summarized in **Table 1**, which is ‘pin-to-pin’ the same as model A3LA-R, A3LA-XM, and A3LA-X. Power and data from an external device is accomplished via a cable connection. NAL recommends the HRC-24-7R Cable (see **Figure 1**).



*Figure 2 HRC-24-7R Power/Data Cable*

**Table 1: Pin Assignment for the Multi-Interface Connector**

Pin #	Signal	Description	Interface
1	EXT_ON_OFF	Power on/off control input	DC Power
2	+12VDC	Output voltage to power the DPL handset	DC Power
3	EXT_GND	External GND input	DC Power
4	EXT_B+	External 4.0 V – 5.5 V or 6.0 V – 32.0 V	DC Power
5	SPKR_AUD	Speaker audio output	Analog Audio
6	DA_TX	PCM digital audio output	Digital Audio
7	RI	RS-232 ring indicator	RS-232 Data
8	RTS	RS-232 request to send	RS-232 Data
9	TX	RS-232 transmit data (input)	RS-232 Data

**Table 1: Pin Assignment for the Multi-Interface Connector**

Pin #	Signal	Description	Interface
10	DCD	RS-232 data carrier detect	RS-232 Data
11	DA_FS	PCM digital audio frame sync output	Digital Audio
12	DA_CLK	PCM digital 2.048 MHz audio clock output	Digital Audio
13	RX	RS-232 receive data (output)	RS-232 Data
14	SIGNAL GND	Signal ground, 0 V signal reference and return	GND
15	MIC_AUD	Microphone audio input	Analog Audio
16	EXT_B+	External 4.0 V – 5.5V or 6.0 V – 32.0 V	DC Power
17	EXT_GND	External GND input	DC Power
18	DPL_TX	Digital Peripheral Link (DPL) data output	DPL UART
19	DTR	RS-232 data terminal ready	RS-232 Data
20	DPL_RX	Digital Peripheral Link (DPL) data input	DPL UART
21	DSR	RS-232 data set ready	RS-232 Data
22	CTS	RS-232 clear to send	RS-232 Data
23	SIGNAL GND	Signal ground, 0 V signal reference and return	GND
24	DA_RX	PCM digital audio input	Digital Audio
25	SIGNAL GND	Signal ground, 0 V signal reference and return	GND

## 2.1 RS-232 DATA INTERFACE (STANDARD 9-WIRE CONFIGURATION)

The A3LA-RM supports a standard RS-232 data interface to a DTE incorporating hardware handshaking and flow control. The RS-232 data interface comprises eight standard RS-232 data, control, and status signals, plus a ground-level signal reference, as shown in **Table 1**. This interface allows a connected DTE to utilize the A3LA-RM's modem functionality through a set of AT commands. These commands are defined in **Appendix A: AT Interface**. The factory-set baud rate is 19,200 bps and can be changed using the **+IPR** command.

Note that the Ring Indicator is used by the A3LA-RM to indicate that a mobile-terminated SBD (MT-SBD) message is queued at the gateway. Application developers can monitor this pin and apply appropriate AT commands to the A3LA-RM to retrieve the MT-SBD message.

## 2.2 RS-232 DATA INTERFACE (3-WIRE CONFIGURATION)

A 3-wire RS-232 data interface may also be implemented. Because of risk of overrun and data loss, especially at high baud rates, the 9-wire interface is the recommended implementation. Several steps must be taken to allow 3-wire configuration (i.e., only using S\_TX, S\_RX, and SIGNAL GND). These steps ensure the A3LA-RM and DTE work together without having hardware handshaking.

1. The modem's DTR line must be held high. Using the modem's input voltage is fine for this purpose BUT ONLY if the input voltage is less than 5 VDC (see important note below). Looping back the modem's DSR line to DTR line will NOT work. Leave the DSR line on the modem unconnected.
2. Disconnect the CTS, DCD, DSR, DTR, RTS, and RI lines between the DTE and modem.
3. Set **AT&Dn** to **AT&D0** to ignore the DTR input from the DTE.
4. Set **AT&Kn** to **AT&K0** for no flow control.
5. The setting can be stored on the modem permanently (until another setting overwrites it) so that it remains after a power cycle. The modem allows two profiles in which settings are stored; you can choose either as a default profile. The relevant commands are **&Wn** and **&Yn**. **&Wn** stores the present configuration in profile <n>, where <n> can be either 0 or 1. **&Yn** designates which profile is loaded after reset or power-up; <n> is either 0 or 1.
6. Address any needs of the DTE separately.

**Warning:** DO NOT use the modem's input voltage to bring the DTR line high when the input voltage is higher than 5 VDC. Supplying voltage higher than 5 VDC to the DTR line will permanently damage the A3LA-RM.

**Note:** The Iridium's Direct Internet service when using the Windows-based Apollo client requires Data Carrier Detect (DCD) to be present; hence it is incompatible with a 3-wire serial

configuration. The Direct Internet with Apollo client is available only on the EMSS DoD gateway and NOT on the commercial gateway.

## 2.3 DC POWER INPUT

The DC power input is through pin 4 & 16 (EXT\_B+) and pins 3 & 17 (EXT\_GND). Note that two pins are provided for the external DC input and two pins are also provided for the associated external ground input. This is done to distribute the current across two wires, and therefore all four pins should be utilized in the external power connection. Keep cables used to supply power to the A3LA-RM as short as possible to prevent significant voltage drop, which can cause the A3LA-RM to malfunction during a data call, an SMS session, or an SBD session. Power reset by the A3LA-RM during a call is an indication that the DC power source is unable to sustain voltage above 4.0 V at peak current demand. **Appendix F: Power Consumption** provides the electrical power profile of the A3LA-RM.

The A3LA-RM accepts either +4.0 V to +5.5 V or +6.0 V to +32 V input. The A3LA-RM is shipped with hardware set for +6.0 V to +32 V input. It can be changed to +4.0 V to +5.5 V input through an internal jumper—POWER MUST BE DISCONNECTED BEFORE RESETTING THE JUMPER. Find the jumper by removing the modem's bottom plate. With the A3LA-RM held in the position shown in **Figure 3** (DB-25 connector to the left), the A3LA-RM is set for 4.0 V to +5.5 V when the red jumper is on the middle and left pins, and it is set for +6.0 V to +32 V when the jumper is on the middle and right pins. Each pin is also labeled with 6 V and 32 V to the left and right pins, respectively.

**Note:** Remember the input voltage setting on the A3LA-RM and do not apply voltage above the maximum limit (of either 5.5 V or 32V). The A3LA-RM will be damaged beyond repair with warranty voided if this were to occur.



**Figure 3: Power Input Setting for the A3LA-RM**

**Important:** You can remove the A3LA-RM’s bottom plate to set the jumper but not for repair or services. The warranty is voided if the A3LA-RM is disassembled for any reason other than to set the jumper.

## 2.4 POWER ON/OFF CONTROL

With the EXT\_ON\_OFF pin left unconnected, the A3LA-RM automatically turns on or off when external DC power is applied or removed. Prior to turning the A3LA-RM off, issue command **AT\*P0** to ensure all memory write activity is completed. When the A3LA-RM is powered off, its internal power-on-reset circuit requires two seconds for voltages to decay. Do not reapply power until this time has elapsed. If the two-second wait time is not adhered to, the reset circuit may not operate and the A3LA-RM could be placed in a nonoperational state. The state is not permanent and can be rectified by the above procedure.

The A3LA-RM automatically turns on/off when external DC power is applied/removed via the EXT\_B+ and EXT\_GND inputs. The EXT\_ON\_OFF (pin 1) control input is used to turn a powered A3LA-RM on and off in a toggle fashion. The EXT\_ON\_OFF control input is normally “floating” (i.e., high). When it is pulled to GND level (i.e., low) for at least 270 ms and released, the A3LA-RM alternates from its current on/off state. The current drawn on the external load used to pull the A3LA-RM to GND is no more than 0.5 mA. The signal on pin 1 is considered GND when it is at 0.5 V or less.

## 2.5 AUDIO INTERFACE

The A3LA-RM supports both digital and analog audio Input/output (I/O). The digital audio is in PCM format. In such format, digital audio cannot travel far (less than one foot); this is why the

analog is chosen for the A3LA-RM audio handset. The analog audio input is a single-ended, unbalanced input with a minimum impedance of 10 k $\Omega$  to ground. The A3LA-RM accepts a maximum input level of 2.0 V peak-to-peak without signal distortion. The analog audio output is also a single-ended, unbalanced output capable of driving an impedance of 600  $\Omega$  or more to ground. The A3LA-RM delivers undistorted audio up to 2.0 V peak-to-peak.

The combined analog I/O audio interface (pins 5 and 15) and the DPL UART I/O interface (pins 18 and 20) enable an analog audio handset to be connected to the A3LA-RM. With the DPL audio handset model DPLS0401-X and DB-25 data kit model HRC-24-8R, the A3LA-RM can be used both as a data modem and a satellite phone. This setup, as shown in **Figure 4**, can be an extremely useful developmental tool because the modem status can be seen on the handset liquid-crystal display (LCD) similar to a 9555 Iridium phone.



*Figure 4: A3LA-RM Connected to a DPL Handset via the HRC-24-8R*

## 2.6 DIGITAL PERIPHERAL LINK (DPL)

The DPL interface is composed of two ports—a full duplex asynchronous serial link for control messages and a Pulse-code modulation (PCM) digital audio link for audio traffic. The protocol used on these ports is made available to application developers only on a case-by-case basis and after appropriate non-disclosure agreements and/or license agreements are executed.

### 3 ANTENNA/CONNECTOR

The A3LA-RM modem uses a single Threaded Neill–Concelman (TNC) female 50-ohm connector for both transmit and receive. Cable loss between the modem and the antenna is critical and must be kept less than 3 dB at the operating frequency of 1616.0 to 1626.5 MHz. The minimum link margin of 12 dB must also be maintained. General RF parameters are listed in the table below.

**Table 2: General RF Parameters**

Type	Description
Frequency Range	1616.0 to 1626.5 MHz
Input/Output Impedance	50 Ohms
Oscillator Stability	±1.5 ppm

NAL Research offers several types of antennas for use with the A3LA-RM modem. These antennas include the fixed mast, mobile magnetic/permanent mount, and portable auxiliary. For low cost and applications where small form factor and lightweight are required, NAL Research recommends model SYN7391-C (see **Figure 5**). If the specific application requires a custom antenna, it must meet the specifications below.



**Figure 5: SYN7391-C Antenna with Cable**

**Table 3: Custom Antenna Specifications**


Parameter	Value
Operating Temperature Range	-40°C/+85°C without loss of function
Measurement Frequency Range	1616.0 to 1626.5 MHz
VSWR	< 1.5 : 1
Maximum Gain	3 dBic
Nominal Impedance	50 Ohms
Polarization	Right-handed circular polarization (RHCP)
Basic Pattern	Omnidirectional and hemispherical

Satellite signal strength reported by the A3LA-RM when issuing an **AT+CSQ** command indicates the signal strength of the ring channel. Be careful when using this signal reading for comparisons between devices. Of particular note are the following:

1. There is a 0.5 dB tolerance on the calibration.
2. Each bar represents a 2 dB increment.
3. Multiple ring channels can be present at the same time so units can lock to different signals.
4. If the reading is near the decision threshold, it would be easy to see a 1-bar difference.

## 4 SIM CARD INTERFACE

The A3LA-RM modem contains an integrated Subscriber Identification Module (SIM) reader. The modem uses and requires an Iridium SIM chip for operation. The SIM chip is inserted into the opening located on top of the modem, as shown in **Figure 6**. A plastic locking mechanism is used hold the SIM in place. Place the SIM chip (facing down) into the SIM reader's bracket. Ensure that the cutoff on the SIM chip aligns with the SIM reader.




**Figure 6: Location of the SIM Reader**

## 5 LED DISPLAY

The A3LA-RM has three (3) status LEDs depicted as *P* for power indicator, *I* for Iridium satellite signal strength, and *S* for status (see **Figure 7**). They provide a quick visual check to ensure proper modem operations and a way to optimize antenna locations during field installation.

These LEDs provide the following information:

- **P:** LED lights up when power is provided to the A3LA-RM.
- **I:** LED stays solid when the signal strength is between 3–5, blinks when the signal strength is between 1 and 2, and is off when signal strength is 0. The Light-emitting diode (LED) also stays solid when the carrier detects (CD) line on the RS-232 goes high during a data call.
- **S:** LED lights up when the A3LA-RM is in data mode.



**Figure 7: Iridium Satellite Modem A3LA-RM**

## 6 CONFIGURATION SETTINGS

The A3LA-RM allows users to configure its data port communication parameters. The three configuration types are active, factory default, and stored.

- **Active:** The active configuration is the set of parameters currently in use. They can be changed individually via specific AT commands.
- **Factory default:** The factory default configuration is stored in permanent memory. This configuration can be recalled at any time through use of the **AT&Fn** command.
- **Stored:** Two groups of settings, or “profiles,” can be stored as user-defined configurations.
  - First create desired active configurations and then write them to memory using the **AT&Wn** command.
  - These profiles can be designated to be loaded as the active configuration upon A3LA-RM power-up through use of the **AT&Yn** command.
  - The A3LA-RM can be reset without loss of power to these profiles through use of the **ATZn** command.
  - The configuration settings are stored in “S-register” locations and are detailed in **Appendix A: AT Interface**.

## 7 MODES OF OPERATION

The A3LA-RM serial data port is always in one of two modes: command mode or data mode.

### Command Mode

When the data port is in command mode, AT commands can be entered to control the A3LA-RM. In command mode, flow control has no effect, if the Request To Send (RTS) input ignored and the CTS output driven ON (low).

### Data Mode

When in data mode, the A3LA-RM transfers data over the Iridium network. In data mode:

1. All characters from the DTE are sent over the Iridium network to the remote side of the connection.
2. No unsolicited result codes are issued.
3. RTS/CTS flow control, if enabled, is active. When RTS is OFF (high), the A3LA-RM suspends transfer of data to the DTE; when Clear To Send (CTS) is OFF (high), the A3LA-RM expects the DTE to suspend transfer of data.

Transitions between the modes of operation are performed automatically by the A3LA-RM in response to AT commands; the DTE has no other control over the mode.

## 8 AES-256 BIT ENCRYPTION

The A3LA-RM modem has a built-in AES-256 encryption software module. It can transmit either encrypted or unencrypted data in all modes—dial-up, direct Internet, RUDICS, SBD, and SMS. The A3LA-RM does not support encrypted voice calls. All voice calls are made in the ‘clear’ unless an external encryption module is hooked to it, such as the General Dynamics® Sectéra. When encryption is enabled and for non-packetized data transmission modes (including dial-up, direct Internet, and RUDICS), the A3LA-RM sends data in NAL Research’s proprietary format called packet send mode. Packet send mode is implemented to handle AES-256 frame synchronization between the A3LA-RM and a connected device. The encryption and decryption keys are matched in each frame to ensure NIST FIPS 140-2 compliance.

Instructions on how to use encryption can be found in the AT Command Reference manual in **Appendix B: AT Command Set Description**. The list of AT commands used to set encryption include `^CCOP`, `^KD`, `^KE`, `^KZ`, `^STR`, and `^UE`. The encryption algorithm implemented into the A3LA-RM complies with NIST FIPS 140-2 as defined in the following documents

(<https://csrc.nist.gov/publications/detail/fips/140/2/final>):

- *Security Requirements for Cryptographic Modules*, FIPS PUB 140-2, US Department of Commerce, National Institute of Standards and Technology, May 25, 2001
- *Security Requirements for Cryptographic Modules*, Annex A: Approved Security Functions for FIPS PUB 140-2, US Department of Commerce, National Institute of Standards and Technology, February 19, 2003

## 9 SELF-MONITORING TO PREVENT MODEM LOCKUP

The 9523 RF board can sometimes ‘lock up’ when inactive over a long period of time (a day or longer). The only way to recover is to power cycle the Iridium Subscriber (ISU). The A3LA-RM has safeguards put in place with a watchdog timer to keep the 9523 RF board from locking up. These were done by having another microcontroller in-line with the serial communications, monitoring the communications, and ensuring the 9523 is responding correctly. Each of the safeguards is enabled by default. Below is a description of each of the four safeguards. These safeguards were also employed on the A3LA-MPT and A3LA-XM.

- **Check When Not in a Data Call:** The microcontroller has a timer that is reset every time a character arrives from the 9523 board. The timer is set to end every 2 minutes. When the timer expires, the microcontroller sends an AT command to the 9523 to verify it is still responding. If the 9523 responds, it starts the counter over again. If there is not response, it power cycles the 9523. This can be enabled or disabled with the **^MPTNC** command.
- **Check When in a Data Call:** The microcontroller has a timer that is reset every time a character arrives from the 9523 board during data calls. The timer is set to end every 4 minutes during data calls. When the timer expires, the microcontroller verifies the 9523 is still responding by sending it the +++ sequence. If the 9523 responds, it returns to the data connection and starts the counter over again. If there is no response, it power cycles the 9523. This can be enabled or disabled with the **^MPTDC** command.
- **Registrations Every 23 Hours:** The microcontroller forces manual registration by implementing the command **AT+COPS=1** every 23 hours to ensure the 9523 stays registered. Registration will not occur during a data/voice call. This can be enabled or disabled with the **^MPTFR** command.
- **Forced Power Cycles Every 24 Hours:** The microcontroller forces a power cycle of the 9523 board every 24 hours. Power cycle will not happen during a data/voice call. This can be enabled or disabled with the **^MPTFP** command.

## 10 MOUNTING RECOMMENDATIONS

The A3LA-RM has four features on its bottom surface that can aid in its mounting (see **Appendix L: Mechanical Drawing**). These four features are predrilled at a minimum depth of 0.25 inch to accept 6-32 thread type.

## 11 TECHNICAL SUPPORT

For technical support, please contact us at:

Phone: 571-833-2169

Fax: 703-392-6795

Email: [Support@Nalresearch.com](mailto:Support@Nalresearch.com)

Technical documents are also available to download on NAL Research's website

<https://www.nalresearch.com/documentation/>.

## 12 APPENDIX A: AT INTERFACE

### 12.1 COMMAND TYPES

The A3LA-RM employs two principal types of AT commands: basic and extended. The two types have differing syntax used to query and adjust their settings. They also have unique reference standards. A specific basic AT command is used to reference S-registers and query and adjust their settings. Its syntax is similar to that of extended AT commands.

### 12.2 BASIC COMMANDS

Basic commands are industry standard and originally developed for Hayes-compatible PSTN modems. In many cases, basic commands consist of a single ASCII alpha character. In other cases, a special character precedes the alpha character. Prefix characters used in A3LA-RM basic commands include `&`, `\`, `%`, and `*`.

Most alpha characters in basic commands are followed by a numeric parameter, `n`. To adjust its setting, a basic command is entered with the appropriate numeric value of `n`. Note that if the numeric parameter `n` is omitted from the basic command entry, a value of zero is assumed for `n`. For example, `ATXn` is set to a value of 4 by entering `ATX4`, whereas it is set to value of 0 by entering either `ATX0` or `ATX`.

To query a basic command setting, enter the **AT&V** command to view the active configuration of a group of basic commands. Some basic commands listed in this document are marked with “No action, compatibility only.” In these cases, the basic command is accepted in the same fashion as it is with other modems, but has no effect on the operation of the A3LA-RM because it has no meaning in the Iridium environment.

### 12.3 EXTENDED COMMANDS

Extended commands perform actions or set parameters that extend the capability of the A3LA-RM beyond that which is allowed by basic commands. In some cases, they were designed for non-PSTN networks, such as the GSM network.

Most extended commands include a prefix of `+` followed by a single alpha character. Prefixes used in A3LA-RM extended commands include `+C`, `+D`, `+G`, `+I`, and `+S`. Extended commands

designed specifically for Iridium products include a –MS prefix. Most extended commands include three alpha characters after the prefix, but some commands include just one or two alpha characters after the prefix.

Some extended commands have a single execution mode. No further syntax is added after the prefix and body of the command. For example, **AT+GSN** is entered as shown to query the A3LA-RM for its assigned serial number (i.e., IMEI). Some extended commands incorporate a test mode to query their range of valid responses. Some extended commands incorporate set, read, and test modes. For example, **AT–MSVTR** is entered as **AT–MSVTR=n** in set mode to enable/disable receipt of DTMF messages. It is entered as **AT–MSVTR?** in read mode to query its current setting and is entered as **AT–MSVTR=?** in test mode to query its range of valid settings. Extended commands are grouped as shown below.

*Extended Cellular Commands:*

- +C prefix
- Used for GSM cellular phone-like functions
- Standards: ETSI specifications GSM 07.07 [2] and GSM 07.05 [3]

*Extended Data Compression Commands:*

- +D prefix
- Used for data compression
- Standard: V.25ter [1]

*Extended Generic Commands:*

- +G prefix
- Used for A3LA-RM issues such as identities and capabilities
- Standard: V.25ter [1]

*Extended Interface Control Commands:*

- +I prefix
- Used to control the DTE interface
- Standard: V.25ter [1]

#### *Extended Short Burst Data Commands:*

- +S prefix
- Used for SBD messaging

#### *Iridium Satellite Product Proprietary Commands:*

- –MS prefix
- Proprietary to the Iridium product line

## 12.4 COMMAND AND RESPONSE CHARACTERS

The execution of a command string follows a left-to-right execution of each command followed by the reporting of a result code for the entire string. The ASCII character set (CCITT T.50 International Alphabet 5, American Standard Code for Information Interchange) is used for the issuance of commands and responses. Only the low-order 7 bits of each character are used for commands or parameters; the high-order bit is ignored. Uppercase characters are equivalent to lowercase characters.

## 12.5 COMMAND ENTRY

An AT command is a string of characters sent by the DTE to the A3LA-RM while it is in command mode. A command string has a prefix, a body, and a terminator.

- The *prefix* consists of the ASCII characters *AT* or *at*.
- The *body* is a string of commands restricted to printable ASCII characters.
- The default *terminator* is the <CR> character.

AT command entry syntax is critical, and the following rules apply:

- All commands (apart from A/ and +++) begin with a prefix of *AT* or *at*.
- The commands in a command string (apart from A/ and +++) are executed only after the *Return* or *Enter* key is pressed.
- Use of uppercase or lowercase letters is allowed.
- The maximum number of characters in a command string is 128.
- If the numeric parameter *n* is omitted from the basic command entry, a value of zero is assumed for *n*.

- If an optional parameter is omitted from an extended command, the current value is implied. Optional parameters are enclosed by square brackets ([...]) in this document.
- Spaces entered into a command string for clarity between the AT prefix and the body of the command are ignored. Likewise, spaces entered for clarity within the command body between alpha characters and decimal parameters are ignored.
- The *Backspace* or *Delete* keys can typically be used to edit commands.
- Characters that precede the AT prefix are ignored.
- Ctrl-x can be used to abort a command line input.

Consider the following six commands to be entered in a single command line:

- **ATX0** (set basic command ATXn to n=0)
- **AT&V** (execute basic command AT&V)
- **AT+GSN** (execute extended command AT+GSN)
- **AT+CMEE=?** (query the valid range of responses of extended command AT+CMEE)
- **AT+CPBR=1,12** (execute extended command AT+CPBR with parameters 1 and 12)
- **AT-MSVTR?** (query the current setting of extended command AT-MSVTR)

The following are valid single command line entries of the above six commands:

- at x 0 &v +gsn +cmee=? +cpbr=1,12 -msvtr? (all lowercase)
- AT X 0 &V +GSN +CMEE=? +CPBR=1,12 -MSVTR? (all uppercase)
- ATX 0 &V +GSN +CMEE=? +CPBR=1,12 -MSVTR? (space omitted between AT and X)
- ATX0 &V +GSN +CMEE=? +CPBR=1,12 -MSVTR? (space omitted between ATX and 0)
- ATX &V +GSN +CMEE=? +CPBR=1,12 -MSVTR? (0 omitted from ATX0)
- ATX;&V;+GSN;+CMEE=?;+CPBR=1,12;-MSVTR? (semicolon separators)
- ATX&V+GSN+CMEE=?+CPBR=1,12-MSVTR? (no separators)

## 12.6 COMMAND RESPONSES

A result code is sent to the DTE in response to the execution of a command. It may also occur unsolicited from other conditions, such as an incoming call (e.g., RING). Responses returned as a result of a query are called information responses.

Result codes can be represented by text if the A3LA-RM is in verbose mode or with numbers if in numeric mode. The command **ATVn** informs the A3LA-RM whether to respond in verbose or numeric mode. Responses can be suppressed by setting the command **ATQn** to **ATQ1**. **Table 4** below shows the difference in format between these modes.

**Table 4: Numeric and Verbose Mode Formats**

	<b>Numeric Mode</b> <b>ATQ0 ATV0</b>	<b>Verbose Mode</b> <b>ATQ0 ATV1</b>
Result codes	<NUMERIC_CODE><CR>	<CR><LF><VERBOSE_CODE><CR><LF>
Information Responses	<TEXT><CR><LF>	<CR><LF><TEXT><CR><LF>

Command entries with invalid syntax typically respond with ERROR. Command entries of valid syntax with an out-of-range parameter can respond in one of three following manners:

- Disallow out-of-range entry and respond with ERROR.
- Disallow out-of-range entry and respond with OK.
- Disallow out-of-range entry, accept the closest in-range value, and respond with OK.

## 12.7 HARDWARE FAILURE REPORTING

If the A3LA-RM detects a hardware problem during initialization, it may be unable to function correctly. The A3LA-RM notifies the DTE of this situation by issuing an unsolicited result code at the end of initialization:

HARDWARE FAILURE: <subsys>,<error>

where <subsys> identifies the software subsystem that detected the error, and <error> is the subsystem-specific error code. Any AT commands that cannot be handled in the failure condition terminate with result code 4 ("ERROR").

## APPENDIX B: AT COMMAND SET DESCRIPTION

### (IRIDIUM RADIO LINK PROTOCOL)

#### B.1 AT – ATTENTION CODE

This is the prefix for all commands except A/ and +++. When entered on its own, the A3LA-RM will respond OK.

#### B.2 A/ – REPEAT LAST COMMAND

Repeat the last command issued to the A3LA-RM unless the power was interrupted or the unit is reset. A/ is not followed by <CR>.

#### B.3 +++ – ESCAPE SEQUENCE

The escape sequence is used to transfer from in-call data mode to in-call command mode without disconnecting from the remote modem. After a pause, the A3LA-RM will respond with OK. Register S2 can be used to alter the escape character from +, the factory default, to any hexadecimal value in the range 0 to 255.

#### B.4 EN – ECHO

Echo command characters.

- 0 Characters are not echoed to the DTE
- 1 Characters are echoed to the DTE (default)

#### B.5 ON – ONLINE

Enter in-call data mode. This is used to return to in-call data mode from in-call command mode using an existing connection. An error is reported if on-hook.

- 0 Switch from in-call command mode to in-call data mode
- Any value for n accepted

#### B.6 QN – QUIET MODE

Control A3LA-RM responses.

- 0 A3LA-RM responses are sent to the DTE (default)

- 1 A3LA-RM responses are NOT sent to the DTE

## B.7 VN – VERBOSE MODE

Set the response format of the A3LA-RM, which may be either numeric or textual.

- 0 Numeric responses
- 1 Textual responses (default)

## B.8 WN – ERROR CORRECTION MESSAGE CONTROL

Set the format of the CONNECT messages.

Upon connection, the A3LA-RM reports the DTE speed (default)

Upon connection, the A3LA-RM reports the line speed, the error correction protocol and the DTE speed in that order

Upon connection, the A3LA-RM reports its data port speed

## B.9 ZN – SOFT RESET

Reset the A3LA-RM to a user-stored configuration.

Restores user configuration 0

Restores user configuration 1

## B.10 &CN – DCD OPTION

Select how the A3LA-RM controls the DCD behavior. DCD always indicates the connection status.

No action, compatibility only.

*Allowed values for n are 0 and 1.*

## B.11 &DN – DTR OPTION

Set the A3LA-RM reaction to DTR signal when auto dialing is disabled (see the ^AD command).

- 0 DTR is ignored. A DTR signal input is not needed when set to &D0.
- 1 If DTR transitions from ON to OFF during a data call and is not restored ON within approximately 10 seconds, the call will be dropped.

- 2 If DTR transitions from ON to OFF during a data call, the call will be dropped (default).

## B.12 &FN – RESTORE FACTORY SETTINGS

Recall factory defaults.

- 0 Recall factory default 0

## B.13 &KN – FLOW CONTROL

Select the flow control method between the A3LA-RM and DTE.

Disables flow control

Enables RTS/CTS flow control (default)

## B.14 &MN – ASYNCHRONOUS/SYNCHRONOUS MODE

Select the DTR operating mode.

- 0 Selects normal asynchronous operation (default). (See &Qn)

## B.15 &QN – SYNC/ASYNC MODE

Select asynchronous mode. This is an extension of the &M command and is used to control the connection modes permitted.

**Note:** The register is not updated right after the user requests new values because the requested values may or may not be what Iridium Radio Link Protocol (IRLP) will use once a data call is established due to negotiations with the other peer. If the register is updated right away, this may give the user the impression that those values will be used during the data call, but there is no guarantee that will be the case. The real values will only be known once a data call is established and the negotiation phase is done. For that reason, the values are written to the register only after a call is established and both sides have negotiated parameter values (such as mode of operation). The value of the register will be reset to default value (5) after the call completed.

- 0, 6 Normal asynchronous operation with no error correction (unacknowledged mode)

- 5 Asynchronous operation with error correction (acknowledged mode)  
(default)

## B.16 &SN – DSR OVERRIDE

Define the behavior of DSR.

- DSR always active (default)
- Same as 0

## B.17 &V – VIEW ACTIVE AND STORED CONFIGURATION

View the current active configuration and stored profiles.

## B.18 &WN – STORE ACTIVE CONFIGURATION

Store the active profile in non-volatile memory. This is used to store user configurations for later use.

- Store current (active) configuration as profile 0
- Store current (active) configuration as profile 1

## B.19 &YN – DESIGNATE DEFAULT RESET PROFILE

Select profile for use after power-up.

- Select profile 0 (default)
- Select profile 1

## B.20 \KN – CONTROL BREAK

Control the response of the A3LA-RM to a break received from the DTE or the remote modem according to the parameter specified. The response is different in three separate states:

- When a break is received from DTE when A3LA-RM is in data transfer mode:
  - Enter in-call command mode, no break sent to remote modem
  - Clear data buffers and send break to remote modem
  - Same as 0
  - Send break to remote modem immediately
  - Same as 0

Send break to remote modem in sequence with transmitted data (default)

When a break is received from the remote modem during a non-error corrected connection:

Clear data buffers and send break to DTE

Same as 0

Send break to DTE immediately

Same as 2

Send break to DTE in sequence with received data

Same as 4 (default)

## B.21 %R – DISPLAY REGISTERS

Display all the S registers in the system.

## B.22 \*PN – POWER

Turn A3LA-RM off.

0 Turn A3LA-RM OFF

## B.23 +CBST – SELECT BEARER SERVICE TYPE

**Set Command:** +CBST=[<speed>[,<name>[,<ce>]]]

Select the bearer service type for mobile originated calls.

<speed> can have the following values:

Autobauding

300 bps V.21

1200 bps V.22

2400 bps V.22bis

4800 bps V.32

9600 bps V.32 (default)

300 bps V.110

1200 bps V.110

2400 bps V.110

4800 bps V.110

9600 bps V.110

<name> takes the following value:

data circuit asynchronous

<ce> can only take the following value:

non-transparent

**Read Command: +CBST?**

Query the current bearer service type settings. Response is in the form:

+CBST: <speed>,<name>,<ce>

**Test Command: +CBST=?**

List the supported <speed>, <name>, <ce>. Response is in the form:

+CBST: (supported <speed>s),(supported <name>s),(supported <ce>s)

## B.24 +CGMI – MANUFACTURER IDENTIFICATION

**Exec Command: +CGMI**

Query A3LA-RM RF board manufacturer.

## B.25 +CGMM – MODEL IDENTIFICATION

**Exec Command: +CGMM**

Query A3LA-RM RF board model.

## B.26 +CGMR – REVISION

**Exec Command: +CGMR**

Query A3LA-RM RF board revision.

## B.27 +CGSN – SERIAL NUMBER

**Exec Command: +CGSN**

Query A3LA-RM IMEI.

## B.28 +CMEE – REPORT MOBILE EQUIPMENT ERROR

**Set Command: +CMEE=[<x>]**

Set mobile equipment error reporting level.

<x> takes the following values:

- Disable error reporting (use ERROR result code) (default)
- Enable numeric error reporting
- Enable verbose error reporting

An example of an error report is:

+CME ERROR: <y>

where <y> can be the number or text listed below:

- A3LA-RM RF board failure
- no connection to A3LA-RM
- A3LA-RM RF board-adaptor link reserved
- operation not allowed
- operation not supported
- PH-SIM PIN required
- PH-FSIM PIN required
- PH-FSIM PUK required
- SIM not inserted
- SIM PIN required
- SIM PUK required
- SIM failure
- SIM busy
- SIM wrong
- incorrect password
- SIM PIN2 required
- SIM PUK2 required
- memory full
- invalid index
- not found
- memory failure
- text string too long
- invalid characters in text string

dial string too long  
invalid characters in dial string  
number is SIM fixed dialing restricted  
no network service  
network timeout  
emergency calls only  
network personalization PIN required  
network personalization PUK required  
network subset personalization PIN required  
network subset personalization PUK required  
service provider personalization PIN required  
service provider personalization PUK required  
corporate personalization PIN required  
corporate personalization PUK required  
unknown

**Read Command: +CMEE?**

Query mobile equipment error reporting level. The response is in the form:

+CMEE: <x>

**Test Command: +CMEE=?**

List the supported error reporting level. The response is in the form:

+CMEE: (supported <x>s)

## B.29 +CPAS – MODEM ACTIVITY STATUS

**Exec Command: +CPAS**

Query A3LA-RM activity status. The response is in the form:

+CPAS: <x>

where <x> can take the following values:

Ready (allows commands)  
Unavailable (does not allow commands)  
Unknown (may not respond to commands)

Data Call Ringing (allows commands)

Data Call In Progress (allows commands)

## B.30 +CR – SERVICE REPORTING CONTROL

**Set Command:** +CR=[<mode>]

Set the service reporting level.

<mode> takes the following values:

Disable reporting (default)

Enable reporting

If reporting is enabled, the intermediate result code +CR: <serv> is returned by the A3LA-RM.

<serv> can have one of the following values:

ASYNC asynchronous transparent

SYNC synchronous transparent

REL ASYNC asynchronous non-transparent

REL SYNC synchronous non-transparent

**Read Command:** +CR?

Query the current service reporting level settings. The response is in the form:

+CR: <mode>

**Test Command:** +CR=?

List the supported reporting levels. The response is in the form:

+CR: (supported <mode>s)

## B.31 +DS – SET DATA COMPRESSION FUNCTION

**Set Command:** +DS=[<direction>[,<comp\_neg>[,<max\_dict>[,<max\_string>]]]]

Set the V.42bis data compression function.

<direction> can take on the following values:

No compression

Transmit only

Receive only

Both directions (default)

<comp\_neg> can take on the following values:

Do not disconnect if V.42bis is not negotiated by the A3LA-RM as specified in

<direction> (default)

Disconnect if V.42bis is not negotiated by the A3LA-RM as specified in <direction>

<max\_dict> can take on the following values: 512 to 2048. Default is 512.

<max\_string> can take on the following values: 6 to 250. Default is 6.

**Read Command: +DS?**

Query the current data compression parameter settings. The response is in the form:

+DS: <direction>,<comp\_neg>,<max\_dict>,<max\_dict>

**Test Command: +DS=?**

List the supported data compression parameters. The response is in the form:

+DS: (supported<direction>s),(supported<comp\_neg>s),(supported  
<max\_dict>s),(supported<max\_dict>s)

**Data compression will not work if IRLP is in unacknowledged mode.**

**Note:** The register is not updated right after the user requests new values because the requested values may or may not be what IRLP will use once a data call is established due to negotiations with the other peer. If the register is updated right away, this may give the user the impression that those values will be used during the data call, but there is no guarantee that will be the case. The real values will only be known once a data call is established and the negotiation phase is done. For that reason, the values are written to the register only after a call is established and both sides have negotiated parameter values. The value of the register will be reset to default value (3) after the call is completed.

## B.32 +DR – DATA COMPRESSION REPORT LEVEL

**Set Command: +DR=[<mode>]**

Set the data compression reporting level.

<mode> can take on the following values:

Disable data compression reporting (default)

Enable data compression reporting

If reporting is enabled, the following intermediate result codes are transmitted by the A3LA-RM:

- +DR: NONE No data compression
- +DR: V42B Data compression in use in both directions
- +DR: V42B RD Data compression in use in receive direction only
- +DR: V42B TD Data compression in use in transmit direction only

**Read Command: +DR?**

Query the current reporting level setting. The response is in the form:

+DR: <mode>

**Test Command: +DR=?**

List the supported parameter settings. The response is in the form:

+DR: (supported <mode>s)

## B.33 +CEER – EXTENDED ERROR REPORT

**Exec Command: +CEER**

Execution command causes the A3LA-RM to return information text <report> which offers the user an extended report of the reason of the failure in the last unsuccessful call setup (originating or answering) or the reason for last call release. The response is in the form:

+CEER: <report>

An example of a <report> is:

User alerting, no answer

## B.34 +CHUP – HANGUP CALL

This command causes the A3LA-RM to hangup the current data call.

## B.35 +CMGD – DELETE SMS MESSAGE

**Exec Command:** +CMGD=<index>

Execution command deletes message from preferred message storage <mem1> (<mem1> is the selected message storage from the +CPMS command) location <index>. If deleting fails, final result code +CMS ERROR: <cms\_err> is returned.

An example of an error report is:

+CMS ERROR: <cms\_err>

where <cms\_err> can be one of the numbers below:

- 1 unassigned number
- operator barred
- operation not allowed (identical to 302)
- call barred
- SM transfer rejected
- destination out of service
- unidentified subscriber
- facility rejected
- unknown subscriber
- network out of order
- temporary failure
- congestion
- resources unavailable
- facility not subscribed
- facility not implemented
- invalid SM reference value
- invalid message
- invalid mandatory information element
- nonexistent message type
- incompatible message
- nonexistent information element
- protocol error

interworking  
telephony interworking not supported  
SM type 0 not supported  
cannot replace SM  
unspecified TP-PID error  
coding scheme not supported  
message class not supported  
unspecified TP-DCS error  
command not actioned  
command unsupported  
TPDU not supported  
SC busy  
no SC subscription  
SC system failure  
invalid SME address  
destination SME barred  
SM rejected  
SIM SMS storage full  
no SMS storage capability in SIM  
error in MS  
memory capacity exceeded  
unspecified error  
A3LA-RM failure  
SMS service reserved  
operation not allowed  
operation not supported  
invalid PDU mode parameter  
invalid text mode parameter  
no SIM  
SIM PIN required

PH-SIM PIN required  
SIM failure  
SIM busy  
SIM wrong  
memory failure  
invalid memory index  
memory full  
SM-SC address unknown  
no network service  
network timeout  
unknown error

## B.36 +CMGF – SMS MESSAGE FORMAT

### ***Set Command:* +CMGF=[<mode>]**

Set command tells the A3LA-RM, which input and output format of messages to use. <mode> indicates the format of messages used with send, list, read and write commands and unsolicited result codes resulting from received messages. Mode can be either PDU mode (entire TP data units used) or text mode (headers and body of the messages given as separate parameters). Only PDU mode is supported at this time.

Valid values for <mode> are:

PDU mode (default)

### ***Read Command:* +CMGF?**

Read command returns the current <mode> set. Response is in the form:

+CMGF: <mode>

### ***Test Command:* +CMGF=?**

Test command returns the list of supported <mode>s. Response is in the form:

+CMGF: (list of supported <mode>s)

## B.37 +CMGL – LIST SMS MESSAGES

### **Exec Command: +CMGL[=<stat>]**

Execution command returns messages with status value <stat> from message storage <mem1> (<mem1> is the selected message storage from the +CPMS command) to the DTE. If listing fails, final result code +CMS ERROR: <cms\_err> is returned.

Valid values for <stat> are:

PDU Text

"REC UNREAD" received unread message (i.e. new message) (default)

"REC READ" received read message

"STO UNSENT" stored unsent message (only applicable to SMS)

"STO SENT" stored sent message (only applicable to SMS)

"ALL" all messages (only applicable to +CMGL command)

Response is in the following format for PDU mode:

```
+CMGL:<index>,<stat>,<alpha>,<length><CR><LF><pdu>[<CR><LF>+CMGL:<index>,<stat>,<alpha>,<length><CR><LF><pdu> [...]]
```

where:

<alpha>: string type alphanumeric representation of TP-destination address or TP-originating address corresponding to the entry found in the phonebook (optional field);

<length>: in PDU mode, this is the length of the actual TP data unit in octets (i.e. the RP layer SMSC address octets are not counted in the length)

<pdu>: GSM 04.11 [8] SC address followed by GSM 03.40 [9] TPDU in hexadecimal format.

### **Test Command: +CMGL=?**

Test command gives a list of all status values supported by the A3LA-RM. Response is in the form:

```
+CMGL: (list of supported <stat>s)
```

## B.38 +CMGR – READ SMS MESSAGE

**Exec Command:** +CMGR=<index>

Execution command returns the SMS message with location value <index> from message storage <mem1> (<mem1> is the selected message storage from the +CPMS command). If status of the message is 'received unread', status in the storage changes to 'received read'. If reading fails, final result code +CMS ERROR: <cms\_err> is returned.

Response is in the following format for PDU mode:

+CMGR: <stat>,[<alpha>],<length><CR><LF><pdu>

where:

<stat>:

- 0 - MT message unread
- 1 - MT message read
- 2 - MO message unsent
- 3 - MO message sent

(When reading an MT message the first time, the status is reported as 0 (unread). The status is then changed to 1 (read), and that is reported on subsequent reads of that message.)

<alpha>:string type alphanumeric representation of TP-destination address or TP-originating address corresponding to the entry found in the phonebook (optional field);

<length>:in PDU mode, this is the length of the actual TP data unit in octets (i.e. the RP layer SMSC address octets are not counted in the length)

<pdu>: GSM 04.11 [8] SC address followed by GSM 03.40 [9] TPDU in hexadecimal format.

## B.39 +CMGS – SEND SMS MESSAGE

**Exec Command:** +CMGS=<length><CR><pdu><ctrl-Z/ESC> (PDU mode)

Execution command sends message from the DTE to the network (SMS-SUBMIT). In PDU mode, <length> is the length of the actual TP data unit in octets; <pdu> is the GSM 04.11 [8] SC address followed by GSM 03.40 [9] TPDU in hexadecimal format.

PDU entry must be terminated by <ctrl-Z>. Sending can be cancelled by the <ESC> character.

Response is in the following format for PDU mode:

+CMGS: <mr>

where <mr> is the message reference value of the message.

If sending fails, final result code +CMS ERROR: <cms\_err> is returned.

## B.40 +CMGW – WRITE SMS MESSAGE TO MEMORY

**Exec Command:** +CMGW=<length>[,<stat>]<CR><pdu><ctrl-Z/ESC> (PDU mode)

Execution command stores a message to memory storage <mem2> (<mem2> is selected by the +CPMS command). In PDU mode, <length> is the length of the actual TP data unit in octets; <pdu> is the GSM 04.11 [8] SC address followed by GSM 03.40 [9] TPDU in hexadecimal format. By default, message status will be set to 'stored unsend', but parameter <stat> allows also other status values to be given.

PDU entry must be terminated by <ctrl-Z>. Storing can be cancelled by sending the <ESC> character.

Response is in the following format for PDU mode:

+CMGW: <index>

where <index> indicates the memory location where the message is stored.

If storing fails, final result code +CMS ERROR: <cms\_err> is returned.

## B.41 +CMOD – CALL MODE

**Set Command: +CMOD=[<mode>]**

Set command selects the call mode of further dialing commands (D) or for next answering command (A). Mode can be either single or alternating (the terms "alternating mode" and "alternating call" refer to all GSM bearer and tele-services that incorporate more than one basic service (voice, data, fax) within one call). For the satellite modem, only a single call is supported.

<mode>:

single mode (default)

**Read Command: +CMOD?**

Query the current call mode settings. The response is in the form:

+CMOD: <mode>

**Test Command: +CMOD=?**

List the supported call modes. The response is in the form:

+CMOD: (supported <mode>s)

## B.42 +CNMI – NEW SMS MESSAGE INDICATIONS TO DTE

**Set Command: +CNMI=[<mode>[,<mt>[,<bm>[,<ds>[, <bfr>]]]]]**

Set command selects the procedure, how receiving of new messages from the network is indicated to the DTE when DTE is active, e.g. DTR signal is ON.

Valid values for <mode> are:

Buffer unsolicited result codes in the A3LA-RM. If result code buffer is full, older indications are discarded and replaced with the new received indications. (default)

Discard indication and reject new received message unsolicited result codes when A3LA-RM-DTE link is reserved (e.g. in in-call data mode). Otherwise forward them directly to the DTE.

Buffer unsolicited result codes in the A3LA-RM when A3LA-RM-DTE link is reserved (e.g. in in-call data mode) and flush them to the DTE after reservation. Otherwise forward them directly to the DTE.

Valid values for <mt> are:

No SMS-DELIVER indications are routed to the DTE. (default)

If SMS-DELIVER is stored in the A3LA-RM, indication of the memory location is routed to the DTE using unsolicited result code:

+CMTI: <mem>,<index>

SMS-DELIVERS (except class 2 messages and messages in the message waiting indication group (store message)) are routed directly to the TE using unsolicited result code:

+CMT: [<alpha>],<length><CR><LF><pdu> (PDU mode)

Class 3 SMS-DELIVERS are routed directly to TE using unsolicited result codes defined in <mt>=2. Messages of other data coding schemes result in indication as defined in <mt>=1.

Valid values for <bm> are:

No CBM indications are routed to the DTE. (default)

Valid values for <ds> are:

No SMS-STATUS-REPORTs are routed to the DTE. (default)

SMS-STATUS-REPORTs are routed to the DTE using unsolicited result code:

+CDS: <length><CR><LF><pdu> (PDU mode)

Valid values for <bfr> are:

0 Buffer of unsolicited result codes defined within this command is flushed to the DTE when <mode> 1...3 is entered (OK response is returned before flushing the codes). (default)

1 Buffer of unsolicited result codes defined within this command is cleared when <mode> 1...3 is entered.

**Read Command: +CNMI?**

Read command returns the current settings for the SMS message indication.

Response is in the form:

+CNMI: <mode>,<mt>,<bm>,<ds>,<bfr>

**Test Command: +CNMI=?**

Test command returns the supported settings of the A3LA-RM. Response is in the form:

+CNMI: (list of supported <mode>s),(list of supported <mt>s),(list of supported <bm>s),(list of supported <ds>s),(list of supported <bfr>s)

## B.43 +COPS – OPERATOR SELECT

**Set Command:** +COPS=[<mode>[,<format>[,<oper>]]]

Set command forces an attempt to manually register the A3LA-RM to the network.

Only IRIDIUM as <oper> is supported.

Valid values for the parameters are outlined below.

<mode>:

automatic (<oper> field is ignored) (default)

manual (<oper> field is optional)

<format>:

long format alphanumeric <oper>

short format alphanumeric <oper>

numeric <oper>

<oper> is of string type enclosed by quotes""; for example "IRIDIUM". <format> indicates if the format is alphanumeric or numeric; long alphanumeric format can be up to 16 characters long and short format up to 8 characters; numeric format is the Location Area Identification number which consists of a three BCD (Binary Coded Decimal) digit country code plus a two BCD digit network code; hence the number has structure: (country code digit 3)(country code digit 2)(country code digit 1)(network code digit 2)(network code digit 1). Since IRIDIUM is the only operator, the short and long format is "IRIDIUM" and the numeric format is "90103". These are the only values accepted.

Note that setting the <mode> to manual does not disable automatic registration of the A3LA-RM to the network. It just forces a manual registration procedure when entered.

**Read Command:** +COPS?

Read command returns the current mode, and will always respond with “000” for <mode>. This is due to the continually enabled nature of the automatic registration mode. The response is in the form:

```
+COPS: <mode>
```

For example:

```
+COPS:000
```

**Test Command: +COPS=?**

Test command returns the list of operators present in the network. Response is in the form:

```
+COPS: [list of supported (<stat>,long alphanumeric <oper>,short alphanumeric
<oper>,numeric <oper>)] [,,(list of supported <mode>s),(list of supported
<format>s)]
```

where <stat> indicates:

```
2      current
```

For example:

```
+COPS:(002,"IRIDIUM","IRIDIUM","90103",,(000-001),(000-002)
```

## B.44 +CPBF – FIND PHONEBOOK ENTRIES

**Exec Command: +CPBF=<findtext>**

Execution command returns phonebook entries (from the current phonebook memory storage selected with +CPBS) which alphanumeric fields start with string <findtext>. <findtext> should be of string type enclosed by “”; for example, “John”.

Entry fields returned are location number <index n>, phone number stored there <number> (of address type <type>), and text <text> associated with the number.

Response is in the following format:

```
+CPBF: <index1>,<number>,<type>,<text>[[...]<CR><LF>+CBPF:
<index2>,<number>,<type>,<text>]
```

**Test Command: +CPBF=?**

Test command returns the maximum lengths of <number> and <text> fields for phonebook entries. Response is in the form:

+CPBF: <nlength>,<tlength>

where <nlength> indicates the maximum length of <number> and <tlength> shows the maximum length of <text>.

## B.45 +CPBR – READ PHONEBOOK ENTRIES

**Exec Command:** +CPBR=<index1>[,<index2>]

Execution command returns phonebook entries in location number range <index1>...<index2> from the current phonebook memory storage selected with +CPBS. If <index2> is left out, only location <index1> is returned.

Entry fields returned are location number <index n>, phone number stored there <number> (of address type <type>) and text <text> associated with the number.

Response is in the form:

```
+CPBR: <index1>,<number>,<type>,<text>[...] <CR><LF>+CPBR:
<index2>,<number>,<type>,<text>]
```

**Test Command:** +CPBR=?

Test command returns location range supported by the current storage and the maximum lengths of <number> and <text> fields. Response is in the form:

```
+CPBR: (list of supported <index>s),<nlength>,<tlength>
```

where <nlength> indicates the maximum length of <number> and <tlength> shows the maximum length of <text>.

## B.46 +CPBS – SELECT PHONEBOOK STORAGE

**Set Command:** +CPBS=<storage>

Set command selects phonebook memory storage <storage>, which is used by other phonebook commands. <storage> should be of string type enclosed by ""; for example, "FD". <storage> takes the following values:

FD	SIM fixed dialing phonebook
LD	Last ten calls dialed phonebook
ME	A3LA-RM phonebook
MT	combined A3LA-RM and SIM phonebook (default)
SM	SIM phonebook

**Read Command: +CPBS?**

Read command returns currently selected memory, the number of used locations and total number of locations in the memory. Response is in the form:

+CPBS: <storage>,<used>,<total>

where <used> indicates the number of used locations and <total> shows the total capacity of <storage>.

**Test Command: +CPBS=?**

Test command returns supported storages.

## B.47 +CPBW – WRITE PHONEBOOK ENTRY

**Exec Command: +CPBW=[<index>][,<number>[,<type>[<text>]]]**

Execution command writes phonebook entry in location number <index> in the current phonebook memory storage selected with +CPBS. Entry fields written are phone number <number> (of address type <type>) and text <text> associated with the number. If those fields are omitted, phonebook entry is deleted. If <index> is left out, but <number> is given, entry is written to the first free location in the phonebook. Both <text> and <number> should be of string type enclosed by “”; for example, “John”,”1234”.

**Test Command: +CPBW=?**

Test command returns the location range supported by the current storage, the maximum length of <number> field, supported number formats of the storage, and the maximum length of <text> field. Response is in form:

+CPBW: (list of supported <index>s),<nlength>,(list of supported <type>s),<tlength>

## B.48 +CPIN – ENTER PIN

### **Set Command: +CPIN=<pin>[,<newpin>]**

Set command sends to the A3LA-RM a password which is necessary before it can be operated (SIM Card PIN Code, SIM PUK, etc.). If no password request is pending, no action is taken by the A3LA-RM.

If the password required is SIM PUK, then <newpin> is required, where <newpin> is the new SIM Card PIN to replace the old SIM Card PIN.

If the password required is SIM PUK2, then <newpin> is required, where <newpin> is the new SIM Card PIN2 to replace the old SIM Card PIN2

Both <pin> and <newpin> should be of string type enclosed by “ ”; for example, “1234”.

### **Read Command: +CPIN?**

Read command returns an alphanumeric string indicating whether some password is required or not. Response is in the form:

+CPIN: <code>

where <code> can be one of the following:

READY	A3LA-RM is not waiting for any password.
PH PIN	A3LA-RM is waiting for Phone Unlock Code to be given.
SIM PIN	A3LA-RM is waiting for SIM Card PIN1 Code to be given.
SIM PUK	A3LA-RM is waiting for SIM PUK to be given (because SIM PIN1 is blocked).
SIM PIN2	A3LA-RM is waiting for SIM PIN2 to be given.*
SIM PUK2	A3LA-RM is waiting for SIM PUK2 to be given (because SIM PIN2 is blocked).

**\*Note:** The response “SIM PIN2” is somewhat misleading, because it indicates one of three possible scenarios:

1. PIN1 has already been successfully entered (thus equivalent to the READY response).
2. No PIN1 is required (thus equivalent to the READY response).

3. The A3LA-RM is waiting for PIN2 (used to access Fixed Dialing settings and other subscription-based features).

In any of these three cases, the A3LA-RM should be available to place and receive calls.

**Note:** +CPIN is closely related to +CLCK and +CPWD. See these commands for additional information.

## B.49 +CPMS – SELECT PREFERRED SMS MESSAGE STORAGE

**Set Command:** +CPMS=<mem1>[, <mem2>[,<mem3>]]

Set command selects memory storages <mem1>, <mem2> and <mem3>. <mem1> is the memory from which messages are read and deleted; <mem2> is the memory to which writing and sending operations are made; <mem3> is the memory to which received SMS messages are to be stored. If a chosen storage is not appropriate for the A3LA-RM, final result code +CMS ERROR: <cms\_err> is returned.

Valid values for <mem1>, <mem2> and <mem3> are:

"SM" SIM message storage

Response is in the form:

+CPMS: <used1>,<total1>,<used2>,<total2>,<used3>,<total3>

where <used1>: number of messages currently in <mem1>

<total1>: total number of message locations in <mem1>

<used2>: number of messages currently in <mem2>

<total2>: total number of message locations in <mem2>

<used3>: number of messages currently in <mem3>

<total3>: total number of message locations in <mem3>

**Read Command:** +CPMS?

Read command returns the current storage selected, usage and capacity. Response is in the form:

+CPMS:  
 <mem1>,<used1>,<total1>,<mem2>,<used2>,<total2>,<mem3>,<used3>,  
 <total3>

**Test Command: +CPMS=?**

Test command returns lists of memory storages supported by the A3LA-RM. Response is in the form:

+CPMS: (list of supported <mem1>s),(list of supported <mem2>s), (list of supported <mem3>s)

## B.50 +CREG – NETWORK REGISTRATION

**Set Command: +CREG=[<n>]**

Set command controls the presentation of an unsolicited result code +CREG: <stat> when <n>=1 and there is a change in the A3LA-RM network registration status, or code +CREG: <stat>[,<lac>,<ci>] when <n>=2 and there is a change in the registration status of the A3LA-RM.

Valid values for <n> are:

- disable network registration unsolicited result code (default)
- enable network registration unsolicited result code +CREG: <stat>
- enable network registration and location information unsolicited result code +CREG: <stat>[,<lac>,<ci>]. <lac> indicates the location area code in string format; <ci> is in the cell identifier which is not applicable to IRIDIUM.

<stat> can be one of the following:

- not registered, A3LA-RM is not currently searching a new operator to register to
- registered, home network
- not registered, but A3LA-RM is currently searching a new operator to register to
- registration denied
- unknown
- registered, roaming

**Read Command: +CREG?**

Read command returns the status of result code presentation and an integer <stat> which shows the network registration status of the A3LA-RM. Location information elements <lac> and <ci> are returned only when <n>=2 and A3LA-RM is registered in the network. Response is in the form:

+CREG: <n>,<stat>[,<lac>,<ci>]

**Test Command: +CREG=?**

Test command lists the supported settings for +CREG. Response is in the form:

+CREG: (list of supported <n>s)

## B.51 +CSCA – SMS SERVICE CENTER ADDRESS

**Set Command: +CSCA=<sca>[,<tosca>]**

Set command updates the SMSC address, through which mobile originated SMs are transmitted. In PDU mode, setting is used by the send and write commands, but only when the length of the SMSC address coded into <pdu> parameter equals zero.

<sca>: GSM 04.11 [8] RP SC address Address-Value field in string format (i.e., enclosed by quotes "");

<tosca>: GSM 04.11 [8] RP SC address Type-of-Address octet in integer format;

**Read Command: +CSCA?**

Read command returns the current service center address. Response is in the form:

+CSCA: <sca>,<tosca>

## B.52 +CSCB – SELECT CELL BROADCAST MESSAGE TYPES

**Read Command: +CSCB?**

Read command returns the current values for <mode>, <mids> and <dcss>. Response is in the form:

+CSCB: <mode>,<mids>,<dcss>

**Test Command: +CSCB=?**

Test command returns supported modes. Response is in the form:

+CSCB: (list of supported <mode>s)

## B.53 +CSCS – SELECT TE CHARACTER SET

**Set Command:** +CSCS=[<chset>]

Set command informs the A3LA-RM which character set <chset> is used by the DTE. Only the IRA character set is currently supported. <chset> should be of string type enclosed by “”; for example, “IRA”.

Valid values for <chset> are: "IRA" international reference alphabet (ITU-T T.50)

**Read Command:** +CSCS?

Read command returns the current character set used. Response is in the form:

+CSCS: <chset>

**Test Command:** +CSCS=?

Test command returns the supported character set of the A3LA-RM. Response is in the form:

+CSCS: (list of supported <chset>s)

## B.54 +CSMS – SELECT SMS MESSAGE SERVICE

**Set Command:** +CSMS=<service>

Set command selects short messaging service <service>. It returns the types of messages supported by the A3LA-RM: <mt> for mobile terminated messages, <mo> for mobile originated messages and <bm> for broadcast type messages. If chosen service is not supported, final result code +CMS ERROR:<cms\_err> shall be returned. Only message service type 0 is currently supported.

Valid values for <service> are:

0 GSM 03.40 [9] and 03.41 [10] (the syntax of SMS AT commands is compatible with GSM 07.05 [3] Phase 2 version 4.7.0) (default)

Response is in the form:

+CSMS: <mt>,<mo>,<bm>

where, <mt>, <mo>, <bm>:

type not supported

type supported

**Read Command: +CSMS?**

Read command returns the current message service type set. Response is in the form:

+CSMS: <service>,<mt>,<mo>,<bm>

**Test Command: +CSMS=?**

Test command returns the supported message services of the A3LA-RM. Response is in the form:

+CSMS: (list of supported <service>s)

## B.55 +CSTA – SELECT TYPE OF ADDRESS

**Set Command: +CSTA=[<type>]**

Select the type of number for the dial command D. <type> is the type of address in integer format specified in GSM 4.08 subclause 10.5.4.7. Typical values for <type> are:

129 Unknown type (default)  
145 International number

**Read Command: +CSTA?**

Query the current address type settings. The response is in the form:

+CSTA: <type>

**Test Command: +CSTA=?**

List the supported address type settings. The response is in the form:

+CSTA: (supported <type>s)

## B.56 +GMI – MANUFACTURER IDENTIFICATION

**Exec Command: +GMI**

Query the A3LA-RM RF board manufacturer. This command is similar to +CGMI.

## B.57 +GMM – MODEL IDENTIFICATION

**Exec Command: +GMM**

Query the A3LA-RM RF board model. This command is similar to +CGMM.

## B.58 +GMR – REVISION

**Exec Command:** +GMR

Query the A3LA-RM RF board revision. This command is similar to +CGMR.

## B.59 +GSN – SERIAL NUMBER

**Exec Command:** +GSN

Query the A3LA-RM IMEI. This command is similar to +CGSN.

## B.60 +GCAP – GENERAL CAPABILITIES

**Exec Command:** +GCAP

Query the A3LA-RM' overall capabilities.

### B.60.1 A – ANSWER

Answer immediately. This causes the A3LA-RM to answer the incoming data or voice call.

### B.62 D – DIAL

Dial a data or voice call number. The dial command causes the A3LA-RM to enter originate mode and act as an auto dialer for connection to other modems or voice lines. The usual format is ATDnx..x where n is a Dial Modifier and x is a number. The following are valid numbers: 0123456789\*#ABC. Dial modifiers are used to alter the manner in which the A3LA-RM dials.

- L Redial last number
- + International dialing prefix. Allows the international access code to be omitted from dial string.
- > Direct dial from phonebook locations. See subsection below for further details.
- ; Start up a voice call. This modifier should be given after the dialing digits (or modifiers).

Any character received from the DTE during the call establishment phase will cause the call attempted to be terminated.

## B.62.1 D> – DIRECT DIAL FROM PHONEBOOK

The A3LA-RM and SIM contain phonebooks which have a phone number and an alphanumeric field for each phonebook entry location. The use of V.25ter dialing command ensures that direct dialing from phone memory and SIM phonebook is possible through ordinary communications software which just gives the phone number field to be filled and then uses the D command to originate the call. Available memories may be queried with Select Phonebook Storage test command +CPBS=?, and location range for example with Read Phonebook Entries test command +CPBR=?.

### **Execute commands: D><str>[;]**

Originate call to phone number which corresponding alphanumeric field is <str> (if possible, all available memories should be searched for the correct entry). <str> is of string type value and should enclosed by "" (e.g., "John").

### **D> mem<n>[;]**

Originate call to phone number in memory mem entry location <n> (available memories may be queried with Select Phonebook Storage test command +CPBS=?).

mem can be one of the following:

FD	SIM fixed dialing phonebook
LD	Last ten calls dialed phonebook
ME	Phone memory
MT	combined phone and SIM phonebook locations
SM	SIM phonebook

### **D><n>[;]**

Originate call to phone number in entry location <n> (the command Select Phonebook Memory Storage +CPBS setting determines which phonebook storage is used).

## B.63 HN – HANGUP

Control the hook switch. This command is used to clear a data call connection. It is also used to clear a voice call connection when the A3LA-R/RM/RGS has originated the voice call with the ATD dial command or terminated the voice call with the ATA or ATSO=n answer command.

- 0 Place the A3LA-RM on hook.

## B.64 S0=N – AUTO-ANSWER

Auto-answer. This causes the A3LA-RM to auto-answer the incoming data or voice call.

Disable auto-answer.

- n>0 Enable auto-answer after n rings

## B.65 XN – EXTENDED RESULT CODES

Select the response set to be used by the A3LA-RM when informing the DTE of the results of a command or data or voice call.

- 0 OK, CONNECT, RING, NO CARRIER, NO ANSWER and ERROR  
CONNECT response is used to inform of a data call connection; OK response is used to inform of a voice call connection (only for A3LA-R/RM/RGS).
- 1 As X0 plus CONNECT x, where x is the DTE speed  
CONNECT x response is used for data calls only.
- 2 As X1 plus NO DIALTONE
- 3 As X2 plus BUSY
- 4 As X3 plus CARRIER x, PROTOCOL: and COMPRESSION:, where x is the line speed  
(default)  
CARRIER x, PROTOCOL:, and COMPRESSION: responses are used for data calls only.

Note that the Wn command limits which connection related responses will be reported.

## B.66 +CLVL – VOLUME LEVEL CONTROL

**Exec Command:** +CLVL=<level>

This command is used to select the 'volume' of the audio on the audio path. <level> is an integer type value with the smallest value representing the lowest sound level.

**Read Command: +CLVL?**

Query the current volume level settings. The response is in the form:

+CLVL: <level>

- 0 Equivalent to level 0 displayed on a handset's volume indicator
- 1 Equivalent to level 1 displayed on a handset's volume indicator
- 2 Equivalent to level 2 displayed on a handset's volume indicator
- 3 Equivalent to level 3 displayed on a handset's volume indicator
- 4 Equivalent to level 4 displayed on a handset's volume indicator
- 5 Equivalent to level 5 displayed on a handset's volume indicator
- 6 Equivalent to level 6 displayed on a handset's volume indicator
- 7 Equivalent to level 7 displayed on a handset's volume indicator

**Test Command: +CLVL=?**

List the supported volume level settings. The response is in the form:

+CLVL: (supported <level>s)

## B.67 +CMUT – MUTE CONTROL

**Exec Command: +CMUT=<n>**

This command is used to enable and disable the uplink voice muting during a voice call. <n> can take one of the following values:

- 0 mute off
- 1 mute on

**Read Command: +CMUT?**

Query the current mute setting. The response is in the form:

+CMUT: <n>

**Test Command: +CMUT=?**

List the supported mute settings. The response is in the form:

+CMUT: (supported <n>s)

## B.68 +CRC – CELLULAR RESULT CODES

### **ExecSet Command: +CRC=[<mode>]**

Set the extended format of incoming data or voice call indication.

<mode> takes the following values:

- 0      Disable extended format (default)
- 1      Enable extended format

If extended format is enabled, the unsolicited result code +CRING: <type> is returned by the A3LA-RM instead of RING, where <type> can be one of the following:

- ASYNC      asynchronous transparent
- SYNC      synchronous transparent
- REL ASYNC      asynchronous non-transparent
- REL SYNC      synchronous non-transparent
- FAX      facsimile
- VOICE      normal voice

### **Read Command: +CRC?**

Query the current result code settings. The response is in the form:

+CR: <mode>

### **Test Command: +CRC=?**

List the supported result code settings. The response is in the form:

+CR: (supported <mode>s)

## B.69 +CVHU – VOICE HANGUP CONTROL

### **Set Command: +CVHU=[<mode>]**

Selects whether the Hn (hangup) command shall cause a voice call connection to be disconnected or not. <mode> can take one of the following values:

- 0      Disconnect as reaction to Hn command. OK response given.
- 1      Ignore Hn command. OK response given.
- 2      Disconnect as reaction to Hn command (default).

### **Read Command: +CVHU?**

Query the current voice control hangup settings. The response is in the form:

+CVHU: <mode>

**Test Command:** +CVHU=?

List the supported voice control hangup settings. The response is in the form:

+CVHU: (supported <mode>s)

## B.70 +CCLK – REAL-TIME CLOCK

**Set Command:** +CCLK=[<time>]

Sets the real-time clock of the A3LA-RM. If setting fails, ERROR is returned.

<time>: string type value; format is “yy/MM/dd, hh:mm:sszz”, where characters indicate year two last digits), month, day, hour, minutes, seconds and time zone. There is no blank space between the two double quotes. Since time zone feature is not supported in Iridium, this particular field (zz) is ignored if it is entered. The range of valid years is between 1970 and 2058.

For example, May 15, 2011, 22:10:00 hours can be set using +CCLK=“11/05/15,22:10:00”.

**Read Command:** +CCLK?

Read command returns the current setting of the clock.

+CCLK: <time>

## B.71 –MSVTS – DTMF GENERATION IN VOICE CALL

**Set Command:** –MSVTS=<string>

Generate the specified DTMF tone (i.e., send tone DTMF message to network). The parameter <string> shall consist of elements in a list where each element is separated by a comma. Each element should either be (1) a single ASCII character; or (2) string that follows the format: <tone>[,<time>] with each string enclosed in square brackets “[ ]”. The string parameter values are defined as follows:

<tone> specifies the string of tones to be played or generated. The valid values are (in ASCII): ‘0’-‘9’, ‘#’, ‘\*’

<time> specifies the duration of each tone in 180-millisecond unit. Default value is 1 for 180 ms.

For example, the command string `-MSVTS=1,[9,2],[5,3]` will:

1. Generate DTMF 1 with a duration of 180 ms (default)
2. Generate DTMF 9 with a duration of 360 ms (2 \* 180 ms)
3. Generate DTMF 5 with a duration of 540 ms (3 \* 180 ms)

**Test Command: -MSVTS=?**

List the supported parameter settings. The response is in the form:

`-MSVTS: (supported <tone>s),(supported <time>s)`

**Note:** DTMF generated with the `-MSVTS` command is never played back locally as tones and is therefore neither played nor muted under control of the `-MSVLS` command.

## B.72 -MSVTR – DTMF RECEIVED IN VOICE CALL

**Set Command: -MSVTR=[<mode>]**

Disable or enable the receiving of DTMF messages from the network.

<mode> takes one of the following values:

- |   |                                      |
|---|--------------------------------------|
| 0 | Receiving of DTMF disabled (default) |
| 1 | Receiving of DTMF enabled            |

If receiving DTMF is enabled, the A3LA-R/RM/RGS sends the following unsolicited result code every time a DTMF inband signaling data is received from the network while in a voice call:

`-MSTRX: <tone>,<event>`

where <tone> is the DTMF tone received ('0'-'9', '#', '\*', 'A'-'D') and <event> can be one of the following:

- |   |                                  |
|---|----------------------------------|
| 0 | tone stopped (i.e. key released) |
| 1 | tone started (i.e. key pressed)  |

**Read Command: -MSVTR?**

Query the current parameter settings. The response is in the form:

–MSVTR: <mode>

**Test Command:** –MSVTR=?

List the supported parameter settings. The response is in the form:

–MSVTR: (supported <mode>s)

## B.73 –MSVLS – LOCAL DTMF FEEDBACK SELECTION

**Set Command:** –MSVLS=[<mode>]

Disable or enable playing of DTMF tones locally (i.e. feedback tones) while in a voice call.

<mode> takes one of the following values:

- 0 No mute. Play all DTMF tones (default) when pressed or received while in voice call.
- 1 Enable mute mode. Mute both pressed or received DTMF tones while in voice call.

**Read Command:** –MSVLS?

Query the current parameter settings. The response is in the form: –MSVLS: <mode>

**Test Command:** –MSVLS=?

List the supported parameter settings. The response is in the form:

–MSVLS: (supported <mode>s)

**Note:** DTMF generated with the –MSVTS command is never played back locally as tones and is therefore neither played nor muted under control of the –MSVLS command.

## B.74 –MSSTM – REQUEST SYSTEM TIME

**Exec Command:** –MSSTM

Query the latest system time received from the network. The response is the form:

–MSSTM: <system\_time>

<system\_time> can take one of the following forms:

no network service The A3LA-RM has not yet received system time from the network.

XXXXXXX Where XXXXXXXX is the current Iridium system time available from the network. The system time as received through the Iridium Air Interface, is a 32 bit integer count of the number of 90 millisecond intervals that have elapsed since the epoch. The return value is formatted as an ASCII hexadecimal number. The counter will rollover approximately every 12 years or be changed to prevent a rollover and as a result should not be used as a time source for user applications.

**Iridium system time epoch: March 8, 2007, 03:50:21.00 GMT. (Note: the original Iridium system time epoch was June 1, 1996, 00:00:11 GMT, and was reset to the new epoch in January, 2008).**

Iridium system time source: The system time is available and valid only after the A3LA-RM has registered with the network and has received the Iridium system time from the network. Once the time is received, the A3LA-RM uses its internal clock to increment the counter. In addition, at least every 8 hours, or on location update or other event that requires re-registration, the A3LA-RM will obtain a new system time from the network.

Time localization: None. The system time value is always expressed in GMT time.

Resolution and accuracy: The resolution of the system time is one Iridium frame tick, or 90 ms. Accuracy as measured by the difference between the time reported and the actual time this message is sent out of the A3LA-RM' serial port should not exceed 4 frame ticks (.36 seconds) and in most cases will be one frame tick (.09 seconds) or less.

## B.75 –MSGEO – REQUEST GEOLOCATION

**Exec Command: –MSGEO**

Query the geolocation grid code received from the network in the last Access Decision Notification message. The response is of the form:

–MSGEO: <x>,<y>,<z>,<time\_stamp>

<x>, <y>, <z> is a geolocation grid code from an earth centered Cartesian coordinate system, using dimensions, x, y, and z, to specify location. The coordinate system is aligned such that the z-axis is aligned with the north and south poles, leaving the x-axis and y-axis to lie in the plane containing the equator. The axes are aligned such

that at 0 degrees latitude and 0 degrees longitude, both y and z are zero and x is positive (x = +6376, representing the nominal earth radius in kilometers). Each dimension of the geolocation grid code is displayed in decimal form using units of kilometers. Each dimension of the geolocation grid code has a minimum value of –6376, a maximum value of +6376, and a resolution of 4. <time\_stamp> is assigned by the A3LA-RM when the geolocation grid code received from the network is stored to the A3LA-RM internal memory. Current Iridium system time, which is a running count of 90 millisecond intervals, is used for the time stamp. Time stamp is a 32-bit integer displayed in hexadecimal form.

## B.76 +CCFC – CALL FORWARD SERVICE

### *Exec Command:*

**+CCFC=<reason>,<mode>[,<number>[,<type>[,class>[,<subaddr>[,<satype>[,<time>]]]]]]]**

This command is based on GSM 07.07 [2] subclause 7.10, and allows control of the call forwarding supplementary service according to GSM 02.82 [11]. Registration, erasure and status query are supported. The valid values for the parameters are as follows:

<reason> takes one of the following values:

- 0 unconditional
- 1 mobile busy
- 2 no reply
- 3 not reachable
- 4 all call forwarding (refer GSM 02.30 [5])
- 5 all conditional call forwarding (refer GSM 02.30 [5])

<mode> takes one of the following values:

- 0 disable (not used in Call Forward)
- 1 enable (not used in Call Forward)
- 2 query status
- 3 registration

## 4 erasure

<number>: quoted string type phone number of forwarding address. It contains digits only, or empty string if not applicable.

<type>: type of address octet in integer format (refer to GSM 04.08 [7] subclause 10.5.4.7); default 145 when dialing string is international number, otherwise 129

<class>: is a sum of integers each representing a class of information:

- 1 voice (telephony)
- 2 data

<subaddr>: string type sub-address, not supported by Iridium

<satype>: type of sub-address, not supported by Iridium

<time>: string containing number of seconds (up to 30, in multiples of 5). When 'no reply' is enabled or queried, this gives the time in seconds to wait before call is forwarded.

if <mode>=2 and command is successful, the A3LA-RM returns a response in the form:

+CCFC:<status>,<class>[,<number>,<type>]

where <status> may be as follows:

- not active
- active

For example:

```
+CCFC:0,1
+CCFC:1,1,"+441223420024",145
+CCFC:2,3,"00881662990000" ,,1,,, "30"
```

**Test Command: +CCFC=?**

List supported <reason>s. The response is in the form of a range rather than a list:

+CCFC:(000-005)

## B.77 +CLCC – REQUEST CURRENT CALL STATUS

**Exec Command:** +CLCC

Returns the current call status of the A3LA-RM. The response is a comma separated list of call states. The number of call states in the response depends on the number of active call instances e.g. incoming calls and held calls.

+CLCC: <stat>[,<stat>[,<stat>]]

where <stat> (State of the A3LA-RM):

000	Active
001	Call Held
002	Dialing (MO Call)
004	Incoming (MT Call)
006	Idle

**Note:** the form of this announcement currently differs from the standard given in 3GPP TS 27.007 [12] subclause 7.18. A change to the interface may be made to become more standard.

## B.78 +CNUM – READ MSISDN NUMBERS

**Exec Command:** +CNUM

Get the MSISDN numbers of the SIM. If returning fails, ERROR is returned. Response is in the form:

+CNUM:<text>,<number>,<type>

<text>: alpha tag of the phone numbers

<number>: MSISDN numbers

<type>: if the number starts with a '+', then the type is 145; otherwise the type is 129

**Note:** MSISDN numbers are only available if they were intentionally stored on the SIM.

## B.79 +CSSSC – SUPPLEMENTARY SERVICES SHORTCODE

**Exec Command:** +CSSSC="<shortcode>"

Execute the given shortcode. If the shortcode fails, a CME ERROR code is returned. Otherwise, OK is returned.



<r1> is used to represent the maximum number of S frames that are used to acknowledge I frames at downlink direction (IWF->A3LA-RM) and can take on the following values:

1-10. Default is 10.

<r2> is used to represent the maximum number of S frames that are used to acknowledge I frames at uplink direction (A3LA-RM->IWF) and can take on the following values:

1-10. Default is 10.

<t4> is used to supervise the re-sequencing of misordered frames. The values are defined to be the earliest instant to consider a tardy frame as lost. It can take on the following values:

20-255 (in 10-ms unit). Default is 25.

<mode> is used to indicate the mode of operation and can take on the following values:

- 0 unacknowledged mode of operation
- 1 acknowledged mode of operation (default)

**Note:** For the proper operation of the IRLP procedures, t2 should be less than t1 and  $2*t4$  should be less than t1.

**Read Command: +WIRLP?**

Query the actual IRLP parameters resulting from the negotiation (XID exchange) at the start of the most recent data call. Note that these may differ from the desired parameters set using "+WIRLP=..."; from power-up they are set to hardcoded defaults, and will only change as the result of the negotiation. The response is in the form:

+WIRLP: <ver>, <k1>, <k2>, <t1>, <n2>, <t2>, <r1>, <r2>, <t4>, <mode>

**Test Command: +WIRLP=?**

List the supported IRLP parameter settings. The response is in the form:

+WIRLP: (supported <ver>s), (supported <k1>s), (supported <k2>s), (supported <t1>s),

(supported <n2>s), (supported <t2>s), (supported <r1>s), (supported <r2s),  
(supported <t4>s), (supported <mode>s)

## B.81 +WFRNG – FORCE IRLP RENEGOTIATION

**Set Command: +WFRNG=<frng>**

Set forced renegotiation of IRLP parameters.

<frng> can take the following values:

Do not renegotiate (default)

Renegotiate

Disconnect

**Read Command: +WFRNG?**

Query the current parameter setting. The response is in the form:

+WFRNG: <frng>

**Test Command: +WFRNG=?**

List the supported parameter settings. The response is in the form:

+WFRNG: (supported <frng>s)

## B.82 +WTM – IRLP TEST MODE

**Set Command: +WTM=<tm>**

Select DCE mode of operation.

<tm> can take the following values:

0 IRLP test mode off (default)

1 IRLP test mode on

**Read Command: +WTM?**

Query the current parameter setting. The response is in the form:

+WTM: <tm>

**Test Command: +WTM=?**

List the supported parameter settings. The response is in the form:

+WTM: (supported <tm>s)

## B.83 +WDLDM – IRLP DYNAMIC LINK DELAY MEASUREMENT

**Set Command:** +WDLDM=[<dldm>[,<mi>[,<dtl>]]]

Set the DCE dynamic link delay measurement parameters.

<dldm> can take the following values:

- 0 measurement off (default)
- 1 measurement on

<mi> denotes the measurement interval and can take the following values:

1-255 (in 1000-ms unit). Default is 15 for 15000 ms.

<dtl> denotes the delay tolerance in the link delay difference and can take the following values:

1-100 (in 1% unit). Default is 10%.

**Read Command:** +WDLDM?

Query the current parameter settings. The response is in the form:

+WDLDM: <dldm>,<mi>,<dtl>

**Test Command:** +WDLDM=?

List the supported parameter settings. The response is in the form:

+WDLDM: (supported <dldm>s), (supported <mi>s), (supported <dtl>s)

## B.84 +WDAV – REGISTER OR DEREGISTER AN RS-232 DAV DATA PERIPHERAL

**Set Command:** +WDAV=[<DP type>[,<encrypt>]]

Register or deregister an RS-232 DAV Data Peripheral (DP).

<DP type> can take on the following values:

- 0 Deregister peripheral
- 1 Register Type 1 RS-232 DAV Data Peripheral

<encrypt> can take on the following values:

- 0 Encryption is not supported at this time

**Read Command:** +WDAV?

Query the current DP registration parameter settings. The response is in the form:

+WDAV:<DP type>,<encrypt>

**Test Command: +WDAV=?**

List the supported DP registration parameters. The response is in the form:

+WDAV:(supported <type>s),(supported <encrypt>s)

## B.85 +SBDWB – SHORT BURST DATA: WRITE BINARY DATA

**Exec Command: +SBDWB=[<SBD message length>]**

This command is used to transfer a binary SBD message from the DTE to the single mobile originated buffer in the A3LA-RM. The mobile originated buffer can contain only one message at any one time.

Once the command is entered, the A3LA-RM will indicate to the DTE that it is prepared to receive the message by sending the ASCII encoded string “READY<CR><LF>” (hex 52 45 41 44 59 0D 0A) to the DTE.

The <SBD message length> parameter represents the length, in bytes, of the SBD message not including the mandatory two-byte checksum.

The maximum mobile originated SBD message length is 1960 bytes. The minimum mobile originated SBD message length is 1 byte.

Once the Dte receives the READY indication from the A3LA-RM, the SBD message must be sent from the DTE formatted as follows:

**{binary SBD message} + {2-byte checksum}**

The checksum is the least significant 2-bytes of the summation of the entire SBD message. The high order byte must be sent first. For example if the DTE were to send the word “hello” encoded in ASCII to the A3LA-RM the binary stream would be hex 68 65 6c 6c 6f 02 14.

The mobile originated buffer will be empty upon power-up.

If any data is currently in the mobile originated buffer, it will be overwritten.

**Command Response:**

- 0: SBD message successfully written to the A3LA-RM.
- 1: SBD message write timeout. An insufficient number of bytes were transferred to the A3LA-RM during the transfer period of 60 seconds.

- 2: SBD message checksum sent from DTE does not match the checksum calculated at the A3LA-RM.
- 3: SBD message size is not correct. The maximum mobile originated SBD message length is 1960 bytes. The minimum mobile originated SBD message length is 1 byte.

## B.86 +SBDRB – SHORT BURST DATA: READ BINARY DATA

### **Exec Command: +SBDRB**

This command is used to transfer a binary SBD message from the single mobile terminated buffer in the A3LA-RM to the DTE. The mobile terminated buffer can contain only one message at any one time.

The SBD message is transferred formatted as follows:

**{2-byte message length} + {binary SBD message} + {2-byte checksum}**

The {2-byte message length} field represents the length, in bytes, of the SBD message not including the length field or the mandatory two-byte checksum. The high order byte will be sent first.

The maximum mobile terminated SBD message length is 1890 bytes.

The checksum is the least significant 2-bytes of the summation of the entire SBD message. The high order byte will be sent first. For example if the A3LA-RM were to send the word “hello” encoded in ASCII to the DTE the binary stream would be hex 00 05 68 65 6c 6c 6f 02 14.

If there is no mobile terminated SBD message waiting to be retrieved from the A3LA-RM, the message length and checksum fields will be zero.

The mobile terminated message buffer will be empty upon power-up.

### **Command Response:**

There are no response codes generated by the A3LA-RM for this command.

## B.87 +SBDRT – SHORT BURST DATA: READ TEXT MESSAGE

### **Exec Command: +SBDRT**

This command is used to transfer a text SBD message from the single mobile terminated buffer in the A3LA-RM to the DTE. This command is similar to +SBDRB but

does not provide a length indicator or checksum. The intent of this command is to provide a human friendly interface to SBD for demonstrations and application development. It is expected that most usage of SBD will be with binary messages.

Once the command is entered, the SBD message in the mobile terminated buffer is sent out of the port.

This command is similar to +SBDRB except no length or checksum will be provided.

The maximum mobile terminated SBD message length is 1890 bytes.

The mobile terminated message buffer will be empty upon power-up.

**Command Response: +SBDRT: <CR> {mobile terminated buffer}**

## B.88 +SBDD – SHORT BURST DATA: CLEAR SBD MESSAGE BUFFER(S)

**Exec Command: +SBDD[<Delete type>]**

This command is used to clear the mobile originated buffer, mobile terminated buffer or both.

The <Delete type> parameter identifies which buffers are cleared.

- 0: Clear the mobile originated buffer
- 1: Clear the mobile terminated buffer
- 2: Clear both the mobile originated and mobile terminated buffers

Using this command or power cycling the phone are the only means by which both buffers are cleared.

The mobile terminated buffer will be cleared when an SBD session is initiated.

Sending a message from the A3LA-RM to the ESS does not clear the mobile originated buffer.

Reading a message from the A3LA-RM does not clear the mobile terminated buffer.

**Command Response:**

- 0: Buffer(s) cleared successfully
- 1: An error occurred while clearing the buffer(s)

## B.89 +SBDC – SHORT BURST DATA: CLEAR SBD MOMSN

**Exec Command: +SBDC**

This command will clear (set to 0) the mobile originated message sequence number (MOMSN) stored in A3LA-RM.

The MOMSN is maintained even after power cycle. Command Response:

- 0: The MOMSN was cleared successfully
- 1: An error occurred while clearing the MOMSN

## B.90 +SBDS – SHORT BURST DATA: STATUS

**Exec Command: +SBDS**

This command returns current state of the mobile originated and mobile terminated buffers.

**Command Response: +SBDS: <MO flag>, <MOMSN>, <MT flag>, <MTMSN>**

where:

<MO flag>: The MO flag indicates the existence of a message in the mobile originated buffer. The response from the A3LA-RM is one of the following numeric codes:

- 0: No message in mobile originated buffer
- 1: Message in mobile originated buffer

<MOMSN>: The MOMSN identifies the sequence number that will be used during the next mobile originated SBD session.

<MT Flag>: The MT flag indicates the existence of a message in the mobile terminated buffer. The response from the A3LA-RM is one of the following numeric codes:

- 0: No message in mobile terminated buffer
- 1: Message in mobile terminated buffer

<MTMSN>: The MTMSN identifies the sequence number that was used in the most recent mobile terminated SBD session. This value will be –1 if there is nothing in the mobile terminated buffer.

## B.91 +SBDTC – SHORT BURST DATA: TRANSFER MO BUFFER TO MT BUFFER

**Exec Command: +SBDTC**

This command will transfer the contents of the mobile originated buffer to the mobile terminated buffer. Developers of DTE can use this command to test reading and writing to the A3LA-RM without actually initiating SBD sessions with the ESS.

**Command Response:**

- 0: Mobile originated buffer transferred successfully
- 1: An error occurred while transferring the mobile originated buffer

## B.92 +CAR – AUDIO OUTPUT CONTROL

**Set Command: +CAR=<n>**

This command switches the type of audio output between analog, digital and mute (no audio output). Valid values for <n> are as follows:

- 0 mute
- 1 analog (Codec port)
- 2 digital (User Connector port)

**Read Command: +CAR?**

This command queries the current audio setting. Response is in the form:

+CAR: <n>

**Test Command: +CAR=?**

This command lists the supported values of <n>. Response is in the form:

+CAR: (list of supported values of <n>)

## B.93 IN – IDENTIFICATION

Requests the A3LA-RM to display information about itself.

- 0 "2400" (traffic channel rate for IRIDIUM data/fax)
- 1 "0000" (ROM checksum which is not supported so zero is output)
- 2 "OK" (result of ROM checksum verification which is not supported so OK is always

- output)
- 3 "XXXXXXX" (Software revision level)
- 4 "IRIDIUM" (Product description)
- 5 "XXXX" (Country code)
- 6 "XXX" (Factory identity)
- 7 "XXXXXXX" (Hardware specification)

## B.94 +CIER – INDICATOR EVENT REPORTING

**Set Command:** +CIER=[<mode>[,<sigind>[,<svcind>]]]

The set command enables or disables sending of the +CIEV unsolicited result code by the A3LA-RM in case of indicator state changes. <mode> controls the processing of the +CIEV unsolicited result codes.

<mode>:

- 0 Disable indicator event reporting; do not send +CIEV unsolicited result codes to the DTE; buffer the most recent indicator event for each indicator in the A3LA-RM. (default)
- 1 Enable indicator event reporting; buffer the most recent +CIEV unsolicited result code for each indicator when the data port is not in command mode, and flush them to the DTE on return to command mode; otherwise forward events directly to the DTE.

<sigind>: Control reporting of "signal quality" indicator changes.

- 0 No "signal quality" indicator reporting
- 1 Enable "signal quality" indicator reporting using result code +CIEV:0,<rss> where <rss> is:
  - 0 Equivalent to 0 bars displayed on the signal strength indicator
  - 1 Equivalent to 1 bar displayed on the signal strength indicator
  - 2 Equivalent to 2 bars displayed on the signal strength indicator

- 3 Equivalent to 3 bars displayed on the signal strength indicator
- 4 Equivalent to 4 bars displayed on the signal strength indicator
- 5 Equivalent to 5 bars displayed on the signal strength indicator

When enabled, the signal quality indicator is reported only when the signal strength changes.

<svcind>: Control reporting of “service availability” indicator changes.

- 0 No “service availability” indicator reporting
- 1 Enable “service availability” indicator reporting using result code +CIEV:1,<value>

where <value> is:

- 0 Network service currently unavailable
- 1 Network service is available

Network service availability is equivalent to a signal strength greater than 0. The service availability indicator provides a way for the DTE to wait until the A3LA-RM can start an SBD session without receiving continual notifications of changes in signal strength.

**Read Command: +CIER?**

Query the current indicator event reporting settings. The response is of the form:

+CIER:<mode>,<sigind>,<svcind>

**Test Command: +CIER=?**

List the supported settings. The response is of the form:

+CIER: (supported <mode>s),(supported <sigind>s),(supported <svcind>s)

**Note:** In <mode> 1, the DTE may miss some indicator state changes if they occur while the data port is reserved (not in command mode). However, the buffering mechanism ensures that the most recent change for each indicator during reservation will be

flushed to the DTE on return to command mode; thus the DTE is always made aware of the latest state of each indicator.

## B.95 +CRIS – RING INDICATION STATUS

### **Exec Command: +CRIS**

Query the ring indication status, returning the reason for the most recent assertion of the Ring Indicate signal. The response contains separate indications for telephony and SBD ring indications.

The response is in the form:

```
+CRIS:<tri>,<sri>
```

where <tri> indicates the telephony ring indication status:

- 0 No telephony ring alert received
- 1 Incoming voice call
- 2 Incoming data call
- 3 Incoming fax call

and <sri> indicates the SBD ring indication status:

- 0 No SBD ring alert received
- 1 SBD ring alert received

**Note:** It is valid for the A3LA-R/RM/RGS to receive a telephony ring alert and an SBD ring alert at the same time. Assertion of the RI signal indicates only the presence of an alert; this command may be used to determine the type(s) of ring alert.

## B.96 +CSQ[F] – SIGNAL QUALITY

### **Exec Command: +CSQ[F]**

Execution command returns the received signal strength indication <rss> from the A3LA-RM.

Response is in the form:

```
+CSQ: <rss>
```

where <rss> is:

- 0 Equivalent to 0 bars displayed on the signal strength indicator
- 1 Equivalent to 1 bar displayed on the signal strength indicator

- 2 Equivalent to 2 bars displayed on the signal strength indicator
- 3 Equivalent to 3 bars displayed on the signal strength indicator
- 4 Equivalent to 4 bars displayed on the signal strength indicator
- 5 Equivalent to 5 bars displayed on the signal strength indicator

**Note:** The +CSQ form of the command waits for an updated signal strength reading to become available. This will usually be within two seconds of issuing the command. If the A3LA-RM is in the process of acquiring the system, or in a satellite handoff, a delay in response of up to 10 seconds may be experienced.

If the A3LA-RM has no SIM, is awaiting a SIM PIN entry, has an invalid SIM, or has otherwise not proceeded to successful registration, the delay in response may exceed the 50 second timeout limit. Under such condition, an ERROR response will be received. To avoid a delayed response due to registration problems, issue the +CREG command to verify registration prior to entering the +CSQ command to obtain signal strength.

**Note:** The +CSQF form of the command returns immediately, reporting the last known signal strength.

**Test Command: +CSQ=?**

List the supported signal strength indications. The response is in the form:

+CSQ: (supported <rss>s)

## B.97 +CULK – UNLOCK

**Exec Command: +CULK=<unlock key>**

Unlock the SBD functionality of the A3LA-RM after it has been locked by the Gateway. The unlock key must be obtained by contacting Iridium’s customer support.

<unlock key>:

0000000000000000 .. FFFFFFFFFFFFFFFF (a string of 16 hexadecimal digits)

While the A3LA-RM is locked, it is unable to perform any SBD sessions. Any attempts to start a session will return an error code indicating that the A3LA-RM is locked.

**Command Response: +CULK:<status>**

where:

<status> indicates the lock status of the A3LA-RM following the unlock attempt:

- 0 Unlocked – A3LA-RM is not locked and is permitted to perform SBD sessions.
- 1 Locked – A3LA-RM is locked and unable to perform SBD sessions. It must be unlocked by supplying the correct unlock key to the +CULK command.
- 2 Permanently locked – A3LA-RM is locked and unable to perform SBD sessions. It cannot be unlocked and must be returned to the supplier.

**Read Command: +CULK?**

Query the current SBD lock status of the A3LA-RM. The response is of the form:

+CULK:<status>

<status>:

- 0 Unlocked
- 1 Locked
- 2 Permanently locked

## B.98 +CVMI – VOICEMAIL INDICATION

**Exec Command: +CVMI**

Query the status of the voicemail indication flag. The response is of the form:

+CVMI:<vmi>

where <vmi> is:

- 0 No voicemail indication has been received
- 1 A voicemail indication has been received

The voicemail indication flag indicates whether a voicemail notification message has been received from the voicemail system. The flag is set to 1 when an indication is received, and is cleared to 0 after being queried with the +CVMI command.

**Note:** For this feature to function, the voicemail number must be programmed into the A3LA-R/RM/RGS.

## B.99 +CICCID – READ ICC ID FROM SIM

**Exec Command:** +CICCID

Query the status ICC ID of the SIM:

+CICCID

This returns the 19 or 20 digit Integrated Circuit Card Identification of the SIM.

**Note:** This value is cached from the SIM and thus is not available until the caching has completed ~5-10 seconds after startup.

## B.100 +CLIP – CALLING LINE IDENTIFICATION PRESENTATION

**Exec Command:** +CLIP=<n>

**Note:** While this command is implemented in the A3LA-RM, it may not yet be supported in the Iridium network. Stand by for an Iridium Technical Bulletin announcing network support for this feature.

This command controls the presentation of the Calling Line Identity of the calling party in a mobile terminated call via the +CLIP unsolicited result code. <n> controls only the presentation of the unsolicited result code; the delivery of Calling Line Identity information to the A3LA-RM is controlled by the provisioning of the CLI Presentation supplementary service in the network where <n> is:

- 0     Disable the +CLIP unsolicited result code. (default)
- 1     Enable the +CLIP unsolicited result code to be sent to the DTE following the RING result code when a mobile terminated call is received and Calling Line Identity information is present.

The unsolicited result code has the format:

+CLIP:<number>,<type>

where:

<number> is the phone number of the calling party in “quotes”, in the format specified by <type>.

<type> indicates the type of number:

- 129   Dial string without the international access character
- 145   Dial string which includes the international access character ‘+’

**Read Command: +CLIP?**

Query the current CLI Presentation provisioning status and the status of the +CLIP unsolicited result code. The response is of the form:

```
+CLIP:<n>,<m>
```

<m>:

- 0 CLIP not provisioned
- 1 CLIP provisioned
- 2 Unknown (e.g. no network, etc.)

## B.101 +CLIR – CALLING LINE IDENTIFICATION RESTRICTION

**Exec Command: +CLIR=<n>**

**Note:** While this command is implemented in the A3LA-RM, it may not yet be supported in the Iridium network. Stand by for an Iridium Technical Bulletin announcing network support for this feature.

This command controls the presentation of the Calling Line Identity of the calling party to the called party in the next mobile originated call.

<n>:

- 0 Presentation is determined by the subscription of the CLIR service
- 1 CLIR invocation – i.e. hide the CLI for the next mobile originated call. This requires CLIR to be provisioned in one of the temporary modes.
- 2 CLIR suppression – i.e. show the CLI for the next mobile originated call. This requires CLIR to be provisioned in one of the temporary modes.

**Note:** If the CLIR service is not provisioned, and either invocation or suppression is requested for the next call, the next call may be rejected by the network. It is the DTE's responsibility to check whether CLIR is provisioned using the +CLIR? read command.

**Read Command: +CLIR?**

Query the current CLI Restriction provisioning status and the CLIR invocation/suppression status for the next call. The response is of the form:

```
+CLIR:<n>,<m>
```

<m>:

- 0 CLIR not provisioned
- 1 CLIR provisioned in permanent mode
- 2 Unknown (e.g. no network, etc.)
- 3 CLIR provisioned in temporary mode, defaulting to presentation restricted
- 4 CLIR provisioned in temporary mode, defaulting to presentation allowed

## B.102 +IPR – FIXED DTE RATE

### **Set Command: +IPR=<rate>[,<autoflag>]**

Set the data rate at which the A3LA-RM will accept commands. The change in data rate takes effect after the result code (e.g. OK) is received by the DTE.

<rate> takes the following values:

- 1 600 bps
- 2 1200 bps
- 3 2400 bps
- 4 4800 bps
- 5 9600 bps
- 6 19200 bps (default)
- 7 38400 bps

<autoflag> takes the following values:

- 0 Fixed rate – automatic rate adjustment is disabled
- 1 Automatic rate adjustment is enabled (default)

### **Read Command: +IPR?**

Query the current data rate and automatic rate adjustment setting. The response is in the form:

+IPR: <rate>,<autoflag>

### **Test Command: +IPR=?**

List the supported data rates. The response is in the form:

+IPR: (supported <rate>s),(supported <autoflag>s)

## B.103 +SBDWT – SHORT BURST DATA: WRITE A TEXT MESSAGE

**Exec Command:** +SBDWT=[<text message>]

This command is used to transfer a text SBD message from the DTE to the single mobile originated buffer in the A3LA-RM.

The text message may be entered on the command line:

For example, “AT+SBDWT=hello”

The length of <text message> is limited to 120 bytes. This is due to the length limit on the AT command line interface.

The message is terminated when a carriage return is entered

Alternatively, the text message may be entered separately:

Upon entering the command “AT+SBDWT”, the A3LA-RM will indicate to the DTE that it is prepared to receive the message by sending the string “READY<CR><LF>” (hex 52 45 41 44 59 0D 0A) to the DTE

Once the DTE receives the READY indication, the text message must be sent, terminated by a carriage return

The length of the text message entered in this way is limited only by the maximum mobile originated message length of 1960 bytes

The mobile originated buffer will be empty upon power-up

If any data is currently in the mobile originated buffer, it will be overwritten

**Command Response:**

For the “AT+SBDWT” form:

- 0 SBD message successfully stored in mobile originated buffer
- 1 SBD message write timeout. No terminating carriage return was sent within the transfer period of 60 seconds.

For the “AT+SBDWT=<text message>” form:

- OK SBD message successfully stored in mobile originated buffer
- ERROR An error occurred storing SBD message in mobile originated buffer

## B.104 +SBDDDET – SHORT BURST DATA: DETACH

### **Exec Command: +SBDDDET**

Initiates an SBD session to detach the A3LA-RM from the Gateway.

### **Command Response: +SBDDDET:<status>,<error>**

where:

<status>:

- 0 Detach successfully performed
- 1 An error occurred while attempting the detach

<error>:

Gateway-reported values:

- 0 Detach successfully performed
- 1..4 Reserved, but indicate success if used
- 5..14 Reserved, but indicate failure if used
- 15 Access is denied

A3LA-RM-reported values:

- 16 Modem has been locked and may not make SBD calls (see +CULK command)
- 17 Gateway not responding (local session timeout)
- 18 Connection lost (RF drop)
- 19 Link failure (A protocol error caused termination of the call)
- 20..31 Reserved, but indicate failure if used
- 32 No network service, unable to initiate call
- 33..34 Reserved, but indicate failure if used
- 35 A3LA-RM is busy, unable to initiate call
- 36.. Reserved, but indicate failure if used

This instructs the GSS to disable (detach) SBD ring alerts for the calling A3LA-RM. Successful completion of the detach command implies that the GSS has performed the requested detach action and the A3LA-RM is no longer registered for SBD ring alerts. This session does not transfer any MO or MT messages.

**Note:** A user can send an MO-SBD message and request a detach at the same time by using the +SBDI command. The +SBDI command always requests a detach.

## B.105 +SBDI – SHORT BURST DATA: INITIATE AN SBD SESSION

**Note:** The +SBDI command is provided for backwards compatibility with existing DTEs which do not use SBD Ring Alert functionality. For SBD calls invoked with this command:

The SBD session type is fixed at type 0 – MO call

The SBD Delivery Short Code will be the value specified by the +SBDDSC command

An SBD Detach is performed as part of the call

No SBD location update is performed

DTEs requiring SBD Ring Alert functionality should use the extended +SBDIX command.

### **Exec Command: +SBDI**

This command initiates an SBD session between the A3LA-RM and the GSS. If there is a message in the mobile originated buffer it will be transferred to the GSS. Similarly, if there are one or more messages queued at the GSS the oldest will be transferred to the A3LA-RM and placed into the mobile terminated buffer.

The message, if any, in the mobile originated buffer will be sent from the A3LA-RM to the GSS

If there is a message queued at the GSS it will be transferred to the A3LA-RM and placed into the mobile terminated buffer

### **Command Response:**

**+SBDI:<MO status>,<MOMSN>,<MT status>,<MTMSN>,<MT length>,<MT queued>**

where:

<MO status>: MO session status provides an indication of the disposition of the mobile originated transaction. The field can take on the following values:

- 0 No SBD message to send from the A3LA-RM
- 1 SBD message successfully sent from the A3LA-RM to the GSS

- 2 An error occurred while attempting to send SBD message from A3LA-RM to GSS

<MOMSN>: The Mobile Originated Message Sequence Number (MOMSN) is a value assigned by the A3LA-RM when sending a mobile-originated message to the GSS. This value is incremented each time an SBD session is successfully completed between the A3LA-RM to the GSS. This wraparound counter can range from 0 to 65535.

<MT status>: The MT status provides an indication of the disposition of the mobile terminated transaction. The field can take on the following values:

- 0 No SBD message to receive from the GSS
- 1 SBD message successfully received from the GSS
- 2 An error occurred while attempting to perform a mailbox check or receive a message from the GSS

<MTMSN>: The Mobile Terminated Message Sequence Number (MTMSN) is assigned by the GSS when forwarding a message to the A3LA-RM. This value is indeterminate if the field <MT status> is zero. This wraparound counter can range from 0 to 65535.

<MT length>: The MT length is the length in bytes of the mobile terminated SBD message received from the GSS. If no message was received, this field will be zero.

<MT queued>: MT queued is a count of mobile terminated SBD messages waiting at the GSS to be transferred to the A3LA-RM.

## B.106 +SBDIX[A] – SHORT BURST DATA: INITIATE AN SBD SESSION EXTENDED

**Note:** The +SBDIX command must be used in place of the +SBDI command for DTEs wishing to make use of SBD Ring Alert functionality.

**Exec Command:** +SBDIX[A][=<location>]

This command initiates an SBD session between the A3LA-RM and the GSS, setting the SBD Session. Type according to the type of command +SBDIX or +SBDIXA, Delivery Short Code according to the value specified by the +SBDDSC command, and the type of location according to whether the optional location value is provided. If there is a

message in the mobile originated buffer it will be transferred to the GSS. Similarly, if there are one or more messages queued at the GSS the oldest will be transferred to the A3LA-RM and placed into the mobile terminated buffer.

The message, if any, in the mobile originated buffer will be sent from the A3LA-RM to the GSS

If there is a message queued at the GSS it will be transferred to the A3LA-RM and placed into the mobile terminated buffer

This command will always attempt an SBD registration, consisting of attach and location update, during the SBD session in order to support SBD Ring Alert. If this is not desired, the +SBDI command should be used.

The DTE should append an 'A' to the command, i.e. +SBDIXA, when the SBD session is in response to an SBD ring alert

<location> has format:

[+|-]DDMM.MMM,[+|-]dddmm.mmm

where:

DD Degrees latitude (00-89)

MM Minutes latitude (00-59)

MMM Thousandths of minutes latitude (000-999)

ddd Degrees longitude (000-179)

mm Minutes longitude (00-59)

mmm Thousandths of minutes longitude (000-999)

This command initiates an SBD session between the A3LA-RM and the GSS, setting the SBD Session. The optional sign indicators specify latitude North (+) or South (-), and longitude East (+) or West (-). If omitted, the default is +.

For example,

AT+SBDIX=5212.483,-00007.350

corresponds to 52 degrees 12.483 minutes North, 0 degrees 7.35 minutes West.

**Command Response:**

+SBDIX:<MO status>,<MOMSN>,<MT status>,<MTMSN>,<MT length>,<MT queued>

where:

<MO status>: MO session status provides an indication of the disposition of the mobile originated transaction. The field can take on the following values:

Gateway-reported values:

- 0 MO message, if any, transferred successfully
- 1 MO message, if any, transferred successfully, but the MT message in the queue was too big to be transferred
- 2 MO message, if any, transferred successfully, but the requested Location Update was not accepted
- 3..4 Reserved, but indicate MO session success if used
- 5..8 Reserved, but indicate MO session failure if used
- 10 GSS reported that the call did not complete in the allowed time
- 11 MO message queue at the GSS is full
- 12 MO message has too many segments
- 13 GSS reported that the session did not complete
- 14 Invalid segment size
- 15 Access is denied

A3LA-RM-reported values:

- 16 Modem has been locked and may not make SBD calls (see +CULK command)
- 17 Gateway not responding (local session timeout)
- 18 Connection lost (RF drop)
- 19 Link failure (A protocol error caused termination of the call)
- 20..31 Reserved, but indicate failure if used
- 32 No network service, unable to initiate call
- 33..34 Reserved, but indicate failure if used
- 35 A3LA-RM is busy, unable to initiate call
- 36.. Reserved, but indicate failure if used

<MOMSN>: The Mobile Originated Message Sequence Number (MOMSN) is a value assigned by A3LA-RM when sending a mobile-originated message to the GSS. This

value is incremented each time an SBD session is successfully completed between the A3LA-RM to the GSS. This wraparound counter can range from 0 to 65535.

<MT status>: The MT status provides an indication of the disposition of the mobile terminated transaction. The field can take on the following values:

- 0 No SBD message to receive from the GSS
- 1 SBD message successfully received from the GSS
- 2 An error occurred while attempting to perform a mailbox check or receive a message from the GSS

<MTMSN>: The Mobile Terminated Message Sequence Number (MTMSN) is assigned by the GSS when forwarding a message to the A3LA-RM. This value is indeterminate if the field <MT status> is zero. This wraparound counter can range from 0 to 65535.

<MT length>: The MT length is the length in bytes of the mobile terminated SBD message received from the GSS. If no message was received, this field will be zero.

<MT queued>: MT queued is a count of mobile terminated SBD messages waiting at the GSS to be transferred to the A3LA-RM.

## B.107 +SBDDSC – SHORT BURST DATA: DELIVERY SHORT CODE

**Set Command:** +SBDDSC=<dsc>

Set the Delivery Short Code (DSC), which provides dynamic routing or control information for MO or MT messages. This is an 8-bit value providing the ability to set individual fields. Value 0x80 (hexadecimal) sets the most significant bit. Value 0x01 sets the least significant bit. Flag values can be added together to achieve a combination of settings. Some fields are overridden during certain SBD sessions (e.g. a +SBDREG registration session sets flag 0x80). Enable or disable ring indications for SBD Ring Alerts.

<dsc>:

- 0..255 DSC to be used for subsequent MO messages (0 default)
- 0x80 Hold MT message delivery
- 0x40 Leave MT message in queue after delivery
- 0x20 Destination in MO payload

**Read Command: +SBDDSC?**

Query the current Delivery Short Code. The response is of the form:

+SBDDSC:<dsc>

## B.108 +SBDMTA – SHORT BURST DATA: MOBILE-TERMINATED ALERT

**Set Command: +SBDMTA=<mode>**

Enable or disable ring indications for SBD Ring Alerts.

<status>:

- 0 Disable ring indication
- 1 Enable ring indication (default)

When SBD ring indication is enabled, the A3LA-RM asserts the RI line and issues the unsolicited result code SBDRING when an SBD ring alert is received.

**Read Command: +SBDMTA?**

Query the current ring indication mode. The response is of the form:

+SBDMTA:<mode>

**Test Command: +SBDMTA=?**

List the supported mode settings. The response is of the form:

+SBDMTA:(supported <mode> settings)

## B.109 +SBDREG – SHORT BURST DATA: NETWORK REGISTRATION

**Exec Command: +SBDREG[=<location>]**

Triggers an SBD session to perform a manual SBD registration.

This command initiates an SBD session to perform a manual SBD registration, consisting of an attach and location update. This session does not transfer any MO or MT messages.

**Note:** The A3LA-RM restricts the number of manual and automatic registrations to one every 3 minutes. Successive attempts within 3 minutes will return an error code indicating that the DTE should try later (see error 36 below).

**Note:** A user can send an MO SBD message and register at the same time by using the +SBDIX

command. The +SBDIX command always performs a registration attempt and should be used for an application requiring SBD Ring Alert. The +SBDI command never includes an SBD registration and should be used for an application that does not require SBD Ring Alert.

<location> has format:

[+|-]DDMM.MMM,[+|-]dddmm.mmm

where:

DD Degrees latitude (00-89)  
MM Minutes latitude (00-59)  
MMM Thousandths of minutes latitude (000-999)  
ddd Degrees longitude (000-179)  
mm Minutes longitude (00-59)  
mmm Thousandths of minutes longitude (000-999)

This command initiates an SBD session between the A3LA-RM and the GSS, setting the SBD Session.

The optional sign indicators specify latitude North (+) or South (-), and longitude East (+) or West (-). If omitted, the default is +.

For example,

AT+SBDIX=5212.483,-00007.350

corresponds to 52 degrees 12.483 minutes North, 0 degrees 7.35 minutes West.

**Command Response:** +SBDREG:<status>,<reg err>

where:

<status> indicates the resulting registration status of the A3LA-RM:

0 Detached – A3LA-RM is detached as a result of a successful +SBDDDET or +SBDI command  
1 Not registered – A3LA-RM is attached but has not provided a good location since it was last detached

2 Registered – A3LA-RM is attached with a good location. Note that this may be the case even when the most recent attempt did not provide a good location.

3 Registration denied – The GSS is denying service to the A3LA-RM

<reg err>:

Gateway-reported values:

0 No error

2 Session completed but the requested Location Update was not accepted

3..14 Reserved, but indicate Location Update failure if used

15 Access is denied

A3LA-RM-reported values:

16 Modem has been locked and may not make SBD calls (see +CULK command)

17 Gateway not responding (local session timeout)

18 Connection lost (RF drop)

19 Link failure (A protocol error caused termination of the call)

20..31 Reserved, but indicate failure if used

32 No network service, unable to initiate call

33..34 Reserved, but indicate failure if used

35 A3LA-RM is busy, unable to initiate call

36 Try later, must wait 3 minutes since last registration

37.. Reserved, but indicate failure if used

**Read Command: +SBDREG?**

Query the current SBD registration status of the A3LA-RM. The response is of the form:

+SBDREG:<status>

<status>:

0 Detached

1 Not registered

2 Registered

### 3 Registration denied

The registration status is stored in A3LA-RM non-volatile memory, and can therefore be queried by the DTE after powering up.

## B.110 +SBDAREG – SHORT BURST DATA: AUTOMATIC REGISTRATION

### **Exec Command: +SBDAREG=<mode>**

Set the A3LA-RM' Auto-registration mode.

<mode>:

- 0 Disable automatic registration (default)
- 1 Set the Auto-registration mode to "Automatic"
- 2 Set the Auto-registration mode to "Ask"

When auto-registration is enabled, mode 1 or 2, the A3LA-RM monitors its current location and triggers an SBD auto-registration when it determines that it has moved sufficiently far away from its last registered location. Note that auto-registration runs only while the A3LA-RM is attached to the GSS, i.e. the registration status is "Not registered" or "Registered".

Auto-registration may only be used with system-provided location. If the DTE is providing its own location (e.g. GPS), the DTE should use the manual registration command, +SBDREG. Upon triggering in mode 1, "Automatic", the A3LA-RM autonomously initiates an SBD session in order to perform a registration with its updated location. This session does not transfer any MO or MT messages.

Upon triggering in mode 2, "Ask", the A3LA-RM reports to the DTE that it should register with the system because its location has changed (see <event> below); it is then the responsibility of the DTE to register via +SBDREG or +SBDIX. +SBDIX allows the DTE to register while including an MO message and/or retrieving any MT message that is pending at the GSS.

When auto-registration is enabled, mode 1 or 2, the A3LA-RM reports relevant events to the DTE by issuing an unsolicited result code +AREG:<event>,<reg error>.

<event>:

- 0 Suggest DTE makes a registration attempt (mode 2 only)
- 1 Auto-registration has been performed successfully (mode 1 only)
- 2 Auto-registration has failed and will be retried after a delay (mode 1 only)

<reg error>:

Gateway-reported values:

- 0 No error
- 2 Session completed but the requested Location Update was not accepted
- 3..14 Reserved, but indicate Location Update failure if used
- 15 Access is denied

A3LA-RM-reported values:

- 16 A3LA-RM has been locked and may not make SBD calls (see +CULK command)
- 17 Gateway not responding (local session timeout)
- 18 Connection lost (RF drop)
- 19 Link failure (A protocol error caused termination of the call)
- 20..31 Reserved, but indicate failure if used
- 32 No network service, unable to initiate call
- 33..34 Reserved, but indicate failure if used
- 35 A3LA-RM is busy, unable to initiate call
- 36 Try later, must wait 3 minutes since last registration
- 37.. Reserved, but indicate failure if used

**Read Command: +SBDAREG?**

Query the current automatic MT registration mode. The response is of the form:

+SBDAREG:<mode>

**Test Command: +SBDAREG=?**

List the supported mode settings. The response is of the form:

+SBDAREG:(supported <mode> settings)

## B.111 +SBDSX – SHORT BURST DATA: STATUS EXTENDED

### **Exec Command: +SBDSX**

This command returns current state of the mobile originated and mobile terminated buffers, and the SBD ring alert status.

### **Command Response:**

**+SBDSX: <MO flag>, <MOMSN>, <MT flag>, <MTMSN>, <RA flag>, <msg waiting>**

where:

<MO flag>: The MO flag indicates the existence of a message in the mobile originated buffer. The response from the A3LA-RM is one of the following numeric codes:

- 0 No message in mobile originated buffer
- 1 Message in mobile originated buffer

<MOMSN>: The MOMSN identifies the sequence number that will be used during the next mobile originated SBD session.

<MT Flag>: The MT flag indicates the existence of a message in the mobile terminated buffer. The response from the A3LA-RM is one of the following numeric codes:

- 0 No message in mobile terminated buffer
- 1 Message in mobile terminated buffer

<MTMSN>: The MTMSN identifies the sequence number that was used in the most recent mobile terminated SBD session. This value will be –1 if there is nothing in the mobile terminated buffer.

<RA flag>: The RA flag indicates whether an SBD ring alert has been received and still needs to be answered.

- 0 No SBD ring alert
- 1 SBD ring alert has been received and needs to be answered

**Note:** The RA flag is set whenever the A3LA-RM receives an SBD ring alert; this happens even if the +SBDMTA setting specifies that SBD ring indications are disabled.

The RA flag is cleared only on successful completion of an SBD mailbox check, i.e. an SBD session invoked with +SBDI[X[A]] in which the returned MT status indicates that no error occurred.

The value of the RA flag is stored in non-volatile memory so it is preserved across power cycling of the A3LA-RM.

<msg waiting>: The message waiting flag indicates how many SBD mobile terminated messages are currently queued at the gateway awaiting collection by the A3LA-RM. This flag is updated after every SBD session, including +SBDI, +SBDIX, +SBDIXA, +SBDREG and +SBDEET.

## B.112 +CCWA – CALL WAITING SERVICE

Command	Possible Response(s)
+CCWA=	None (command ignored without error)
+CCWA=<n>[,<mode>,<class>]	<p><b>When command unsuccessful</b> +CME ERROR: &lt;err&gt;</p> <p><b>When &lt;mode&gt;=2 command successful</b> +CCWA:&lt;status&gt;,&lt;class1&gt; [&lt;CR&gt;&lt;LF&gt;+CCWA:&lt;status&gt;,&lt;class2&gt; [...]] (but the A3LA-RM will in practice only report a single line, &lt;class1&gt; = 1)</p> <p><b>When &lt;mode&gt; not 2 and command successful</b> None</p>
+CCWA?	<p><b>Current unsolicited result presentation status</b> +CCWA:&lt;n&gt;</p>
<p><b>Test command</b> +CCWA=?</p>	<p><b>List of supported &lt;n&gt;s</b> +CCWA:(0,1)</p>
None	<p><b>Unsolicited result notifying that a call is waiting</b> +CCWA:&lt;number&gt;,&lt;type&gt;,&lt;class&gt;</p>

**Note:** While this command is implemented in the A3LA-RM, it may not yet be supported in the Iridium network. Stand by for an Iridium Technical Bulletin announcing network support for this feature.

This command is based on GSM 07.07 [2] subclause 7.11, and allows control of the Iridium Call Waiting supplementary service similar to GSM 02.83 [6]. Activation, deactivation and status query are supported. Parameter <n> is used to disable/enable

the presentation of the unsolicited result code to the DTE when the Call Waiting service is enabled.

Command is abortable in the cases when the network is interrogated. The interaction of this command with other commands based on other GSM supplementary services is described in the GSM standard.

### Defined values

<n> (sets/shows the result code presentation status in the A3LA-RM):

- 0      disable unsolicited result presentation
- 1      enable unsolicited result presentation

On a DTE-DCE command, <n> will set the result code presentation status in the A3LA-RM, regardless of the value of any <mode> parameter.

<mode> (when <mode> parameter is not given, network is not interrogated):

- 0      disable Call Waiting service for specified class(es)
- 1      enable Call Waiting service for specified class(es)
- 2      query status of Call Waiting service for specified class(es)

<classx> is a sum of integers each representing a class of information:

- 1      voice
- 2      data
- 4      fax

This parameter defaults to 7, equal to all classes, but the A3LA-R/RM/RGS only supports Voice Call Waiting so this is illegal. Therefore in practice the DTE must supply <classx>=1.

<status>:

- 0      Call Waiting service not active for specified Class
- 1      Call Waiting service active for specified Class

<number>: quoted string type phone number of calling address in format specified by <type>

<type>: type of address octet in integer format (refer GSM 04.08 [7] subclause 10.5.4.7); default 145 when dialing string is international number, otherwise 129.

If the network rejects a request to activate/deactivate the Call Waiting service due to it not being provisioned (or for other reasons), the reported CME ERROR code will be 133 “requested service option not subscribed”. This is strictly speaking a GPRS-related code (GSM 07.07 [2] subclause 9.2.2), but is the most informative choice in this case.

**Informative examples:**

The status of only the Voice class can be queried:

AT+CCWA=1,2,1

If the command is successful, the A3LA-RM might return (after contacting the network):

+CCWA:1,1

If a remote caller tries to place a voice call to the A3LA-RM while it already has a call in progress, and the Call Waiting service has been made active for class Voice, then the network will send a message to the A3LA-RM. Then, if <n> has previously been set to ‘1’, the A3LA-RM will send an unsolicited result code to the DTE, e.g.:

+CCWA:”+441223420024”,145,1

## B.113 +CLCK – FACILITY LOCK

Command	Possible Response(s)
+CLCK=	None (command ignored without error)
+CLCK=<fac>,<mode>[<passwd>[,<classx>]]	<p><b>When command unsuccessful</b> +CME ERROR: &lt;err&gt;</p> <p><b>When &lt;mode&gt;=2 and command successful</b> +CLCK:&lt;status&gt;[,&lt;class1&gt; [&lt;CR&gt;&lt;LF&gt;+CLCK:&lt;status&gt;,&lt;class2&gt; [...]] (but the A3LA-RM will in practice only report a single line, &lt;class1&gt; = 1)</p> <p><b>When &lt;mode&gt; not 2 and command successful</b> None</p>
Test command	List of supported <fac>s

+CLCK=?	+CLCK:("CS","SC","FD","AO","AI","AB")
---------	---------------------------------------

This command is based on GSM 07.07 [2] subclause 7.4, and is used to enable, disable or interrogate an ME or a network facility <fac>.

Command is abortable in the cases when network facilities are set or interrogated. The interaction of this command with other commands based on other GSM supplementary services is described in the GSM standard.

Execute command is used to activate or deactivate Call Barring Supplementary Services, SIM Fixed Dialling feature, the SIM card PIN Code, or to enable or disable the Phone Lock feature in the A3LA-RM. A password code (detailed below) may be required, depending on the action chosen.

Not all Call Barring services detailed in GSM 07.07 [2] subclause 7.4 are supported. A subset of those implemented in the H1 menu MMI is supported.

**Note:** This command will not work unless the SIM PIN has been entered using the +CPIN command.

**Note:** Once this command has been issued to disable the PIN, neither it nor the +CPIN need to be issued again unless the PIN function is reactivated.

The following parameter values are currently supported:

<fac>:

- "CS" CNTRL Surface (Enable/Disable Phone Lock feature). The current Phone Unlock Code is required as <passwd>.
- "SC" SIM: Activate/Deactivate SIM card PIN Code, in which the SIM asks password in ME power-up. The PIN code is required as <passwd>.
- "FD" SIM fixed dialling memory feature (PIN2 is required as <passwd>)
- "AO" BAOC (Bar All Outgoing Calls) (refer GSM 02.88 [4] clause 1). The Call Barring password is required as <passwd>.
- "AI" BAIC (Bar All Incoming Calls) (refer GSM 02.88 [4] clause 2). The Call Barring password is required as <passwd>.

"AB" All Barring services (refer GSM 02.30 [5]) (applicable only for <mode>=0).  
The Call Barring password is required as <passwd>.

**Note:** Several GSM standard facility codes including the following are NOT supported:

"OI" BOIC (Bar Outgoing International Calls) (refer GSM 02.88 [4] clause 1). All Iridium calls are International, so this facility should not be exercised by a user interface.

"OX" BOIC-exHC (Bar Outgoing International Calls except to Home Country) (refer GSM 02.88 [4] clause 1). All Iridium calls are International, so this facility should not be exercised by a user interface.

"IR" BIC-Roam (Bar Incoming Calls when Roaming outside the home country) (refer GSM 02.88 [4] clause 2). In Iridium it is not possible to roam (there is only one "home country"), so this facility should not be exercised by a user interface.

"AG" All outGoing barring services (refer GSM 02.30 [5]) (applicable only for <mode>=0). This subgroup of services cannot be addressed; the user interface should just use "AB".

"AC" All inComing barring services (refer GSM 02.30 [5]) (applicable only for <mode>=0). This subgroup of services cannot be addressed; the user interface should just use "AB".

<mode>:

0 Disable (Deactivate)

1 Enable (Activate)

<passwd>: string type, enclosed by " "; for example, "1234".

**Note:** Factory default SIM card PIN Code is "1111"

**Note:** Factory default Phone Unlock Code is "1234"

<classx> is a sum of integers each representing a class of information:

1 voice

2 data

4 fax

This parameter defaults to 7, equal to all classes, but the A3LA-RM only supports Voice Call Barring so this is illegal. Therefore in practice the DTE must supply `<classx>=1` when querying or changing the status of any Call Barring facility. When querying (`<mode>=2`), `<passwd>` is irrelevant and should be supplied as "" in order to allow the `<classx>=1` parameter to be supplied.

For facilities "CS", "SC" and "FD", the `<passwd>` and `<classx>` parameters are not relevant and will be ignored if supplied.

**Test Command: +CLCK=?**

Test command returns the facility values supported by the phone. The response is in the form:

+CLCK:(list of supported <fac>s)

**Note:** Only "CS" will appear as a supported value if there is no SIM card in the device.

**Note:** +CLCK is closely related to +CPIN and +CPWD. See these commands for additional information.

## B.114 +CPWD – CHANGE PASSWORD

**Exec Command: +CPWD=<fac>,<oldpwd>,<newpwd>**

This command sets a new password for the facility lock function defined by the AT command Facility Lock +CLCK. The following parameter values are currently supported:

<fac>:

"CS" CNTRL Surface (Phone Unlock Code)

"SC" SIM (SIM Card PIN Code)

"P2" SIM PIN2 (SIM Card PIN2 Code)

"AB" Call Barring password (single password used for all call barring supplementary services)

**Note:** AT+CPWD="SC",<oldpwd>,<newpwd> will return "Error" unless the SIM Card Pin Code is currently activated (see AT command Facility Lock +CLCK).

**Note:** A user interface may prompt the user for two copies of the new password, in which case it should check the two are identical as only one copy is needed for this command.

**Test Command: +CPWD=?**

Test command returns a list of pairs which present the available facilities and the maximum length of their password. Response is in the form:

+CPWD: list of supported (<fac>,<pwdlength>)s

where <pwdlength> indicates the maximum length for the password.

**Note:** +CPWD is closely related to +CLCK and +CPIN. See these commands for additional information.

## B.115 +CSDT – SIDETONE

**Exec Command: +CSDT=<sidetone enabled>**

This command controls the A3LA-RM RF board sidetone generation. Enabling sidetone will cause the A3LA-RM to start sidetone generation. Disabling sidetone will cause the A3LA-RM to stop sidetone generation. The following parameter values are currently supported:

< sidetone enabled >:

- 1 Enable sidetone
- 0 Disable sidetone

**Query Command: +CSDT?**

This command returns the current transceiver board sidetone generation state. 1 = enabled, 0 = disabled.

**Test Command: +CSDT=?**

Test command returns a list of valid values. Response is in the form:

+CSDT: list of supported modes

## B.116 +CDSI – REPORT SMS STATUS

This announcement is sent when the network responds after a mobile-originated SMS send attempt.

**Exec Command:** none

**Unsolicited Announcement:**

+CDSI:<status>

where:

<status>:

0..255 Success code or failure cause (TD\_SMS\_RP\_CAUSE\_\*)

1 Unassigned Number

8 Operator Barring

10 Call Barred

21 SM Transfer Rejected

22 Memory Capacity Exceeded

27 Destination Out Of Order

28 Unidentified Subscriber

29 Facility Rejected

30 Unknown Subscriber

38 Network Out Of Order

41 Temporary Failure

42 Congestion

47 No Resources

50 Facility Not Subscribed

69 Facility Not Implemented

81 Invalid RP MR

95 Semantic Error

96 Mandatory IE Error

97 RP MT Not Implemented

98 Bad State

99 IE Not Implemented

111 Unspecified Error

127 Interworking Error

128 Success

129	Success Ack
253	No Transaction Id
254	CM Internal Error
255	RL Timeout

Values up to 127 are defined by GSM for SMS-PP Relay Layer messages and values 128 and above are internal codes introduced by Iridium.

## B.117 +GPSSTA – CONFIGURE GPS STATUS

This command enables and disables the GPS receiver when the module is idle. When the module is in a call, then the GPS receiver is disabled to avoid interference between the module's Iridium band transmitter and the GPS band receiver.

**Note:** the GPS receiver (and associated circuitry) is optional and is not fitted to some revisions of the A3LA-RM RF board. In this case all forms of the +GPSSTA command will return an error.

**Exec Command:** +GPSSTA=<mode>

where:

<mode>:

0	disable GPS receiver
1	enable GPS receiver

**Query Command:** +GPSSTA?

This command returns the current GPS receiver state. 1 = enabled, 0 = disabled.

**Test Command:** +GPSSTA=?

Test command returns a list of valid values. Response is in the form:

+GPSSTA: list of supported modes

## B.118 +PA – GPS: LIST OF NMEA MESSAGE FORMATS

**Exec Command:** +PA=<n>

No action, compatibility only. Only allows a value of 1 for <n>. The NMEA string returned does not contain any GPS information.

## B.119 +PLOC – GPS: DISPLAY POSITION TO 5<sup>TH</sup> DECIMAL PLACE

**Exec Command:** +PLOC

No action, compatibility only. This command always returns the string "+PLOC: For Compatibility Only".

## B.120 ^AA – AUTO ANSWER DISPLAY

**Exec Command:** ^AA=<n>

This command sets whether or not to display the ^AAI unsolicited result code when attempting to auto answer a call.

<n>:

- 0 URC is not displayed
- 1 URC is displayed. ^AAI:1 is displayed when auto answering starts and ^AAI:0 is displayed when auto answering is finished whether or not it was successful.

**Read Command:** ^AA?

Queries the current setting

**Test Command:** ^AA=?

Returns the accepted values

## B.121 ^AD – AUTO DIAL

**Exec Command:** ^AD=<enabled>,<number>

This command enables or disables auto dialing. If auto dialing is enabled, the A3LA-RM will go into auto dial mode when the DTR line is brought low and will go back to command mode when the DTR line is brought high again. While in auto dial mode, the A3LA-RM will not respond to AT commands. Instead, the A3LA-RM will continuously dial the number that is setup for auto dialing. The ^ADR command controls the retry delay in between dial attempts.

<enabled>:

- 0 Do not auto dial when the DTR line is low (default)
- 1 Auto dial when the DTR line is low

<number>: The phone number to dial. The number must be enclosed in double quotes and cannot be more than 20 characters long.

## B.122 ^ADR – AUTO DIAL RETRY

**Exec Command:** ^ADR=<delay>

This command sets the time to delay in between dial attempts in auto dial mode.

<delay>: The number of seconds to delay. The value must be between 5 and 255 seconds.

## B.123 ^CCOP – CHANGE CRYPTO OFFICER PASSWORD (ENCRYPTION)

**Exec Command:** ^CCOP=<old>,<new>

Change the Crypto Officer's password from factory-set/old value to new value. The password must include all printable keyboard characters. The password will not be reset by AT command &F. When the A3LA-RM is set to echo, all entries are replaced with asterisks (\*) instead of the actual typed value. All passwords must be between 8 and 16 characters in length. The factory-set password is 'temp password' and must be changed before encryption can be used.

<old>: Old password and must be enclosed by two single quotes ('old password')

<new>: New password and must be enclosed by two single quotes ('new password')

## B.124 ^CMGEC – CLEAR SMS ENCRYPTED STORAGE

This command is a synonym for ^SMSE for backward compatibility. See the ^SMSE command for details.

## B.125 ^FFW – FLASH FIRMWARE

**Exec Command:** ^FFW

Puts the firmware into flashing mode

## B.126 ^KD – KEY FOR DECRYPTION (ENCRYPTION)

**Exec Command:** ^KD=<password>,<key>

Allow entering the 32 bytes for the AES decryption key. These bytes must be entered with mandatory leading 0s, where each byte is represented by 2 hexadecimal uppercase characters for a total of 64 digits. The password and key will not be reset by &F. The password and key will not be echoed. This command must be entered twice before an update is made.

**Note:** The decryption key must match the encryption key at the base station or network operation center (NOC).

**Note:** A decryption key of all 0s and a TBR (Time Between Reports) value of 64801 will cause requested reports not to be sent out in tracking mode.

<password>: The Crypto Officer Password must be enclosed by two single quotes (' '). The Crypto Officer Password must be changed from its factory-set value before this command will work.

<key>: The key that must be enclosed by two single quotes (' '). This can only have characters 0-9 or A-F and must be 64 bytes long. For example, '0102030405060708090A0B0C0D0E0F101112131415161718191A1B1C1D1E1F20'.

## B.127 ^KE – KEY FOR ENCRYPTION (ENCRYPTION)

**Exec Command:** ^KE=<password>,<key>

Allow entering the 32 bytes for the AES encryption key. These bytes must be entered with mandatory leading 0s, where each byte is represented by 2 hexadecimal uppercase characters for a total of 64 digits. The password and key will not be reset by &F. The password and key will not be echoed. This command must be entered twice before an update is made.

**Note:** The Encryption key must match the Decryption key at the base station or NOC.

<password>: The Crypto Officer Password must be enclosed by two single quotes (' '). The Crypto Officer Password must be changed from its factory-set value before this command will work.

<key>: The key that must be enclosed by two single quotes (' '). This can only have characters 0-9 or A-F and must be 64 bytes long. For example, '0102030405060708090A0B0C0D0E0F101112131415161718191A1B1C1D1E1F20'.

## B.128 ^KZ – KEY ZEROIZATION (ENCRYPTION)

**Exec Command:** ^KZ=<password>

Reset or zeroize the encryption and the decryption keys and stop encryption until the keys are re-entered with the AT^KD and AT^KE commands.

<password>: The Crypto Officer Password must be enclosed by two single quotes (' '). The Crypto Officer Password must be changed from its factory-set value before this command will work.

## B.129 ^MODRSTn – MODEM RESET INFORMATION MESSAGE DISPLAYED

Whether to display the information message ^MODRST:1 when the modem is automatically recovered. Command has read.

- 0 Information message is not displayed
- 1 Information message is displayed.

## B.130 ^MPTDC- MODEM POWER TOGGLE DATA CONNECTION

**Exec Command:** ^MPTDC = [<mode>]

Enable or disable the modem power toggle functionality during a data connection. When in a data connection, after there has been a four minute period of inactivity, there will be a check sent to determine if the modem is still responding. If it is not, the modem will power cycle and return in command mode.

<mode> takes the following values:

- 0 Disable the MPT functionality during a data call.
- 1 Enable the MPT functionality during a data call.

**Read Command: ^MPTDC?**

Query the current modem power toggle data connection mode. The response is in the form:

^MPTDC: <mode>

**Test Command: ^MPTDC=?**

List the supported modem power toggle data connection modes. The response is in the form:

^MPTDC: (supported <mode>s)

## B.131 ^MPTFP- MODEM POWER TOGGLE FORCED POWER-CYCLE

**Exec Command: ^MPTFP = [<mode>]**

Enable or disable the modem power toggle forced power-cycle functionality. Every twenty-four hours the modem will attempt to find a period of inactivity to cycle the power. If it cannot find a period of inactivity, it will retry a set number of times, after which it will force a power-cycle. The forced power-cycle will not occur during a data connection.

<mode> takes the following values:

- 0 Disable the MPT forced power-cycle functionality.
- 1 Enable the MPT forced power-cycle functionality.

**Read Command: ^MPTFP?**

Query the current modem power toggle data connection mode. The response is in the form:

^MPTFP: <mode>

**Test Command: ^MPTFP=?**

List the supported modem power toggle data connection modes. The response is in the form:

^MPTFP: (supported <mode>s)

## B.132 ^MPTFR- MODEM POWER TOGGLE FORCED REGISTRATION

**Exec Command:** ^MPTFR = [<mode>]

Enable or disable the modem power toggle forced registration functionality. Every hour the modem will attempt to find a period of inactivity to make a registration. If it cannot find a period of inactivity, it will retry a set number of times, after which it will force a registration. The modem is registered to the Iridium network by dialing a dummy number. The forced registration will not occur during a data connection because it is assumed that the modem is registered.

<mode> takes the following values:

- 0 Disable the MPT forced registration functionality.
- 1 Enable the MPT forced registration functionality.

**Read Command:** ^MPTFR?

Query the current modem power toggle forced registration. The response is in the form:

^MPTFR: <mode>

**Test Command:** ^MPTFR=?

List the supported modem power toggle forced registration. The response is in the form:

^MPTFR: (supported <mode>s)

## B.133 ^MPTNC- MODEM POWER TOGGLE NOT IN DATA CONNECTION

**Exec Command:** ^MPTNC = [<mode>]

Enable or disable the modem power toggle functionality out of a data connection. When not in a data connection, after there has been a two-minute period of inactivity, there will be a check sent to determine if the modem is still responding. If it is not, the modem will power cycle and return in command mode.

<mode> takes the following values:

- 0 Disable the MPT functionality out of a data call.

- 1 Enable the MPT functionality out of a data call.

**Read Command: ^MPTNC?**

Query the current modem power toggle not data connection mode. The response is in the form:

^MPTNC: <mode>

**Test Command: ^MPTNC=?**

List the supported modem power toggle not data connection modes. The response is in the form:

^MPTNC: (supported <mode>s)

## B.134 ^MSB – MOTION SENSOR BEGIN

**Exec Command: ^MSB=<m>,<s>**

This determines the number of minutes to look for motion for before the unit wakes up.

<m>: Number of minutes to wait to determine movement. The range is from 0 to 60. The value of 0 means that the unit wakes up after sensing a single motion. Default is 3.

<s>: Sensitivity. How vigorous and consistent the motion must be every minute for the unit to determine it is in motion. The range is 1 to 26 where 1 requires the least motion and 26 requires the most motion.

**Read Command: ^MSB?**

Returns the current state for this command.

**Test Command: ^MSB=?**

Returns a fixed message indicating the ranges this can be set to.

## B.135 ^PKTS – USE PACKETS

**Exec Command: ^PKTS=<pkts>**

Set the unit to send data using packets during a data connection.

<pkts> can have the following values:

- Do not use packets
- Use packets
- Use streaming encryption

**Read Command: ^PKTS?**

Query the current setting if the unit will use packets. Response is in the form:

^PKTS: <pkts>

**Test Command: ^PKTS=?**

List the supported <pkts> Response is in the form:

^PKTS: (supported <pkts>s)

## B.136 ^PKTST – PACKET SEND TIMER

**Exec Command: ^PKTST=<timer>**

Sets the timeout interval for when to send a packet if the packet threshold size has not been reached.

<timer> can have the following values:

1..600 Timeout value in 10th of seconds

**Read Command: ^PKTST?**

Query the current value of the send timeout if the packet size threshold is not reached. Response is in the form:

^PKTST: <timer>

**Test Command: ^PKTST=?**

List the supported <timer> Response is in the form:

^PKTST: (supported <timer>s)

## B.137 ^PKTRT – PACKET RESEND TIMER

**Exec Command: ^PKTRT=<timer>**

Sets the timeout interval for when to resend a packet if an acknowledgement has not been received.

<timer> can have the following values:

1..200     Timeout value in 10th of seconds.

**Read Command: ^PKTRT?**

Query the current value of the packet resend timeout delay. Response is in the form:

^PKTRT: <pktrt>

**Test Command: ^PKTRT=?**

List the supported <timer> Response is in the form:

^PKTRT: (supported <timer>s)

## B.138 ^PKTTH – PACKET SEND THRESHOLD

**Exec Command: ^PKTTH =<threshold>**

Set the threshold size in bytes of the payload of a packet.

<threshold> can have the following values:

1..112     Size in bytes of the payload of a packet.

**Read Command: ^PKTTH?**

Query the current value of the packet payload threshold. Response is in the form:

^PKTTH: <threshold>

**Test Command: ^PKTTH=?**

List the supported <threshold> Response is in the form:

^PKTTH: (supported <threshold>s)

## B.139 ^RESETMODEMTG – RESET MODEM TOGGLE

**Exec Command: ^RESETMODEMTG**

Causes the modem to toggle its power state. When the controller receives this it brings the modem's on/off pin to ground for 300ms and releases it. Command must be the only command following the AT.

## B.140 ^RESETMODEMVF – RESET MODEM VERIFY

**Exec Command: ^RESETMODEMVF**

Causes the modem to be recovered and to have the recovery verified. When the controller receives this it runs the same code as is run when the checks have failed. Command must be the only com

## B.141 ^RLE – USE RUN LENGTH ENCODING

**Exec Command:** ^RLE=<rl>

Set the modem to utilize run length encoding for data transfers.

<rl> can have the following values:

- Do not use run length encoding
- Use run length encoding

**Read Command:** ^RLE?

Query the current setting if the unit will use packets. Response is in the form:

^RLE: <rl>

**Test Command:** ^RLE=?

List the supported <rl> Response is in the form:

^RLE: (supported <rl>s)

## B.142 ^SE – CONFIGURE STREAMING ENCRYPTION

**Exec Command:** ^SE=<imei>,<blocks>,<timeout>

<imei>: Whether or not to send the unencrypted IMEI at the beginning of the call.

- 0 Do not send IMEI (Default)
- 1 Send IMEI

<blocks>: Max number of encrypted blocks to send before a sync byte is required.

Allowable range is 1 - 255. Default is 1.

<timeout>: Milliseconds to wait before sending a partial block.

Allowable range is 1 – 65535 in units of milliseconds. Default is 1000.

**Note:** The timeout value will be rounded up to the nearest tens of milliseconds.

**Read Command:** ^SE?

Read command returns the current streaming encryption settings. Response is in the form:

^SE: =<imei>,<blocks>,<timeout>

**Test Command: ^SE=?**

Test command returns lists of memory storages supported by the A3LA-RM. Response is in the form:

^SE: (list of supported <imei >s),(list of supported <blocks>s), (list of supported <timeout>s)

mand following the AT.

## B.143 ^SMSD – SMS DELETE

**Exec Command: ^SMSD=<n>**

This command deletes a message from SMS flash memory.

<n>: The index of the message to delete. The index must be between 1 and 100.

**Test Command: ^SMSD=?**

Returns a fixed message indicating the range of acceptable values.

## B.144 ^SMSE – SMS ERASE

**Exec Command: ^SMSE**

This command erases the SMS flash memory. This command is a synonym for ^CMGEC.

## B.145 ^SMSR – SMS READ

**Exec Command: ^SMSR[=<index>]**

This command will display the message from SMS flash memory for the provided index or all of the messages in SMS flash memory if the index is not specified.

<index>: The index of the message to display. The index must be between 1 and 100.

**Read Command: ^SMSR?**

Returns the number of messages in SMS flash memory.

**Test Command: ^SMSR=?**

Returns a fixed message indicating the range of acceptable values.

## B.146 ^SSI – SEND START-UP INFORMATION

**Exec Command:** ^SSI=<n>

This command sets whether or not to display the start-up information.

<n>:

- 0 Do not display the start-up information
- 1 Display the start-up information

**Read Command:** ^SSI?

Returns the current value

**Test Command:** ^SSI=?

Returns a fixed message indicating the range of acceptable values.

## B.147 ^STR – SELF TEST RUN (ENCRYPTION)

**Exec Command:** ^STR

Cause the modem to run self-test. This is the same test performs by the modem at each power up.

## B.148 ^UE – USE ENCRYPTION

**Exec Command:** ^UE=<password>,<n>

Set the modem on whether to use encryption or not at power up. The factory-default setting is not to use encryption at power up. Setting the ^UE command will take effect only after power has been cycled. This command will return an error if the encryption password has not been set.

<password>:The Crypto Officer Password which must be enclosed by two single quotes ( ' ' )

<n>: 0 is not to use encryption and 1 is to use encryption at power up

**Read Command:** ^UE?

Returns whether <n> is set to 0 or 1 and then one of the following messages will appear:

"Encryption Disabled No Keys Entered"

("Encryption Currently Enabled" OR "Encryption Currently Disabled") AND ("Set to be Enabled Next Power Cycle" OR "Set to be Disabled Next Power Cycle")  
"Encryption Feature Not Included"

## B.149 ^VOLB – VOLUME BOOST

**Exec Command:** ^VOLB=<n>

This command controls the volume boost function. Enabling it will increase the analog audio output by 16dB

<n>:

- 0 Disable volume boost
- 1 Enable volume boost

**Read Command:** ^VOLB?

Returns the current value

**Test Command:** ^VOLB=?

Returns a fixed message indicating the range of acceptable values.

## APPENDIX C: S-REGISTER DEFINITIONS

S-registers allow control over specific A3LA-RM operations. Some S-registers contain a single numeric value. Other S-registers are bit mapped where individual bits, or sets of bits, control specific functions.

### C.1 S-REGISTER COMMANDS

Commands allow S-registers to be read, written, or simply referenced (i.e., set a pointer to designate the current, referenced S-register). S-register commands are described in the following subsections.

Commands allow S-registers to be read, written, or simply referenced (i.e. set a pointer to designate the current, referenced S-register). S-register commands are described in the following subsections.

#### C.1.1 SR – DIRECT S-REGISTER REFERENCE

Set a pointer to reference S-register r.

#### C.1.2 SR? – DIRECT S-REGISTER READ

Read the value of S-register r.

#### C.1.3 SR=N – DIRECT S-REGISTER WRITE

Set the value of S-register r to n, where n is a decimal value in the range 0 to 255.

#### C.1.4 REFERENCED S-REGISTER READ

Read the value of the current referenced S-register. The current referenced S-register is that which was last acted upon by a direct reference (ATSr), read (ATSr?), or write (ATSr=n) command.

#### C.1.5 =N – REFERENCED S-REGISTER WRITE

Set the value of the current referenced S-register to n. The current referenced S-register is that which was last acted upon by a direct reference (ATSr), read (ATSr?), or write (ATSr=n) command.

## C.2 STANDARD S-REGISTERS

**Table 5: Standard S-Registers**

Register Number	Range	Default	Description	Sr=n Command Write-Protected in SAC0201
S3	0 – 127	13	Carriage return character	
S4	0 – 127	10	Line feed character	
S5	0 – 32	8	Backspace character	
S6	0 – 255	4	Wait for dial tone <b>No action, compatibility only</b>	
S7	0 – 255	50	Communication standard used by A3LA-RM <b>No action, compatibility only</b>	
S8	0 – 255	4	Pause time for comma <b>No action, compatibility only</b>	
S9	0 – 255	6	Carrier detect response time <b>No action, compatibility only</b>	
S10	0 – 255	14	Carrier loss time <b>No action, compatibility only</b>	
S11	0 – 255	0	DTMF tone duration <b>No action, compatibility only</b>	Yes
S12	0 – 255	40	Escape guard time. Time, in 50ths of a second, until OK displayed after entering command mode by escape sequence.	
S14	0 – 255	170	Bitmap register where bit 1 reflects the En setting, bit 2 turns off command responses, bit 3 reflects the Vn setting, and bit 5 reflects pulse/tone dial mode.	

**Table 5: Standard S-Registers**

Register Number	Range	Default	Description	Sr=n Command Write-Protected in SAC0201
S21	0 – 255	48	Bitmap register where bit 0 reflects telephone jack control, bit 2 reflects RTS/CTS on/off, bits 3 and 4 reflect the &Dn setting, bit 5 reflects the &Cn setting, bit 6 reflects DSR on/off, and bit 7 reflects disconnecting long space.	Yes
S22	0 – 255	246	Bitmap register where bits 0 and 1 reflect the speaker volume setting, bits 2 and 3 reflect the speaker on/off setting, and bits 4, 5 and 6 reflect the Xn setting.	Yes
S23	0 – 255	61	Bitmap register: bit 0: autobaud setting bits 1-3: DTE baud rate bits 4-5: parity bits 6-7: guard tone	Yes
S25	0 – 255	5	Sets length of time in hundredths of a second that a change in the DTR status has to persist for before it is recognized.	
S27	0 – 255	9	Bitmap register where bits 0, 1 and 3 reflect the &Qn setting, bit 3 reflects leased line operation setting, and bits 4 and 5 reflect synchronous clock setting.	Yes
S30	0 – 255	0	Disconnect activity timer. Timer used to determine how long the call connection has been inactive, in increments of 1/10000 ms. A value of 0 disables this function.	
S31	0 – 255	0	Bitmap register where bit 1 reflects line modulation method setting, and bits 2 and 3 reflect the Wn setting.	Yes

**Table 5: Standard S-Registers**

Register Number	Range	Default	Description	Sr=n Command Write-Protected in SAC0201
S36	0 – 255	7	Bitmap register where bits 0, 1, and 2 reflect the link type setting. <b>No action, compatibility only</b>	Yes
S39	0 – 255	3	Bitmap register where bits 0, 1 and 2 reflect the &Kn setting.	Yes
S40	0 – 255	192	Bitmap register where bits 2, 3, and 4 reflect the \K setting, and bits 6 and 7 reflect the \An setting, bits 3-5 reflects the \Kn setting. <b>No action, compatibility only</b>	Yes
S41	0 – 255	3	Bitmap registers where bits 2 and 6 enable retrain on bad signal quality setting, bit 4 reflects xon/xoff usage setting, and bit 5 reflects DTE auto rate adjustment setting. <b>No action, compatibility only</b>	Yes
S95	0 – 255	0	Bitmap register for extended result codes (overrides Wn setting). 0 = CONNECT shows DCE speed 2 = Enable CARRIER XXXX 3 = Enable PROTOCOL: XXXX 5 = Enable COMPRESSION: XXXX	

### C.3 IRIDIUM SPECIFIC S-REGISTER EXTENSIONS

**Table 6: Iridium Specific S-Register Extensions**

Register Number	Range	Default	Description	Sr=n Command Write-Protected in SAC0201
S13	0 – 255	0	Bitmap register where bits 0–1 reflect the DCE data bits, bits 2–3 reflect the DCE stop bits, bits 4–6 reflect the DCE parity settings, and bit 7 is not used.	Yes
S15	0 – 2	0	Auto-answer mode selection Bits 0–1: 0 (auto-answer voice and data calls) 1 (auto-answer voice calls only) 2 (auto-answer data calls only)	
S34	0 – 255	0	Bitmap register where bit 7 reflects the +DR setting, bits 0–1 reflect the data compression type (PT), and bit 6 reflects the +DS compression negotiation setting.	Yes
S35	0 – 255	5	Bearer service capabilities	
S42	0 – 255	0	GSM Call clearing code as returned by the network. Refer to GSM 04.08 [7] Table 10.86 Cause Information Element Values.	Yes
S43	0 – 255	32	Bitmap register: 0 = +CMGF setting 1 = +CBST parameter <name> setting 2 = +CMEE setting 3 = +CMEE setting 5 = +CBST parameter <ce> setting 6 = +CRC setting 7 = +CR setting	Yes

**Table 6: Iridium Specific S-Register Extensions**

Register Number	Range	Default	Description	Sr=n Command Write-Protected in SAC0201
S44	0 – 255	4	Bitmap register: 0–2 = +CPBS setting 5–6 = +CREG setting 7 = +CLIP setting	Yes
S45	0 – 255	0	Bitmap register: 0–1 = +CNMI parameter <mode> setting 2–3 = +CNMI parameter <mt> setting 4–5 = +CNMI parameter <bm> setting 6–7 = +CNMI parameter <ds> setting	Yes
S47	0 – 255	0	Bits 4, 5, and 6 reflect TON settings for dial string	
S49	0 – 255	1	Bits 0–3 reflect NPI settings for dial string	
S51	0 – 255	0	V.42bis maximum codewords (P1), high byte	Yes
S52	0 – 255	128	V.42bis maximum codewords (P1), low byte	
S54	0 – 255	20	V.42bis maximum string size (P2)	
S58	0 – 255	0	V.42bis compression direction (P0)	
S96	0 – 255	0	IRLP version number (N0) parameter	
S98	0 – 105	105	IRLP k iwf->isu parameter	
S99	0 – 105	105	IRLP k isu->iwf parameter	
S100	1 – 15	15	IRLP N2 parameter	
S102	26 – 255	30	IRLP T1 parameter	
S103	10 – 255	10	IRLP T2 parameter	

**Table 6: Iridium Specific S-Register Extensions**

Register Number	Range	Default	Description	Sr=n Command Write-Protected in SAC0201
S104	4 – 255	4	IRLP T4 parameter	
S106	1 – 10	10	IRLP riwf->isu parameter	
S107	1 – 10	10	IRLP risu->iwf parameter	
S112	0 – 255	0	SBD upload message sequence number (high byte)	Yes
S113	0 – 255	0	SBD upload message sequence number (low byte)	Yes
S121	0 – 31	1	Bitmap register: bit 0: +SBDMTA setting (SBD ring indication) bits 1-2: +SBDAREG setting (SBD automatic registration) bit 3: +CCWA<n> setting bit 4: +GPSSTA<n> setting	Yes
S122	0 – 31	0	Bitmap register: bit 0: unused: bits 1-3: +CIER setting (indicator event reporting)	Yes
S123	0 – 255	8	Bitmap register: bit 0: unused bit 1 = +WTM bit 2 = +WDLDM<dldm> bit 3 = +WIRLP<mode> bits 4-5 = +WFRNG	Yes
S124	0 – 255	15	Dynamic link measurement interval (+WDLDM <mi> setting). Value in 1000 ms unit.	

**Table 6: Iridium Specific S-Register Extensions**

Register Number	Range	Default	Description	Sr=n Command Write-Protected in SAC0201
S125	1 – 100	10	Dynamic link delay measurement delay tolerance (+WDLM<dtl> setting). Value in % unit.	
S126	0 – 255	2	Bitmap register: 0 = Ignore &Dn command specified reaction to DTR ON to OFF transitions. Disconnect as reaction to Hn command. OK response given. 1 = Ignore &Dn command specified reaction to DTR ON to OFF transitions. Ignore Hn command. OK response given 2 = Comply with &Dn command specified reaction to DTR ON to OFF transitions. Disconnect as reaction to Hn command.	Yes
S127	0 – 255	0	Bitmap Register containing copies of MSVTR/MSVLS parameters: Bit 0 = –MSVTR: 0 = Disabled (default) 1 = Enabled Bit 1 = –MSVLS: 0 = No Mute (default) 1 = Mute Enabled Bits 2-5 = Reserved (see IID#2600)	Yes

## APPENDIX D: SUMMARY OF RESULT CODES

The following tables list the result codes returned by the A3LA-RM.

**Table 7: V.25ter/Hayes Result Codes**

Numeric (V0)	Verbose (V1)	Description
0	'OK'	Acknowledges execution of command; voice call connection has been established.
1	'CONNECT'	Data call connection has been established.
2	'RING'	Incoming data or voice call received (unsolicited).
3	'NO CARRIER'	Data or voice call connection terminated.
4	'ERROR'	Command not accepted.
5	'CONNECT 1200'	Data call connection established at 1200 bps.
6	'NO DIALTONE'	No dial tone detected.
7	'BUSY'	Busy signal detected.
8	'NO ANSWER'	Data or voice call connection completion timeout.
9	'CONNECT 0600'	Data call connection established at 600 bps.
10	'CONNECT 2400'	Data call connection established at 2400 bps.
11	'CONNECT 4800'	Data call connection established at 4800 bps.
12	'CONNECT 9600'	Data call connection established at 9600 bps.
13	'CONNECT 7200'	Data call connection established at 7200 bps.
14	'CONNECT 12000'	Data call connection established at 12000 bps.
15	'CONNECT 14400'	Data call connection established at 14400 bps.
16	'CONNECT 19200'	Data call connection established at 19200 bps.
17	'CONNECT 38400'	Data call connection established at 38400 bps.
18	'CONNECT 57600'	Data call connection established at 57600 bps.

**Table 7: V.25ter/Hayes Result Codes**

Numeric (V0)	Verbose (V1)	Description
19	'CONNECT 115200'	Data call connection established at 115200 bps.
40	'CARRIER 300'	Data rate detected at 300 bps.
44	'CARRIER 1200/75'	Data rate detected at V.23 backward channel.
46	'CARRIER 1200'	Data rate detected at 1200 bps.
47	'CARRIER 2400'	Data rate detected at 2400 bps.
48	'CARRIER 4800'	Data rate detected at 4800 bps.
49	'CARRIER 7200'	Data rate detected at 7200 bps.
50	'CARRIER 9600'	Data rate detected at 9600 bps.
51	'CARRIER 12000'	Data rate detected at 12000 bps.
67	'COMPRESSION: V.42bis'	Data call connected with V.42bis compression enabled.
69	'COMPRESSION: NONE'	Data call connected with no data compression.
126	'SBDRING'	SBD ring alert received, indicating presence of a mobile-terminated SBD message at gateway.
127	'HARDWARE FAILURE: <subsys>,<error>'	Issued at initialization in case of a hardware failure.
as verbose	'+DR: V42B NONE'	Data call connected with no data compression.
as verbose	'+DR: V42B TD'	Data call connected with V.42bis compression enabled on transmit direction.
as verbose	'+DR: V42B RD'	Data call connected with V.42bis compression enabled on receive direction.
as verbose	'+DR: V42B'	Data call connected with V.42bis compression enabled on both transmit and receive direction.

**Table 8: GSM 7.07 Result Codes**

<b>Numeric (V0)</b>	<b>Verbose (V1)</b>	<b>Description</b>
as verbose	'+CR: ASYNC'	Asynchronous transparent data connection
as verbose	'+CR: REL ASYNC'	Asynchronous nontransparent data
as verbose	'+CME ERROR: <error>	Command not accepted
as verbose	'+CREG: <stat>[,<lac>,<ci>]	Registration indication status (unsolicited if enabled)
as verbose	'+CRING: ASYNC'	Asynchronous transparent data call indication
as verbose	'+CRING: REL ASYNC'	Asynchronous nontransparent data
as verbose	'+CRING: VOICE'	Voice call connection

**Table 9: GSM 7.05 Result Codes**

<b>Numeric (V0)</b>	<b>Verbose (V1)</b>	<b>Description</b>
as verbose	'+CMTI: <mem>,<index>'	SMS-DELIVER message indication (unsolicited if enabled).
as verbose	'+CMT: <alpha>],<length><CR><LF><pdu>' (PDU mode)	SMS-DELIVER message indication (unsolicited if enabled).
as verbose	'+CDS:<length><CR><LF><pdu>' (PDU mode)	SMS-STATUS-REPORT message indication (unsolicited if enabled).
as verbose	'+CMS ERROR: <error>	SMS command failed.

**Table 10: Iridium Specific Result Codes**

<b>Numeric (V0)</b>	<b>Verbose (V1)</b>	<b>Description</b>
as verbose	'READY'	Ready to receive SBD binary message data from DTE.
as verbose	'+AREG:<event>,<reg error>'	Auto-registration event report.
as verbose	'+CIEV:<sig><value>'	Indicator event report.
as verbose	'+ADJANT:<deployed>'	User antenna adjustment is required.

## APPENDIX E: INFORMATIVE EXAMPLES

The examples below are presented in two different formats. The format used in each example has no significance. A single format will be used in a future revision of this document.

### E.1 UNIT IDENTIFICATION

When beginning to build a communication link, a general DTE application controlling the A3LA-RM should confirm the type of Iridium device to which it is connected.

**Table 11: Unit Identification**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
AT+CGMI		Get manufacturer name
	Iridium OK	
AT+CGMM		Get model number
	<model ID> OK	
AT+CGMR		Get revision
	Call processor version: <revision> DSP version: <revision> ... OK	
AT+CGSN		Get IMEI
	3000010000000000 OK	

## E.2 SETTING THE DEFAULT CONFIGURATION

The DTE sets the A3LA-RM's default configuration to no flow control, SBD automatic notifications enabled.

**Table 12: Default Configuration**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
AT&K0		Disable RTS/CTS flow control
	OK	
AT+SBDMTA=1		Enable SBD ring indications
	OK	
AT&W0		Store the configuration as profile 0
	OK	
AT&Y0		Select profile 0 as the power-up default
	OK	

## E.3 POWER-ON TO SENDING AN SBD MESSAGE

The DTE will power up the A3LA-RM, wait for the A3LA-RM to acquire the network, and send a 70-byte message.

**Table 13: Sending an SBD Message**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
		Wait for DSR to become asserted
AT+CIER=1,0,1		Enable service indication reporting (note that this can be stored in the default configuration)
	OK	
	+CIEV: 1, 1	Wait for the A3LA-RM to acquire the network
AT+SBDWB=70		

**Table 13: Sending an SBD Message**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
	READY	Transfer message to A3LA-RM
<binary transfer>		
	0	
AT+SBDIX		Perform SBD session
	+SBDIX: 0, 23, 0, -1, 0, 0	
AT+SBDDO		Clear the MO message buffer
	OK	

## E.4 SBD AUTOMATIC NOTIFICATION REGISTRATION

The DTE verifies its registration state, performs a registration in order to be able to receive automatic notifications, and enables automatic notification indications.

**Table 14: SBD Automatic Notification Registration**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
AT+SBDREG?		Query the A3LA-RM registration status
	+SBDREG: 0	A3LA-RM is detached, i.e., unregistered
AT+SBDREG		Tell the A3LA-RM to register for automatic notifications
	+SBDREG: 2,0	A3LA-RM is now registered
AT+SBDREG?		Query the A3LA-RM registration status
	+SBDREG: 2	A3LA-RM is registered
AT+SBDMTA=1		Enable SBD ring indications from A3LA-RM to DTE

**Table 14: SBD Automatic Notification Registration**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
	OK	

## E.5 SBD AUTOMATIC NOTIFICATION MESSAGE RECEPTION

The DTE verifies its registration state. Upon receiving automatic notification, the DTE initiates an SBD session to receive an MT message.

**Table 15: SBD Automatic Notification Message Reception**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
AT+SBDREG?		Query the A3LA-RM registration status
	+SBDREG: 2	A3LA-RM is registered
	...	Vendor application sends an MT message to the GSS
	+SBDRING	A3LA-RM indicates an incoming message. The RI line also toggles.
AT+SBDIXA		DTE initiates an SBD session in answer to the automatic notification
	+SBDIXA:0,23,1,237,90,2	A3LA-RM informs DTE that a 90-byte message was successfully received with MTMSN 237, and that two further MT messages are queued at the GSS
AT+SBDRB		DTE retrieves the received message from the A3LA-RM
	<binary transfer>	

## E.6 SBD AUTOMATIC NOTIFICATION AUTOMATIC REGISTRATION

The DTE verifies its registration state and enables automatic registration using the “Ask” mode.

**Table 16: SBD Automatic Notification Automatic Registration**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
AT+SBDREG?		Query the A3LA-RM registration status
	+SBDREG: 2	A3LA-RM is registered
AT+SBDAREG=2		DTE sets the automatic registration to “Ask” mode
	OK	
	...	A3LA-RM is moved
	+AREG: 0, 0	A3LA-RM notifies DTE that it needs to register
AT+SBDREG		DTE instructs the A3LA-RM to register
	+SBDREG: 2, 0	Registration is successful

## E.7 ORIGINATING A DATA CALL

An example of how to make a data call is given below:

**Table 17: Originating a Data Call**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
AT+CBST=6,0,1		Asynchronous modem 4800 bps and IRLP
	OK	
AT+CR=1		Enable reporting
	OK	
ATD1234567890		Dial remote modem
	OK	

**Table 17: Originating a Data Call**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
+CR: REL ASYNC		Call connected at DTE rate of 9600
	CONNECT ASYNC 9600	

## E.8 ANSWERING A DATA CALL

The A3LA-RM is capable of accepting mobile-terminated data calls. The following is a sequence of commands that can be used to establish the connection.

**Table 18: Answering a Data Call**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
	RING	Indicates arrival of call request
ATA		Manually answer the call
	CONNECT 9600	Call connected at DTE rate of 9600
ATS0=2		To automatically answer a call, register 0 should be set to a non-zero value
	RING	Indicates arrival of call request
	CONNECT	Call connected at DTE rate of 9600

## E.9 DISCONNECTING A DATA CALL

**Table 19: Disconnecting a Data Call**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
AT+CBST=6,0,1		Asynchronous modem 4800 bps and IRLP
	OK	
AT+CR=1		Enable reporting

**Table 19: Disconnecting a Data Call**

To A3LA-RM (from DTE)	To DTE (from A3LA-RM)	Description
	OK	
ATD1234567890		Dial remote modem
	OK	
+CR: REL ASYNC		Call connected at DTE rate of 9600
	CONNECT ASYNC 9600	
...	...	Data transfer
<+++>		Send escape sequence
	OK	
ATH0		Hang up call
	OK	

## E.10 COORDINATION OF +CLCC AND +CPAS RESPONSES

In order to determine the call state of the A3LA-RM, the +CLCC and +CPAS commands may be used. The following table demonstrates how the output of the two commands, as well as the Extended Ring Message, can be combined to provide a more detailed definition of the call state than any one of the results provides by itself.

**Table 20: Coordination of +CLCC and +CPAS Responses**

Call State	+CLCC Response	+CPAS Response	Extended Ring Message
Idle	+CLCC: 006	+CPAS: 000 or 003	n/a
Handset dialing – Voice	+CLCC: 002	+CPAS: 000 or 003	n/a
ATD dialing – Voice	command aborts call	command aborts call	n/a

**Table 20: Coordination of +CLCC and +CPAS Responses**

Call State	+CLCC Response	+CPAS Response	Extended Ring Message
ATD dialing – Data	command aborts call	command aborts call	n/a
Alerting after ATD dialing – Voice	command aborts call	command aborts call	n/a
Alerting after ATD dialing – Data	command aborts call	command aborts call	n/a
Ringing – Voice	+CLCC: 004	+CPAS: 003	CRING: VOICE
Ringing – Data	+CLCC: 004	+CPAS: 003	CRING: DATA
In call – Voice	+CLCC: 000	+CPAS: 000 or 003	n/a
In call – Data	+CLCC: 000	+CPAS: 004	n/a
On hold – Voice	+CLCC: 001	+CPAS: 000 or 003	n/a
Call waiting – Voice	2 or more call states, one of which is 004, e.g., +CLCC: 000,004	+CPAS: 000 or 003	n/a

## APPENDIX F: POWER CONSUMPTION


This section provides the electrical power profile of the A3LA-RM. It does not describe every situation; however, it does offer a starting point to continue your own development design. The actual usage profile can vary for a number of reasons, including manufacturing variation from unit-to-unit. Optimize your setup to attain the lowest possible power consumption. Some of the setup parameters to be carefully observed include:

1. Have a clear view of the sky for the antenna—poor visibility of the sky is when a clear line-of-sight is not available between the A3LA-RM and the satellites.
2. Keep the antenna's VSWR low—the higher the antenna VSWR, the higher the current consumed by the A3LA-RM.
3. Keep the antenna cables' loss to less than 3 dB—the higher the antenna cable loss, the higher the current consumed by the A3LA-RM.
4. Keep the power cable between the A3LA-RM and the power source as short as possible.
5. Use both power input pins on the multi-interface connector.


Power consumption of the A3LA-RM can be divided into five distinct operating segments: (1) standby, (2) data-switch/RUDICS call, (3) SBD transmission, (4) SMS transmission, and (5) audio call. Typical current drawn and power consumption for these cases are shown in plots below.

The A3LA-RM is designed to accept input power at two different voltage ranges—either from 4.0 V to 5.5 V or from 6.0 V to 32 V. A different internal DC-DC converter is used for each range. In each figure below, electrical profile for both ranges are displayed in separate curves.


The A3LA-RM can be connected to a DPL handset through an HRC-24-8R data kit to make voice calls. The DPL handset requires 12 V, which is supplied by the A3LA-RM through pin 2 of the multi-interface connector. When the DPL handset is on with the backlight turned on, the DPL handset current drawn is about 350 mA at 12 V or about 500 mA at 5 V. Therefore, when a DPL handset is connected to an A3LA-RM, you must account for the added current drawn.




**Figure 8: Average Current Drawn During Standby**




**Figure 9: Average Power Consumption During Standby**




**Figure 10: Average Current Drawn During Standby with DPL Handset**




**Figure 11: Average Power Consumption During Standby with DPL Handset**




**Figure 12: Average Current Drawn During a Data Switch Call**




**Figure 13: Average Power Consumption During a Data Switch Call**




**Figure 14: Average Current Drawn During an SBD Transmission**




**Figure 15: Average Power Consumption During an SBD Transmission**




**Figure 16: Average Current Drawn During an SMS Transmission**



**Figure 17: Average Power Consumption During an SMS Transmission**




**Figure 18: Average Current Drawn During a Voice Call Using DPL Handset**



**Figure 19: Average Power Consumption During a Voice Call Using DPL Handset**

## APPENDIX G: THE IRIDIUM NETWORK

The Iridium satellite network is owned and operated by Iridium Communications Inc. It is constructed as a constellation of 66 satellites in low-earth orbit (LEO), terrestrial gateways, and Iridium subscriber units (ISUs). An ISU can either be an Iridium satellite phone or various types of modems. The satellites are placed in an approximate polar orbit at an altitude of 780 km. There are 6 polar planes populated with 11 satellites per orbit constituting the 66-satellite constellation. The near polar orbits of the Iridium constellation provide truly real-time and global coverage from pole-to-pole.



**Figure 20: Iridium Network Major Components**

The Iridium network is designed to operate in the band of 1616.0 to 1626.5 MHz, although the exact frequencies used depend on the local regulating authorities and issued licenses in any particular region. Each satellite projects 48 beams on the surface of earth, which may be viewed as providing coverage cells on the ground similar to terrestrial systems. Each beam is approximately 600 km in diameter. The 66-satellite constellation has the potential to support a total of 3,168 spot beams; however, as the satellite orbits converge at the poles, overlapping

beams are shut down. The satellite footprint is approximately 4,700 km in diameter. Under each footprint, a satellite is power-limited to approximately 1,100 simultaneous circuits.


The Iridium network uses a time division duplex (TDD) method and transmits and receives in an allotted time window within the frame structure. Since the system is TDD, the ISUs transmit and receive in the same frequency band. The access technology is a frequency division multiple access/time division multiple access (FDMA/TDMA) method whereby an ISU is assigned a channel composed of a frequency and time slot in any particular beam. Channel assignments may be changed across cell/beam boundaries and are controlled by the satellite. The system provides an average link margin of 12 dB.

Although there are multiple gateways, a user is registered to a single gateway. The gateways perform call connection setup and administrative duties such as billing and resource management. The satellite constellation provides connectivity between users, from a user to the Iridium system gateway, and between gateways. Within the Iridium network architecture, the satellites are cross-linked, which allows ISU-to-ISU communication independent of gateway intervention once the call connection is established.

There are currently two commercial Iridium gateways located in Arizona, United States; and Fucino, Italy. The U.S. government owns and operates an Iridium gateway located in Hawaii, United States. Each gateway generates and controls all user information pertaining to its registered users, such as user identity, geolocation, and billing items. The gateway also provides connectivity from the Iridium system to the terrestrial-based networks such as the Public Switched Telephone Network (PSTN).

## G.1 IRIDIUM NETWORK DATA CAPABILITIES

For data communications, the Iridium network supports five different modes of operation, as shown in **Figure 21**: dial-up data service, direct internet connection, SBD, SMS, and RUDICS.




**Figure 21: Iridium Network Data Capabilities**

## G.2 DIAL-UP DATA SERVICE

Dial-up data service provides connectivity through the Iridium satellite network to another Iridium modem, to the public switched telephone network (PSTN), to the Defense Switch Network (DSN), to a remote LAN (e.g., a corporate network), or to an internet service provider (ISP) at a nominal data rate of 2.4 kilobits per second (kbps). The connection time involving user authentication and handshaking (or modem training) can range from 15 to 30 seconds. For an Iridium-to-Iridium call, dial-up data service offers an additional option known as Data After Voice (DAV). Similar to a voice call, a DAV call is routed directly from one Iridium modem to another Iridium modem without going through the gateway.

Many desktop and laptop computers are equipped with either an internal or external modem to perform dial-up data applications across the landline telephone network (PSTN). On these computers, terminal emulator software or a dial-up networking connection can be configured


to a specific modem with a phone number to dial, user identification, and password. The modem can then be used to call another computer, a remote Local area network (LAN), or an Internet service provider (ISP), as shown in **Figure 22**. The handshaking and protocols are established between the modems independent of the landline.



**Figure 22: PSTN Dial-up Connectivity**

The Iridium dial-up data service, as shown in **Figure 23**, functions in much the same way as the PSTN dial-up connectivity. From the perspective of a computer, the Iridium modem is just another external modem. The only difference is that the dialed telephone number must conform to the international dialing pattern used by Iridium. When a data call is placed, the Iridium modem actually dials and initiates a connection with the Iridium gateway through the Iridium satellite constellation. Because the Iridium modem is requesting to establish a data connection, the switch at the gateway routes the call through another modem. The modem at the Iridium gateway then dials into and connects to another modem at the other end. **Figure 23** illustrates how an Iridium dial-up data service call is routed. The handshaking and protocols established between the modems are independent of the Iridium network.

For those ISU-to-ISU dial-up calls where data transmission delay is critical, such as the application of TCP/IP protocol, DAV should be considered in the design. This option eliminates the Iridium gateway once authentication and registration is completed, allowing ISU-to-ISU communication without the gateway in the loop.



*Figure 23: Iridium Dial-up Data Service*

### G.3 DIRECT INTERNET CONNECTION

The Iridium Direct Internet service allows users to connect to the internet via the Iridium gateway without having to sign up with an internet service provider. This service utilizes a dedicated Apollo Server at the Iridium gateway, which provides high-speed connectivity to the internet and optimizes server-to-Iridium modem communications. The dial-up networking setup is similar to the dial-up networking setup for a landline telephone. The only difference is that the dialed telephone number is an international number provided by Iridium. **Figure 23** illustrates how an Iridium internet call is routed.

Direct Internet service can be enhanced using Windows-based emulated point-to-point protocol (PPP) called the Apollo Emulator. With the use of the Apollo Emulator software instead of Microsoft Windows® dial-up networking, Direct Internet service can reduce connection time and improve data throughput. In addition, the Apollo Emulator offers a feature called Smart Connect™, which manages airtime by seamlessly connecting and disconnecting a user through the Iridium system. Airtime charges accumulate only while the call is connected. Improved

effective data throughput is achieved with user-transparent data compression. The channel rate is still 2.4 kbps. However, 10 kbps effective throughput can be achieved depending on content (graphics and images result in lower effective throughput).

## G.4 SHORT BURST DATA

SBD is a simple and efficient bidirectional transport capability used to transfer messages with sizes ranging from zero (a mailbox check) to 1960 bytes. SBD takes advantage of signals within the existing air interface but without using the dedicated traffic channels. As a result, small amounts of data can be transferred more efficiently than those associated with circuit-switched data calls. Messages that originate from an Iridium modem can be delivered to a variety of destinations. Commonly, data are delivered across terrestrial communications networks (NIPRNet and internet) to servers and applications that process data from one or multiple fielded Iridium modems. SBD service also supports the transfer of messages to Iridium modems, where messages may originate from terrestrial sources. Delivery methods and options are initially configured when the Iridium modem is first purchased and may be easily modified via webpages at a later time.

## G.5 SHORT MESSAGING SERVICE

SMS is a mechanism to deliver short data messages over the Iridium satellite network to the NIPRNet/internet. Iridium SMS incorporates a subset of the GSM SMS features. Each SMS message can be up to 160 text characters (7-bit coded) in length. The text characters are based on a 7-bit alphabet, which is encoded and transmitted as 8-bit data, hence the 140 octet (byte) maximum message size.

SMS is a store-and-forward method of transmitting messages to and from an Iridium modem. The short message from the modem is stored in a central Short Message Service Center (SMSC), which then forwards it to the destination. If the recipient is not available, the SMSC attempts to deliver the SMS message until it is delivered or the validity period expires. SMS supports a limited confirmation of message delivery. The sender of the short message can request to receive a return message notifying them whether the short message has been delivered. With this option, the originator gets a confirmation that the message was delivered to the SMSC.

Unlike standard GSM, the Iridium SMS can only acknowledge that the message was delivered to the SMSC and not the end destination.

SMS messages can be sent and received simultaneously while a voice call is in progress. This is possible because SMS messages travel over and above the radio channel using the signaling path, whereas the voice call uses a dedicated “traffic” radio channel for the duration of the call.

## G.6 RUDICS

Router-based unrestricted digital internetworking connectivity solution (RUDICS) is an enhanced gateway termination and origination capability for circuit-switched data calls across the Iridium satellite network. When an Iridium modem places a call to the RUDICS Server located at the Iridium gateway, the RUDICS server connects the call to a predefined IP address, allowing an end-to-end IP connection between the host application and the Iridium modem. There are three key benefits of using RUDICS over the conventional PSTN circuit-switched data connectivity or mobile-to-mobile data solutions: (1) elimination of analog modem training time, (2) increased call connection quality, reliability, and maximized throughput, and (3) protocol independence.

## G.7 IRIDIUM GEOLOCATION

The Iridium network makes calculations of the geographical location (geolocation) of an ISU each time a call is placed. The technique employed to determine the geolocation of an ISU is based on measurements of the ISU and satellite propagation delay and Doppler frequency shift. These measurements are used to estimate cosines of spherical angles that identify the ISU’s location relative to the satellite by the gateway.

The Iridium network can locate an ISU to within 10 km only about 78% of the time. The so-called error ellipse can have a large eccentricity with the major axis oriented in the azimuth dimension and the minor axis oriented in the radial dimension. The position of the ISU in the radial dimension relative to the satellite can almost always be determined to within 10 km with just one measurement. Errors in the azimuth dimension relative to the satellite are largest along the satellite’s ground path and tend to increase with distance from the satellite.

Geolocation errors in the east-west dimension, therefore, are sometimes more than 100 times greater than in the north-south dimension.

## APPENDIX H: STANDARDS COMPLIANCE

The A3LA-RM comprises an Iridium 9523 L-band transceiver board. The 9523 is a regulatory approved daughter module transceiver that can be fitted within an enclosed host system. The 9523 is designed to comply with the standards for Radio Emissions Compliance, Electromagnetic Compatibility, and AC Safety in the United States, European Union, and Canada, assuming an antenna with a gain of ~3 dBi and adequate shielding.

**FCC Compliance:** The 9523 is certified under FCC CFR47 Parts 2, 15, and 25 as FCC ID: Q639523. Operation is subject to the condition that this device does not cause harmful interference. Any changes or modifications, including the use of a nonstandard antenna not expressly approved by the party responsible for compliance, could void the user's authority to operate the equipment.

**CE Compliance:** The 9523, when marked with the CE symbol, complies with the European Community Council Directive for R&TTE, 99/5/EC, provided that the integrator/user adheres to the instructions detailed in this LBT Interface Specification. This product complies with applicable ETSI standards. Compliance with the requirements of ETSI EN 301 441 V1.1.1 requires the use of a shielded digital data interface cable.

**Industry Canada:** The 9523 is compliant with Industry Canada RSS-170 Issue 2 for RF Exposure.

**Important:** Output power listed is conducted. Peak power is 5.16 W and mean power is 0.48 W. The antenna gain, including cable loss, must not exceed 3 dBi. To comply with FCC RF exposure experiments, a minimum separation of 20 cm is required between the antenna and all persons. Additional testing and certification are required for applications that combine the 9523 with another radio element or are intended for use within 20 cm of a person.

# APPENDIX I: MIL-STD-810G CERTIFICATION



## NATIONAL TECHNICAL SYSTEMS

---

### CERTIFICATE OF COMPLIANCE

March 25, 2013

**Customer:** NAL Research Corporation      **Purchase Order #:** PO3736  
 9300 West Courthouse Road              **NTS Project #:** PR018792  
 Manassas, VA 20110

**Test Items:**

Item #	Qty	Description	Part #	Serial #
1	1	Satellite Modem	A3LA-RG-MIL	Q00F7S
2	1	Satellite Modem	A3LA-RG-MIL	Q00F43
3	-	Satellite Modem	A3LA-R-MIL	N/A
4	-	Satellite Modem	A3LA-RM-MIL	N/A
5	-	Satellite Modem	A3LA-RGS-MIL	N/A

**Test Specifications:**

NAL Research Corporation Purchase Order No. PO3736 dated 10/16/12  
MIL-STD-810G

Test Performed	Test Standard/Method	Test Date(s)
Altitude Operation	MIL-STD-810G Method 500.5 Procedure II	1/24/13
High Temperature Storage	MIL-STD-810G Method 501.5 Procedure I	1/22/13
High Temperature Operation	MIL-STD-810G Method 501.5 Procedure II	1/23/13
Low Temperature Storage	MIL-STD-810G Method 502.5 Procedure I	1/22/13
Low Temperature Operation	MIL-STD-810G Method 502.5 Procedure II	1/24/13
Blowing Rain	MIL-STD-810G Method 506.5 Procedure I	2/15/13
Humidity	MIL-STD-810G Method 507.5 Procedure II	1/25/13-2/4/13
Salt Fog	MIL-STD-810G Method 509.5	3/4/13-3/7/13
Sand and Dust	MIL-STD-810G Method 510.4 Procedure I and II	1/28/13-2/7/13
Non Operational Shock	MIL-STD-810G Method 516.6 Procedure I	3/4/13

National Technical Systems (NTS) certifies that the above referenced item(s) has/have been tested in accordance with the above Requirements set forth in the above referenced documents.




---

**David Potpink**  
NTS Quality Representative




---

**Mark Betts**  
NTS Project Manager

---

36 Gilbert Street South • Tinton Falls, New Jersey 07701  
 (732) 936-0800 • Fax (732) 936-0700  
 www.nts.com

**Figure 24: Mil-STD-810G Certification**

Document Number: 451-93156-002D

168 of 172

## APPENDIX J: EXPORT COMPLIANCE

The A3LA-RM is controlled by the export laws and regulations of the United States of America (USA). It is the policy of NAL Research to fully comply with all U.S. export and economic sanction laws and regulations. The export of NAL Research products, services, hardware, software and technology must be made only in accordance with the laws, regulations and licensing requirements of the U.S. government. NAL Research customers must also comply with these laws and regulations. Failure to comply can result in the imposition of fines and penalties, the loss of export privileges, and termination of your contractual agreements with NAL Research.

The export and re-export of NAL Research products and services are subject to regulation by the Export Administration Regulations (15 CFR 730-744), as administered by the U.S. Department of Commerce, Bureau of Industry and Security (BIS).

See: <https://www.bis.doc.gov/index.php/regulations/export-administration-regulations-ear> for further information on BIS and the Export Administration Regulations (EAR). Additional export restrictions are administered by the U.S. Department of the Treasury's Office of Foreign Asset Controls (OFAC). See: <http://www.ustreas.gov/ofac> for further information on OFAC and its requirements.

## APPENDIX K: DESIGN SPECIFICATIONS

### K.1 MECHANICAL SPECIFICATIONS

Dimensions:	102 mm x 61 mm x 24 mm (4.0" x 2.43" x 0.95")
Weight:	198 g (7.0 ounces)
Multi-interface connector:	25-pin male D-sub
Iridium antenna:	TNC female connector
SIM chip reader:	Located beneath a cover plate on top of the A3LA-RM
Status display:	Power, Iridium, and Status
Cooling:	Convection
Enclosure:	Aluminum/EMI shielding

### K.2 RF SPECIFICATIONS

Operating frequency:	1616.0 to 1626.5 MHz
Duplexing method:	TDD
Multiplexing method:	TDMA/FDMA
Link margin:	12 dB average
Average power during a transmit slot (max):	7 W
Average power during a frame (typical):	0.6 W
Receiver sensitivity at 50Ω (typical):	-118 dBm

### K.3 ELECTRICAL SPECIFICATIONS

Main input voltage range:	+4.0 V to +5.5 V or +6.0 V to +32.0 V
Average standby current:	~130 mA @ 6.0 VDC (with +6.0 V to +32.0 V setup)
Average data call current:	~400 mA @ 6.0 VDC (peak of 2 A)

**Note:** The power requirements apply to DC power measured at the A3LA-RM multi-interface connector input. The average data call current may vary depending on the field of view between the modem antenna and the Iridium satellite.

## K.4 ENVIRONMENTAL SPECIFICATIONS

Operating temperature range: .....–30°C to +70°C (–22°F to +158°F)

Operating humidity range:.....< 75% RH

Storage temperature range: .....–40°C to +85°C (–40°F to +185°F)

Storage humidity range: .....< 93% RH

## K.5 DATA I/O SPECIFICATIONS

Dial-up data/RUDICS: .....2.4 kbps (average)

Direct Internet: .....2.4 kbps (average)

Short-burst data:.....1960 bytes for mobile-originated and 1890  
bytes for mobile-terminated

Short messaging:.....160 characters (maximum)

Hardware interface: .....RS-232

Software interface: .....Standard AT commands

## K.6 RELATED HARDWARE

Antennas: .....SYN7391 series, SAF2040 series, SAF5340  
series, SAF5350 series

Data kit/connector:.....HRC-24-7R

<https://www.nalresearch.com/product/hrc-24-7r/>

Power adapters:.....LA-3098, LA-7021

Audio handset:.....DPLS0401-X

# APPENDIX L: MECHANICAL DRAWING




Figure 25: A3LA-RM Mechanical Drawing